

Таблица 5. Списък на основни параметри за ЕМФ-Е123 and PV123a

Индуктивен напреженов трансформатор тип ЕМФ-Е123 и PV123a	
Номинално първично напрежение U_{pr}	$\leq 115/\sqrt{3}$ kV
На-високо напрежение на оборудването U_{in}	≤ 126 kV
Номинална честота f	50 Hz
Номинално изоляционно ниво	AC 230 kV / LI 550 kV
Изпитание на издръжливост на статично нагояване P_0	3600 N
Външна изолация – път на утечка на изолятора l_1	3150 mm +4495 mm
Степен на защита срещу механично въздействие на	IK07
Степен на защита на вторичната клемна кутия	IP55
Номинален фактор на напрежение U_r / време	$\leq 1.9/8$ h
Номинално вторично напрежение U_{sr}	≤ 115 V
Клас на точност на измервателните и защитни намотки	0.1; 0.2; 0.5; 1; 3; 3P; 6P
Ном. мощност на измервателните и защитни намотки S_r	≤ 1000 VA
Номинално напрежение на остатъчната намотка $U_{sr} (da-dh)$	≤ 115 V
Клас на точност на остатъчната намотка	0.5; 1; 3; 3P; 6P
Номинална мощност на остатъчната намотка S_r	≤ 450 VA
Обща мощност S_{Σ}	4000 VA

Таблица 6. Списък на основни параметри за ЕМФ-Е145 and PV145a

Индуктивен напреженов трансформатор тип ЕМФ-Е145 и PV145a	
Номинално първично напрежение U_{pr}	$\leq 145/\sqrt{3}$ kV
На-високо напрежение на оборудването U_{in}	≤ 145 kV
Номинална честота f	50 Hz
Номинално изоляционно ниво	AC 275 kV / LI 650 kV
Изпитание на издръжливост на статично нагояване P_0	3600 N
Външна изолация – път на утечка на изолятора l_1	3150 mm +4495 mm
Степен на защита срещу механично въздействие на	IK07
Степен на защита на вторичната клемна кутия	IP55
Номинален фактор на напрежение U_r / време	$\leq 1.9/8$ h
Номинално вторично напрежение U_{sr}	≤ 115 V
Клас на точност на измервателните и защитни намотки	0.1; 0.2; 0.5; 1; 3; 3P; 6P
Ном. мощност на измервателните и защитни намотки S_r	≤ 1000 VA
Номинално напрежение на остатъчната намотка $U_{sr} (da-dh)$	≤ 115 V
Клас на точност на остатъчната намотка	0.5; 1; 3; 3P; 6P
Номинална мощност на остатъчната намотка S_r	≤ 450 VA
Обща мощност S_{Σ}	4000 VA


ЗАБЕЛЕЖКИ:

- 1) Приложимо за композитни и за порцеланови изолятори
- 2) Не е приложимо за порцеланови изолятори

(

(

Author: Jan Tomaszewski M. Sc. Eng.



INSTYTUT ENERGETYKI
Certification Department
PRODUCT EVALUATION REPORT

No. DZC/111c/E/2015-2
revision 4
2016.12.30

Product name and symbol: Inductive voltage transformers
types EMF-E072, EMF-E084, EMF-E123, EMF-E145,
PV123a and PV145a.

Supplier:
ABB Sp. z o. o.
1 Żegańska Str.
04-713 Warsaw
Poland

Manufacturer:
ABB AB Power Products
Valhallavägen 2
771 31 Ludvika
Sweden
ABB Sp. z o. o., Branch Office in Przasnysz
59 Leszno Str.
06-300 Przasnysz
Poland

Contents

- 1. Introduction.....3
- 2. List of used documents.....4
- 3. Competences of the testing laboratories.....7
- 4. Test objects.....7
- 5. Test results.....8
- 5.1. Type tests.....9
 - 5.1.1. Temperature-rise test.....9
 - 5.1.2. Impulse voltage test on primary terminals.....9
 - 5.1.3. Wet test.....10
 - 5.1.4. RIV test.....10
 - 5.1.5. Test for accuracy.....11
 - 5.1.6. Verification of the degree of protection by enclosures.....11
 - 5.1.7. Short-circuit withstand capability test.....11
- 5.2. Routine tests.....12
- 5.3. Special tests.....12
 - 5.3.1. Chopped impulse voltage withstand test on primary terminals.....12
 - 5.3.2. Measurement of capacitance and dielectric dissipation factor.....13
 - 5.3.3. Transmitted overvoltage test.....13
 - 5.3.4. Mechanical test.....13
- 5.4. Additional tests.....13
 - 5.4.1. Capacitor discharge test.....13
- 6. Summary.....14

Appendix: Type test, special test and routine test reports (pages not numbered), Manufacturers statements

Non-conformities observed:

None found

General evaluation result:

Positive
On the basis of analysis made, herewith I apply for granting the certificate of conformity to the inductive voltage transformers, type EMF-E072, EMF-E084, EMF-E123 and EMF-E145, PV123a and PV145a, according to the Summary.

Jan Tomaszewski
Full name
signature
2016.12.30
date

Warsaw, November 2016

153

1. Introduction

This evaluation report concerning inductive voltage transformers series, type EMF-E... and PV...a was made during the certification processes carried out by the Certification Department of Instytut Energetyki upon the application of ABB Sp. z o.o., Poland (issuance of the certificate for EMF-E... - no. DZC/111c/E/2015, extension of EMF-E... certificate - no. DZC/131c/E/2016 and DZC/187c/E/2016, issuance of a certificate for PV...a - no. DZC/189c/E/2016).

The EMF-E... and PV...a voltage transformers are designed to energize measurement and protection circuits in outdoor electrical grids with highest voltages up to 72.5 kV (EMF-E072), 84 kV (EMF-E084), 126 kV (EMF-E123 and PV123a) and 145 kV (EMF-E145 and PV145a) and frequency 50 Hz.

According to the documents delivered by the Manufacturer (statement about no changes in the design and test reports), new type names of the same voltage transformer construction are introduced. The PV123a and PV145a units are identical to respectively EMF-E123 and EMF-E145 from technical point of view. The former are assembled only in ABB Sp. z o.o., Branch Office in Przasnysz, Poland, while the latter, as well as EMF-E072 and EMF-E084, both in ABB Sp. z o.o., Branch Office in Przasnysz, Poland and in ABB AB Power Products in Ludvika, Sweden. Correctness of drying, assembling and oil filling has been confirmed by appropriate tests which are described in chapter 5 of this report.

The in question inductive voltage transformers have a single-pole construction. The active part of the VT is located in the tank which serves also as the base of the device and which is supposed to be grounded. The VT can have up to six secondary windings which are led out to the terminal box. The grounded tank is separated from the high voltage terminal with a porcelain or composite insulator. The internal insulation of the device is designed as paper-oil.

The construction of housing and the insulator types of EMF-E072 and EMF-E084 is identical. The same applies to EMF-E123, PV123a, EMF-E145 and PV145a.

The type and special tests of the in question voltage transformers have been performed in Instytut Energetyki (Warsaw), Instytut Elektrotechniki (Warsaw) and in the manufacturer's factory facilities in Ludvika, Sweden (under supervision of SATS inspector). The routine tests have been performed in the manufacturer's laboratory in Przasnysz, Poland under supervision of IEN representatives.

The parameters of the whole series of VTs were assigned on the basis of performed tests. The test results confirming the devices' properties are given in test reports listed in cl. 2 of this study. The results were compared with the requirements of following standards:

- IEC 61869-1:2007 (PN-EN 61869-1:2009)
Instrument transformers - Part 1: General requirements
- IEC 61869-3:2011 (PN-EN 61869-3:2011)
Instrument transformers - Part 3: Additional requirements for inductive voltage transformers.

- IEC 60529:1989+AMD1:1999+AMD2:2013 CSV (PN-EN 60529:2003/A2:2014-07)
Degrees of protection provided by enclosures (IP Code)
- IEC 62262:2002 (PN-EN 62262:2003)
Degrees of protection provided by enclosures for electrical equipment against external mechanical impacts (IK code)

ABB AB Power Products holds certificates confirming the quality of their management systems in the range of following standards:

- SS-EN ISO 9001:2008 (certificate no. SE004225-1)
- SS-EN ISO 14001:2004 (certificate no. SE004224-1)
- OHSAS 18001:2007 (certificate no. SE004226-1)

issued by Bureau Veritas Certification Sverige AB.
ABB Sp. z o.o. with all its Branch Offices holds a certificate confirming the quality of their management systems in the range of following standards:

- ISO 9001:2015 (certificate no. 01 100 1541800)
- ISO 14001:2015 (certificate no. 01 104 1541809)
- PN-N 18001:2004 (certificate no. 0198 113 00113)

issued by TÜV Rheinland Cert GmbH.

2. List of used documents

Following reports delivered by the Supplier were used to perform the evaluation process of the in question voltage transformers:

- D1. Report No. EWP/52/E/2015-1; Temperature-rise test; EMF-E084, SN. 1HSE8851777; High Current Laboratory (EWP) of Instytut Energetyki; October 2015
- D2. Report No. EWP/52/E/2015-3; Temperature-rise test; EMF-E145, SN. 1HSE8851772; High Current Laboratory (EWP) of Instytut Energetyki; September 2015
- D3. Report No. EWP/52/E/2015-4; Temperature-rise test; EMF-E145, SN. 1HSE8851773; High Current Laboratory (EWP) of Instytut Energetyki; September 2015
- D4. Report No. EWN/134/E/15; Impulse voltage withstand test on primary terminal and chopped impulse voltage withstand test on primary terminal; EMF-E145, SN. 1HSE8851773; High Voltage Laboratory (EWN) of Instytut Energetyki; November 2015
- D5. Report No. EWN/109/E/15-1; Impulse voltage withstand test on primary terminal, chopped impulse voltage withstand test on primary terminal, transmitted overvoltage test and capacitor discharge test; EMF-E123, SN. 1HSE8851774; High Voltage Laboratory (EWN) of Instytut Energetyki; October 2015
- D6. Report No. EWN/109/E/15-3; Impulse voltage withstand test on primary terminal, chopped impulse voltage withstand test on primary terminal and transmitted overvoltage test; EMF-E084, SN. 1HSE8851777; High Voltage Laboratory (EWN) of Instytut Energetyki; October 2015

- D23. Routine test report before type tests; EMF-E145, SN. 1HSE8851773; Laboratory of ABB Sp. z o.o., Przasnysz, October 2015
- D24. Routine test report before type tests; EMF-E123, SN. 1HSE8851774; Laboratory of ABB Sp. z o.o., Przasnysz, October 2015
- D25. Routine test report before type tests; EMF-E072, SN. 1HSE8851776; Laboratory of ABB Sp. z o.o., Przasnysz, October 2015
- D26. Routine test report before type tests; EMF-E084, SN. 1HSE8851777; Laboratory of ABB Sp. z o.o., Przasnysz, October 2015
- D27. Routine test report before type tests; EMF-E084, SN. 1HSE8851778; Laboratory of ABB Sp. z o.o., Przasnysz, October 2015
- D28. Routine test report after lightning impulse test; EMF-E145, SN. 1HSE8851773; Laboratory of ABB Sp. z o.o., Przasnysz, November 2015
- D29. Routine test report after lightning impulse test; EMF-E123, SN. 1HSE8851774; Laboratory of ABB Sp. z o.o., Przasnysz, November 2015
- D30. Routine test report after lightning impulse test; EMF-E084, SN. 1HSE8851777; Laboratory of ABB Sp. z o.o., Przasnysz, November 2015
- D31. Routine test report after lightning impulse test; EMF-E072, SN. 1HSE8851776; Laboratory of ABB Sp. z o.o., Przasnysz, November 2015
- D32. Routine test report after short-circuit withstand capability test; EMF-E145, SN. 1HSE8851773; Laboratory of ABB Sp. z o.o., Przasnysz, November 2015
- D33. Routine test report after short-circuit withstand capability test; EMF-E084, SN. 1HSE8851778; Laboratory of ABB Sp. z o.o., Przasnysz, November 2015
- D34. Report No. EUR/44/E/16-1; Mechanical test; EMF-E072, SN. 2GGKV1190628; Distribution Equipment Laboratory (EUR) of Instytut Energetyki; November 2016
- D35. Report No. EUR/44/E/16-2; Mechanical test; EMF-E072, SN. 2GGKV1190629; Distribution Equipment Laboratory (EUR) of Instytut Energetyki; November 2016
- D36. Report No. EUR/44/E/16-3; Mechanical test; EMF-E072, SN. 2GGKV1190649; Distribution Equipment Laboratory (EUR) of Instytut Energetyki; November 2016
- D37. Report No. EUR/44/E/16-4; Mechanical test; EMF-E145, SN. 2GGKV1190669; Distribution Equipment Laboratory (EUR) of Instytut Energetyki; December 2016
- D38. Report No. EUR/44/E/16-5; Mechanical test; EMF-E145, SN. 2GGKV1190668; Distribution Equipment Laboratory (EUR) of Instytut Energetyki; December 2016
- D39. Report No. EUR/44/E/16-6; Mechanical test; EMF-E145, SN. 2GGKV1190670; Distribution Equipment Laboratory (EUR) of Instytut Energetyki; December 2016

- D7. Report No. EWN/109/E/15-2; Impulse voltage withstand test on primary terminal, chopped impulse voltage withstand test on primary terminal and transmitted overvoltage test; EMF-E072, SN. 1HSE8851776, High Voltage Laboratory (EWN) of Instytut Energetyki; October 2015
- D8. Report no. EWN/45/E/16; Impulse and chopped impulse voltage withstand test on primary terminal; PV145a, SN. 2GKPO15V1188086, High Voltage Laboratory (EWN) of Instytut Energetyki; May 2016
- D9. Report no. EWN/106/E/16-1; Impulse and chopped impulse voltage withstand test on primary terminal; EMF-E072, SN. 2GGKV1190628; High Voltage Laboratory (EWN) of Instytut Energetyki; December 2016
- D10. Report no. EWN/106/E/16-2; Impulse and chopped impulse voltage withstand test on primary terminal; PV145a, SN. 2GGKV1190678; High Voltage Laboratory (EWN) of Instytut Energetyki; December 2016
- D11. Report No. R Q 15-78; Wet test; EMF-E145, SN. 1HSE8851772; Laboratory of ABB AB Power Products, Ludvika, Sweden, October 2015
- D12. Report No. R Q 15-79; Wet test; EMF-E145, SN. 1HSE8851773; Laboratory of ABB AB Power Products, Ludvika, Sweden, October 2015
- D13. Report No. R Q 15-74; Wet test; EMF-E084, SN. 1HSE8851777; Laboratory of ABB AB Power Products, Ludvika, Sweden, September 2015
- D14. Report No. R Q 15-75; Wet test; EMF-E084, SN. 1HSE8851778; Laboratory of ABB AB Power Products, Ludvika, Sweden, September 2015
- D15. Report No. EWN/109/E/15-4; Transmitted overvoltage test and RIV test; EMF-E145, SN. 1HSE8851772; High Voltage Laboratory (EWN) of Instytut Energetyki; November 2015
- D16. Report No. EWN/109/E/15-5; RIV test; EMF-E145, SN. 1HSE8851772; High Voltage Laboratory (EWN) of Instytut Energetyki; November 2015
- D17. Report No. 8604/NZL/NBR/15; Verification of the degree of protection; Terminal box 2GHV042554; Switchgear Testing Laboratory of Instytut Elektrotechniki; April 2015
- D18. Report No. 8606/NZL/NBR/15; Verification of the degree of protection; Terminal box 2GHV042542; Switchgear Testing Laboratory of Instytut Elektrotechniki; April 2015
- D19. Report No. EWP/40/E/2015; Verification of the degree of protection against mechanical impact; EMF-E072, SN. 2GKPO15V1188091, EMF-E072, SN. 2GKPO15V1188038, EMF-E145, SN. 1HSE8849700, EMF-E145, SN. 2GKPO13K1486306, EMF-E072, SN. 2GKPO15V1188093, EMF-E072, SN. 2GKPO15V1188092; High Current Laboratory (EWP) of Instytut Energetyki; October 2015
- D20. Report No. 8734/NZL/NBR/15; Short-circuit withstand capability test; EMF-E145, SN. 1HSE8851773; Switchgear Testing Laboratory of Instytut Elektrotechniki; November 2015
- D21. Report No. 8733/NZL/NBR/15; Short-circuit withstand capability test; EMF-E084, SN. 1HSE8851778; Switchgear Testing Laboratory of Instytut Elektrotechniki; November 2015
- D22. Routine test report before type tests; EMF-E145, SN. 1HSE8851772; Laboratory of ABB Sp. z o.o., Przasnysz, October 2015

3. Competences of the testing laboratories

The type tests, the special tests and the routine tests of the EMF-E voltage transformers were performed in following laboratories:

- Laboratorium Wielkopądowe (High Current Laboratory), a unit of Instytut Energetyki (Institute of Power Engineering) in Warsaw, holding the PCA Accreditation Certificate of the Research Laboratory PCA No. AB 323
- Laboratorium Wysokich Napięć (High Voltage Laboratory), a unit of Instytut Energetyki (Institute of Power Engineering) in Warsaw, holding the PCA Accreditation Certificate of the Research Laboratory PCA No AB 272.
- ABB AB Power Products Manufacturing Plant Laboratory in Ludvika - tests performed under supervision of the representatives of S.A.T.S.
- ABB Sp. z o.o. Manufacturing Plant Laboratory in Przasnysz - OUM Warsaw (District Office of Measures) Verification Unit, routine tests performed under supervision of the representatives of Instytut Energetyki.
- Laboratorium Badawcze Aparatury Rozdzielczej (Switchgear Testing Laboratory), a unit of Instytut Elektrotechniki (Electrotechnical Institute) in Warsaw, holding the PCA Accreditation Certificate of the Research Laboratory PCA No AB 074.

- Laboratorium Urządzeń Rozdzielczych (Distribution Equipment Laboratory), a unit of Instytut Energetyki (Institute of Power Engineering) in Warsaw, holding the PCA Accreditation Certificate of the Research Laboratory PCA No AB 324.

4. Test objects

The manufacturer prepared thirteen VT prototypes to be subjected to the type tests and special tests. The basic parameters of the prototypes are listed in the Table 1.

Table 1. Basic parameters of the test prototypes

No.	Type	Primary voltage U_p	Voltage factor F_v	Total thermal burden	Rated insulation level ($U_m/AC/UL$)	Insulator, creepage distance	Serial number
1.	EMF-E145	145/ $\sqrt{3}$ kV	1.9xUn / 8h	4000 VA	145/275/650 kV	composite, 3150 mm	1HSE8851772
2.	EMF-E145	145/ $\sqrt{3}$ kV	1.9xUn / 8h	4000 VA	145/275/650 kV	porcelain, 3075 mm	1HSE8851773
3.	EMF-E123	115/ $\sqrt{3}$ kV	1.9xUn / 8h	4000 VA	123/230/650 kV	composite, 3150 mm	1HSE8851774
4.	EMF-E072	66/ $\sqrt{3}$ kV	1.9xUn / 8h	2000 VA	72.5/140/325 kV	composite, 1813 mm	1HSE8851776
5.	EMF-E084	77/ $\sqrt{3}$ kV	1.9xUn / 8h	2000 VA	84/150/380 kV	porcelain, 1813 mm	1HSE8851777
6.	EMF-E084	77/ $\sqrt{3}$ kV	1.9xUn / 8h	2000 VA	84/150/380 kV	composite, 1813 mm	1HSE8851778
7.	EMF-E145	138/ $\sqrt{3}$ kV	1.9xUn / 8h	4000 VA	145/275/650 kV	composite, 4300 mm	1HSE8849700
8.	EMF-E145	145/ $\sqrt{3}$ kV	1.9xUn / 8h	4000 VA	145/275/650 kV	porcelain, 4250 mm	2GKP013K1486306
9.	EMF-E072	66/ $\sqrt{3}$ kV	1.9xUn / 8h	750 VA	72.5/140/325 kV	composite, 3150 mm	2GKP015V1188092
10.	EMF-E072	66/ $\sqrt{3}$ kV	1.9xUn / 8h	750 VA	72.5/140/325 kV	porcelain, 3075 mm	2GKP015V1188093
11.	EMF-E072	66/ $\sqrt{3}$ kV	1.9xUn / 8h	750 VA	72.5/140/325 kV	composite, 1813 mm	2GKP015V1188038
12.	EMF-E072	66/ $\sqrt{3}$ kV	1.9xUn / 8h	750 VA	72.5/140/325 kV	porcelain, 1813 mm	2GKP015V1188091
13.	PV145a	145/ $\sqrt{3}$ kV	1.9xUn / 8h	4000 VA	145/275/650 kV	composite, 3150 mm	2GPKV1190628
14.	EMF-E072	66/ $\sqrt{3}$ kV	1.9xUn / 8h	2600 VA	72.5/140/325 kV	porcelain, 1813 mm	2GPKV1190678
15.	EMF-E084	77/ $\sqrt{3}$ kV	1.9xUn / 30s	2000 VA	84/150/380 kV	composite, 3150 mm	2GPKV1190629
16.	EMF-E072	66/ $\sqrt{3}$ kV	1.9xUn / 8h	2600 VA	72.5/140/325 kV	composite, 3150 mm	2GPKV1190649
17.	EMF-E072	66/ $\sqrt{3}$ kV	1.9xUn / 8h	2600 VA	72.5/140/325 kV	porcelain, 4495 mm	2GPKV1190669
18.	EMF-E145	145/ $\sqrt{3}$ kV	1.9xUn / 8h	2600 VA	145/275/650 kV	porcelain, 4495 mm	2GPKV1190668
19.	EMF-E145	145/ $\sqrt{3}$ kV	1.9xUn / 8h	2600 VA	145/275/650 kV	composite, 4495 mm	2GPKV1190670
20.	EMF-E145	145/ $\sqrt{3}$ kV	1.9xUn / 8h	2600 VA	145/275/650 kV	composite, 4495 mm	2GPKV1190670

The detailed drawings and parameters of the prototypes can be found in attached test reports.

To verify if the processes of drying, assembling and oil filling are performed correctly in the factory of ABB Sp. z o.o. in Przasnysz, an additional lightning impulse and chopped lightning impulse tests, as well as routine tests before and after the impulse tests was performed on PV145a, EMF-E072 and EMF-E084 units. It was agreed to be a most valuable source of information in this case. The construction of insulation system of PV123a, as well as its production process is identical to PV145a, thus it is deemed that the additional impulse test performed on a voltage transformer with higher rated voltage value is sufficient. This test also confirms the correctness of assembling process of EMF-E072, EMF-E084, EMF-E123 and EMF-E145 carried out by ABB Sp. z o.o., Branch Office in Przasnysz. EMF-E123 and EMF-E145 are identical to the PV123a and PV145a units.

5. Test results

The tests were performed on chosen EMF-E... and PV... a voltage transformer constructions. The achieved results are valid for the whole series of devices.

test. As the lightning impulse voltage test concerns the internal insulation only, this amount of test objects was agreed to be sufficient.

Three additional voltage transformers – Prototype 13 (PV145a), Prototype 14 (EMF-E072) and Prototype 15 (EMF-E084) were additionally tested with lightning impulse to verify if the processes of drying, assembling and oil filling are performed correctly in the factory of ABB Sp. z o.o. in Przasnysz. Testing of PV123a was deemed unnecessary because of same construction as PV145a while the rated voltage value is lower, thus less exposed. This test also confirms the correctness of assembling process of EMF-E123 and EMF-E145 carried out by ABB Sp. z o.o., Branch Office in Przasnysz, which are identical to the PV123a and PV145a units.

The test results and the detailed test procedure are given respectively in reports D4 – D7. The additional reports concerning the VTs assembled in ABB Sp. z o.o. are given in reports D8 – D10. The assigned parameters can be found in the Summary.

5.1.3. Wet test – IEC 61869-3:2011, cl. 7.2.4

The wet tests were performed in Laboratory of ABB AB Power Products in Ludvika, Sweden under supervision of SATS inspectors. Four voltage transformers – Prototype 1 (EMF-E145), Prototype 2 (EMF-E145), Prototype 5 (EMF-E084) and Prototype 6 (EMF-E084) – were subjected to this test because of the higher test voltage values than respectively EMF-E123 and EMF-E072, while the dimensions remain the same. For each rated voltage porcelain and composite insulator with the shortest creepage distance were tested. The PV123a and PV145a units are identical to respectively EMF-E123 and EMF-E145, thus this test was deemed unnecessary for them. As the wet test concerns the external insulation only, this amount of test objects was agreed to be sufficient.

The test results and the detailed test procedure are given in reports D11 – D14. The assigned parameters can be found in the Summary.

5.1.4. RIV test – IEC 61869-3:2011, cl. 7.2.5.1

The RIV test was performed in High Voltage Laboratory (EWN) of Instytut Energetyki in Warsaw. This test applies to instrument transformer having $U_m \geq 123$ kV only. Two voltage transformers – Prototype 1 (EMF-E145) and Prototype 2 (EMF-E145) – were chosen for this test because of the higher test voltage values than EMF-E123, while the dimensions remain the same. The PV123a and PV145a units are identical to respectively EMF-E123 and EMF-E145, thus this test was deemed unnecessary for them. The test results and the detailed test procedure are given in reports D15 and D16.

5.1. Type tests

5.1.1. Temperature-rise test – IEC 61869-3:2011, cl. 7.2.2

The temperature-rise test was performed in High Current Laboratory (EWP) of Instytut Energetyki in Warsaw. The test was performed on three voltage transformers – Prototype 1 (EMF-E145), Prototype 2 (EMF-E145) and Prototype 5 (EMF-E084). Testing of EMF-E072 and EMF-E123 was deemed unnecessary because of same construction as respectively EMF-E084 and EMF-E145 VTs while the rated voltage values are lower, thus less heat-exposed. The PV123a and PV145a units are identical to respectively EMF-E123 and EMF-E145, thus this test was deemed unnecessary for them.

The test procedure was divided in three steps, as indicated in IEC 61869-3:2011, cl. 7.2.2:

- The first step was performed with 120% of rated voltage, rated burden connected to each secondary winding, the residual voltage winding unloaded.
- The second step was performed with 190% of rated voltage, rated burden connected to each secondary winding, the residual voltage winding loaded with the burden corresponding to its rated thermal limiting output.

The third step should be performed with 100% of rated voltage, the residual voltage winding unloaded, each of secondary windings connected to the burden corresponding to its rated thermal output, one at a time. The Manufacturer however decided to load all of the secondary windings with burden corresponding to their rated thermal limiting output in order to achieve more extreme testing conditions.

The results obtained for the EMF-E084 voltage transformer and the detailed test procedure are given in report D1. The Prototype 5 was successfully submitted to all three testing stages. The results obtained for the EMF-E145 voltage transformers and the detailed test procedure are given in reports D2 and D3. The Prototype 1 was subjected to the stage 1 and 2 of the test, while the Prototype 2 was subjected to the stage 3.

The performed tests confirmed the values of voltage factor and total thermal limiting output declared by the Manufacturer. The rated output during the tests was lower than Manufacturer declares. However, on the basis of recalculating the burden and the voltage of the third step, it was possible to verify that the voltage transformers will also comply with the requirements with the maximum rated output. The assigned parameters can be found in the Summary.

5.1.2. Impulse voltage test on primary terminals – IEC 61869-3:2011, cl. 7.2.3

The impulse voltage tests were performed in High Voltage Laboratory (EWN) of Instytut Energetyki in Warsaw. Four voltage transformers, one of each rated voltage – Prototype 2 (EMF-E145), Prototype 3 (EMF-E123), Prototype 5 (EMF-E084) and Prototype 4 (EMF-E072) – were subjected to this

157

All tests for accuracy were performed in laboratory of ABB Sp. z o. o. in Przasnysz under the supervision of representatives of Instytut Energetyki. All of the prototypes were subjected to this test before the type tests and after the lightning impulse test and short-circuit withstand capability test, as a verification of the test result. The measured errors comply with the requirements of the IEC 61869-3:2011 standard, cl. 5.6. The test results are given in reports D22 – D33. The additional reports concerning the VTs assembled in ABB Sp. z o.o. are attached to the impulse voltage test reports and are given in reports D8 – D10. Testing of PV123a, EMF-E123 and EMF-E145 manufactured by ABB Sp. z o.o., Branch Office in Przasnysz is deemed unnecessary because their active parts are identical to the active part of PV145a. Since the verification of all accuracy classes in combination with different rated outputs wouldn't be economically and technically justified, the obtained results were recalculated to describe all possible combinations. The assigned parameters can be found in the Summary.

5.1.6. Verification of the degree of protection by enclosures – IEC 61869-3:2011, cl. 7.2.7

The tests to confirm the declared IP55 protection degree were performed in Switchgear Testing Laboratory of Instytut Energetyki in Warsaw. Two types of terminal boxes – 2GHV042554 and 2GHV042542 – were tested. The test results and the detailed test procedure are given in reports D17 and D18.

The tests to confirm the declared IK07 protection degree against mechanical impact were performed in High Current Laboratory of Instytut Energetyki in Warsaw. Six voltage transformers – Prototype 7 (EMF-E145), Prototype 8 (EMF-E145), Prototype 9 (EMF-E072), Prototype 10 (EMF-E072), Prototype 11 (EMF-E072), Prototype 12 (EMF-E072) – were tested. The PV123a and PV145a units are identical to respectively EMF-E123 and EMF-E145, thus this test was deemed unnecessary for them. The test results and the detailed test procedure are given in report D19. The assigned parameters can be found in the Summary.

5.1.7. Short-circuit withstand capability test – IEC 61869-3:2011, cl. 7.2.301

These tests were performed in Switchgear Testing Laboratory of Instytut Energetyki in Warsaw. Two voltage transformers – Prototype 2 (EMF-E145) and Prototype 6 (EMF-E084) – were subjected to this test because of the higher nominal voltage values than respectively EMF-E123 and EMF-E072. The PV123a and PV145a units are identical to respectively EMF-E123 and EMF-E145, thus this test was deemed unnecessary for them. The test results and the detailed test procedure are given in reports D20 and D21.

5.2. Routine tests

The routine tests were performed on all prototypes before the type tests. They were also repeated for the prototypes which were subjected to the lightning impulse tests and short-circuit withstand capability tests in order to confirm that these tests didn't cause any internal damage in the tested VTs. The routine tests were performed in the laboratory of ABB Sp. z o. o. in Przasnysz under supervision of representatives of Instytut Energetyki. Following tests were performed within the routine tests:

- Power-frequency voltage withstand test on primary terminals – IEC 61869-3:2011, cl. 7.3.1

The power-frequency voltage withstand test on primary terminals after the short-circuit withstand capability test was performed with test voltage reduced to 90% of the nominal power-frequency withstand voltage value. After the lightning impulse voltage test, the power-frequency voltage was reduced to 80% of the nominal power-frequency withstand voltage value.

- Partial discharge measurement – IEC 61869-3:2011, cl. 7.3.2

The partial discharge level measured before and after type tests didn't exceed 0.6 pC in any of the tested VTs for both $1.2 \times U_m$ and $1.2 \times U_m / \sqrt{3}$, while the permissible levels are respectively 10 and 5 pC. The measured values were approximately equal to the measured background noise level.

- Power-frequency voltage withstand test on secondary terminals – IEC 61869-3:2011, cl. 7.3.4

The power-frequency voltage withstand test on secondary terminals was performed with test voltage 3 kV both before and after type tests.

- Test for accuracy – IEC 61869-3:2011, cl. 7.3.5

See cl. 5.1.5.

- Verification of markings – IEC 61869-3:2011, cl. 7.3.6

- Enclosure tightness test at ambient temperature – IEC 61869-3:2011, cl. 7.3.7

The test results are given in reports D22 – D33. The additional reports concerning the VTs assembled in ABB Sp. z o.o. are attached to the impulse voltage test reports and are given in reports D8 – D10.

5.3. Special tests

5.3.1. Chopped impulse voltage withstand test on primary terminals – IEC 61869-3:2011, cl. 7.4.1

These tests were performed in High Voltage Laboratory (EWN) of Instytut Energetyki in Warsaw. The tests were performed during the impulse voltage tests on primary terminals on all of the VTs tested with full wave impulse voltage. The peak value of the test voltage was equal 115% of the full wave peak

times in 2-minutes intervals. The test objective was to check the influence of discharging the capacitor on the winding temperature and overall performance of the voltage transformer. The results and the detailed test procedure is given in report D5.

All tests gave positive results.

6. Summary

On the basis of analyzed test results, it is concluded as follows:

- The EMF-E... and PV... a voltage transformer series meet the requirements of the IEC-61869-3:2011 standard in the range of type and routine tests. They have also passed several special tests and an additional test on request of the Manufacturer.
- The performed tests are sufficient for a complete evaluation of the voltage transformers, type EMF-E... and PV...a
- The Manufacturers to be mentioned in the certificates are:
 - ABB AB Power Products, Valhallavagen 2, 771 31 Ludvika, Sweden for products EMF-E072, EMF-E084, EMF-E123 and EMF-E145
 - ABB Sp. z o.o. Branch Office in Przasnysz, 59 Leszno Str., 06-300 Przasnysz, Poland for products EMF-E072, EMF-E084, EMF-E123, EMF-E145, PV123a and PV145a
- The list of all tests with the tested voltage transformers is given in Table 2.
- The list of parameters assigned to the voltage transformers based on analyzed test results is given in Table 3. (EMF-E072), Table 4. (EMF-E084), Table 5. (EMF-E123 and PV123a) and Table 6. (EMF-E145 and PV145a).

value. The test results and the detailed test procedure are given in reports D4 – D7. The additional reports concerning the VTs assembled in ABB Sp. z o.o. are given in D8 – D10.

5.3.2. Measurement of capacitance and dielectric dissipation factor – IEC 61869-3:2011, cl. 7.4.3

This test is treated by the Manufacturer as a routine test and was performed with other routine tests in laboratory of ABB Sp. z o.o. in Przasnysz under supervision of representatives of Instytut Energetyki. The test voltage values were 10 kV, $U_{1p}/\sqrt{3}$ and $U_{1m}/\sqrt{3}$. The capacitance and the dielectric dissipation factor did not change significantly with the increase of the voltage or after type tests. The test results are given in reports D22 – D33. The additional reports concerning the VTs assembled in ABB Sp. z o.o. are attached to the impulse voltage test reports and are given in reports D8 – D10.

5.3.3. Transmitted overvoltage test – IEC 61869-3:2011, cl. 7.4.4

These tests were performed in High Voltage Laboratory (EWN) of Instytut Energetyki in Warsaw. Four voltage transformers, one of each rated voltage – Prototype 1 (EMF-E145), Prototype 3 (EMF-E123), Prototype 5 (EMF-E084) and Prototype 4 (EMF-E072) – were subjected this test. The PV123a and PV145a units are identical to respectively EMF-E123 and EMF-E145, thus this test was deemed unnecessary for them. The test results and the detailed test procedure are given respectively in reports D15, D5, D6 and D7.

5.3.4. Mechanical test – IEC 61869-3:2011, cl. 7.4.5

The tests were performed in Distribution Equipment Laboratory (EUR) of Instytut Energetyki in Warsaw. Six voltage transformers – Prototype 14 (EMF-E072), Prototype 17 (EMF-E072), Prototype 18 (EMF-E072), Prototype 19 (EMF-E145), Prototype 20 (EMF-E145) and Prototype 21 (EMF-E145) – were subjected to this test to cover the whole range of porcelain and composite insulators and primary terminals used for EMF-E... type voltage transformers. The PV123a and PV145a units are identical to respectively EMF-E123 and EMF-E145, thus this test was deemed unnecessary for them. The static test load was 3600 N.

The test results and the detailed test procedure are given in reports D34 – D39.

5.4. Additional tests

5.4.1. Capacitor discharge test

The capacitor discharge test was performed in High Voltage Laboratory (EWN) of Instytut Energetyki in Warsaw. Prototype 3 (EMF-E123) was subjected to this test. The test procedure was provided by ABB. A 6 µF capacitor has been connected in parallel to the tested VT and discharged ten

Table 2. List of tests and tested voltage transformers

Item	Test	Requirements TYPE TESTS	Report numbers	Prototypes
1	Temperature-rise test	IEC 61869-3:2011, cl. 7.2.2	EWP/52/E/2015-1 EWP/52/E/2015-3 EWP/52/E/2015-4	1, 2, 5
2	Impulse voltage test on primary terminals	IEC 61869-3:2011, cl. 7.2.3	EWN/134/E/15 EWN/109/E/15-1 EWN/109/E/15-2 EWN/109/E/15-3 EWN/45/E/16 EWN/106/E/16-1 EWN/106/E/16-2	2, 3, 4, 5, 13, 14, 15
3	Wet test	IEC 61869-3:2011, cl. 7.2.4	R Q 15-74 R Q 15-75 R Q 15-78 R Q 15-79	1, 2, 5, 6
4	RIV test	IEC 61869-3:2011, cl. 7.2.5.1	EWN/109/E/15-4 EWN/109/E/15-5	1, 2
5	Tests for accuracy	IEC 61869-3:2011, cl. 7.2.6	Routine test reports from the Laboratory in ABB Sp. z o.o.	1, 2, 3, 4, 5, 6, 13, 14, 15
6	Verification of the degree of protection by enclosures	IEC 61869-3:2011, cl. 7.2.7	8604/NZL/NBR/15 8606/NZL/NBR/15 EWP/40/E/2015	7, 8, 9, 10, 11, 12 Terminal boxes: 2GHV042554 2GHV042542
7	Short-circuit withstand capability test	IEC 61869-3:2011, cl. 7.2.301	8734/NZL/NBR/15 8733/NZL/NBR/15	2, 6
SPECIAL TESTS				
8	Chopped impulse voltage withstand test on primary terminals	IEC 61869-3:2011, cl. 7.4.1	EWN/134/E/15 EWN/109/E/15-1 EWN/109/E/15-2 EWN/109/E/15-3 EWN/45/E/16 EWN/106/E/16-1 EWN/106/E/16-2	2, 3, 4, 5, 13, 14, 15
9	Measurement of capacitance and dielectric dissipation factor	IEC 61869-3:2011, cl. 7.4.3	Routine test reports from the Laboratory in ABB Sp. z o.o.	1, 2, 3, 4, 5, 6, 13, 14, 15
10	Transmitted overvoltage test	IEC 61869-3:2011, cl. 7.4.4	EWN/109/E/15-1 EWN/109/E/15-2 EWN/109/E/15-3 EWN/109/E/15-4	1, 3, 4, 5
11	Mechanical tests	IEC 61869-3:2011, cl. 7.4.5	EUR/44/E/16-1 EUR/44/E/16-2 EUR/44/E/16-3 EUR/44/E/16-4 EUR/44/E/16-5	14, 17, 18, 19, 20, 21
ADDITIONAL TESTS				
12	Capacitor discharge test	ABB	EWN/109/E/15-1	3

Table 3. List of evidenced parameters for EMF-E072

Inductive voltage transformer type EMF-E072	
Rated primary voltage U_p	$\leq 69/43$ kV
Highest voltage for equipment U_m	≤ 72.5 kV
Rated frequency f_N	50 Hz
Rated insulation level	AC 140 kV / LI 325 kV
Static withstand test load F_N	3600 N
External insulation – creepage distance of insulators ¹⁾	1813 mm + 3150 mm
Degree of protection against mechanical impact of enclosure ²⁾	IK07
Degree of protection of secondary terminals enclosure	IP55
Rated voltage factor F_V / time	$\leq 1.9/8$ h
Rated secondary voltage U_s	≤ 115 V
Accuracy class of measurements and protection windings	0.1; 0.2; 0.5; 1; 3; 3P; 6P
Rated output of measurement and protection windings S_r	≤ 500 VA
Rated voltage of residual voltage winding $U_{s(dn-dm)}$	≤ 115 V
Accuracy class of residual voltage winding	0.5; 1; 3; 3P; 6P
Rated output of residual voltage winding S_r	≤ 150 VA
Total thermal limiting output S_{Tth}	2000 VA

Table 4. List of evidenced parameters for EMF-E084

Inductive voltage transformer type EMF-E084	
Rated primary voltage U_p	$\leq 77/43$ kV
Highest voltage for equipment U_m	≤ 84 kV
Rated frequency f_N	50 Hz
Rated insulation level	AC 150 kV / LI 380 kV
Static withstand test load F_N	3600 N
External insulation – creepage distance of insulators ¹⁾	1813 mm + 3150 mm
Degree of protection against mechanical impact of enclosure ²⁾	IK07
Degree of protection of secondary terminals enclosure	IP55
Rated voltage factor F_V / time	$\leq 1.9/8$ h
Rated secondary voltage U_s	≤ 115 V
Accuracy class of measurements and protection windings	0.1; 0.2; 0.5; 1; 3; 3P; 6P
Rated output of measurement and protection windings S_r	≤ 500 VA
Rated voltage of residual voltage winding $U_{s(dn-dm)}$	≤ 115 V
Accuracy class of residual voltage winding	0.5; 1; 3; 3P; 6P
Rated output of residual voltage winding S_r	≤ 150 VA
Total thermal limiting output S_{Tth}	2000 VA

Table 5. List of evidenced parameters for EMF-E123 and PV123a

Inductive voltage transformer type EMF-E123 and PV123a	
Rated primary voltage U_p	$\leq 115/43$ kV
Highest voltage for equipment U_m	≤ 126 kV
Rated frequency f_R	50 Hz
Rated insulation level	AC 230 kV / LI 550 kV
Static withstand test load F_R	3600 N
External insulation – creepage distance of insulators ¹⁾	3150 mm + 4495 mm
Degree of protection against mechanical impact of enclosure ²⁾	IK07
Degree of protection of secondary terminals enclosure	IP55
Rated voltage factor F_T / time	$\leq 1.9 / 8$ h
Rated secondary voltage U_S	≤ 115 V
Accuracy class of measurements and protection windings	0.1; 0.2; 0.5; 1; 3; 3P; 6P
Rated output of measurement and protection windings S_r	≤ 1000 VA
Rated voltage of residual voltage winding $U_{S_r(d=0)}$	≤ 115 V
Accuracy class of residual voltage winding	0.5; 1; 3; 3P; 6P
Rated output of residual voltage winding S_r	≤ 450 VA
Total thermal limiting output $S_T^{\#}$	4000 VA

Table 6. List of evidenced parameters for EMF-E145 and PV145a

Inductive voltage transformer type EMF-E145 and PV145a	
Rated primary voltage U_p	$\leq 145/43$ kV
Highest voltage for equipment U_m	≤ 145 kV
Rated frequency f_R	50 Hz
Rated insulation level	AC 275 kV / LI 650 kV
Static withstand test load F_R	3600 N
External insulation – creepage distance of insulators ¹⁾	3150 mm + 4495 mm
Degree of protection against mechanical impact of enclosure ²⁾	IK07
Degree of protection of secondary terminals enclosure	IP55
Rated voltage factor F_T / time	$\leq 1.9 / 8$ h
Rated secondary voltage U_S	≤ 115 V
Accuracy class of measurements and protection windings	0.1; 0.2; 0.5; 1; 3; 3P; 6P
Rated output of measurement and protection windings S_r	≤ 1000 VA
Rated voltage of residual voltage winding $U_{S_r(d=0)}$	≤ 115 V
Accuracy class of residual voltage winding	0.5; 1; 3; 3P; 6P
Rated output of residual voltage winding S_r	≤ 450 VA
Total thermal limiting output $S_T^{\#}$	4000 VA

REMARKS:

- 1) Applies to composite and porcelain insulators
- 2) Does not apply to porcelain insulators

164

(

(

ABB AB Power Transformers

Report - Report

Form-From: PPR/QT Datum-Date: 2015-10-15 R Q 15-78 Side-Page: 1 (4)

Revision-Number: 1

Order-number-Ref.No.: E90000012-10

Customer-Order-Number: E90000012-10

Proj/Alt:

Actual serial-no. of pages: 4

Actual diagram/block-no. of supplement, pages:

Revision-Status: Undröjning, leveret Undröjning-Analys Utvärdering, experim. under- sökning* Test, experim. mental Utvärdering-Interim Report Slutrapport-Final report

Power-frequency withstand voltage test, wet condition, on one voltage transformer of type EMF-E145 with composite insulator

Powering/understanding analyzed:
 Test investigation finished: 2015-10-13

Summary/Title-Summary

1 TEST OBJECT

One voltage transformer of type EMF-E145 with composite insulator

Serial No: 1HSE 8851772

Dimension drawing: 2GHV025729 Rev. A

Rating plate: 1HSE 22040-PCA Rev. A

2 STANDARDS

IEC 61869-1, IEC 61869-3 and IEC 60060-1, 2010 cl. 4.4.1 and 4.4.2

3 PERFORMED TEST

Power-frequency voltage withstand test in wet condition. Test voltage applied on primary winding. The secondary terminals 1n, 2n, 3n and dn were connected to ground.

Applied test voltage (kV)	Corrected test voltage (kV)	Frequency test voltage Hz	Duration of test	Result
273	275	240	25s	Withstood

Precipitation rate: 1.5 / 1.5 mm/min, (horizontal / vertical component)

Resistivity of water: 97 Ohmm

Conductivity of water: 103 µS/cm

4. ATMOSPHERIC CONDITIONS AND CORRECTION FACTOR

Pressure: 1011 mb

Temperature: 22.2 °C

Correction factor: k = 0.993

5 RESULT

The voltage transformer passed the wet power-frequency voltage withstand test

5 INSPECTOR

Mr. Lars - Olof Gunnarsson, SATS Certification

SATS Certification
Lars-Olof Gunnarsson

Inspector

Sign: *Lars-Olof Gunnarsson* Date: 2015-10-16

About SATS Certification: SATS Certification (www.sats-certification.org) is an certification body accredited in accordance with ISO/IEC 17065 (2012) by Norwegian Accreditation. SATS (Scandinavian Association for Testing Electrical Power Equipment) is a member of the Short-Circuit Testing Liaison (STL)

This document is hereby approved and certifies that the object specified above have successfully passed the test herein reported, thereby verifying guaranteed data.

Approved/Authoriser-Key word: 1 år 2 år mer än 3 år

ABB

ABB AB Power Transformers

R Q 15-78 Page 2

1 TEST OBJECT

One voltage transformer of type EMF-E145 with composite insulator

Serial No: 1HSE 8851772

Dimension drawing: 2GHV025729 Rev. A

Rating plate: 1HSE 22040-PCA Rev. A

See page 3

See page 4

2 STANDARDS

IEC 61869-1, IEC 61869-3 and IEC 60060-1, 2010 cl. 4.4.1 and 4.4.2

3 PERFORMED TEST

Power-frequency voltage withstand test in wet condition. Test voltage applied on primary winding. The secondary terminals 1n, 2n, 3n and dn were connected to ground.

Applied test voltage (kV)	Corrected test voltage (kV)	Frequency test voltage Hz	Duration of test	Result
273	275	240	25s	Withstood

Precipitation rate: 1.5 / 1.5 mm/min, (horizontal / vertical component)

Resistivity of water: 97 Ohmm

Conductivity of water: 103 µS/cm

4. ATMOSPHERIC CONDITIONS AND CORRECTION FACTOR

Pressure: 1011 mb

Temperature: 22.2 °C

Correction factor: k = 0.993

5 RESULT

The voltage transformer passed the wet power-frequency voltage withstand test

6 INSTRUMENTS

Equipment	Reg. No.	Last calibration
Voltage divider	IM301908	10-2014
Voltmeter	M296144	04-2015

Fluke 187

ABB

163

ABB AB Power Transformers

Rapport - Report

Reg. 2751 Side Page 1 (4)

Order number/Ref.No. E90000012-20
 Declared order number E90000012-20
 PU/MI
 Anvil level/Iden.-No. of pages 4
 Anvil tilleggsIden.-No. of supplies pages

From/From 2015-10-15
 PPR/QT
 Utredning, teknisk undersökning-Analysa
 Proving, separim, under-öbning-Test, experimantal Investigation
 Rapport-Interim Report
 Slutrapport-Final report

Power-frequency withstand voltage test, wet condition, on one voltage transformer of type EMF-E145 with porcelain insulator

Powering/underöbning evaluated Test Investigation finished 2015-10-13

1 TEST OBJECT

One voltage transformer of type EMF-E145 with porcelain insulator

Serial No: 1HSE 8851773
 Dimension drawing: 2GHV025799 Rev. A
 Rating plate: 1HSE 22040-PCB Rev. A

2 STANDARDS

IEC 61869-1, IEC 61869-3 and IEC 60060-1, 2010 cl. 4.4.1 and 4.4.2

3 PERFORMED TEST

Power-frequency voltage withstand test in wet condition. Test voltage applied on primary winding. The secondary terminals 1n, 2n, 3n and dn were connected to ground.

Applied test voltage (kV)	Corrected test voltage (kV)	Frequency Hz	Duration of test	Result
273	275	240	25s	Withstood

4 RESULT

Power-frequency voltage withstand test in wet condition. 275kV*, 240Hz, 25s.
 *) Voltage is corrected for atmospheric conditions

The voltage transformer passed the wet power-frequency voltage withstand test

5 INSPECTOR

Mr. Lars - Olof Gunnarsson, SATS Certification

SATS Certification
 Lars-Olof Gunnarsson
 Inspector
 Sign: *[Signature]* Date: 2015-10-13

About SATS Certification: SATS Certification (www.sats-certification.org) is an certification body accredited in accordance with ISO/IEC 17065 (2012) by Norwegian Accreditation. SATS (Scandinavian Association for Testing Electrical Power Equipment) is a member of the Short-Circuit Testing Liaison (STL)

This document is hereby approved and certifies that the object specified above have successfully passed the test herein reported, thereby verifying guaranteed data.

Uppdrags-/Användarstycke
 Övrigt märkt
 1 år
 2 år
 mer än 2 år

ABB AB Power Transformers

R Q 15-79 Page 2

1 TEST OBJECT

One voltage transformer of type EMF-E145 with porcelain insulator

Serial No: 1HSE 8851773
 Dimension drawing: 2GHV025799 Rev. A
 Rating plate: 1HSE 22040-PCB Rev. A

See page 3
 See page 4

2 STANDARDS

IEC 61869-1, IEC 61869-3 and IEC 60060-1, 2010 cl. 4.4.1 and 4.4.2

3 PERFORMED TEST

Power-frequency voltage withstand test in wet condition. Test voltage applied on primary winding. The secondary terminals 1n, 2n, 3n and dn were connected to ground.

Applied test voltage (kV)	Corrected test voltage (kV)	Frequency Hz	Duration of test	Result
273	275	240	25s	Withstood

4. ATMOSPHERIC CONDITIONS AND CORRECTION FACTOR

Precipitation rate: 1.5 / 1,3 mm/min, (horizontal / vertical component)
 Resistivity of water: 96 Ohm*cm
 Conductivity of water: 104 µS/cm

Pressure: 1011 mb
 Temperature: 22,6 °C
 Correction factor: k = 0,991

5 RESULT

The voltage transformer passed the wet power-frequency voltage withstand test

6 INSTRUMENTS

Equipment	Reg. No.	Last calibration
Voltage divider	M301908	10-2014
Voltmeter	M296144	04-2015

Fluke 187





Instytut Elektrotechniki Electrotechnical Institute



ZESPÓŁ LABORATORIÓW INSTYTUTU ELEKTROTECHNIKI
LABORATORIUM BADAWCZE APARATURY ROZDZIELCZEJ
ul. Pocztyńskiego str. 28, 04-703 WARSZAWA
phone: (+48 22) 11 25 300, email: zwarcb@iel.waw.pl

Testing Laboratory is accredited by Polish Centre of Accreditation,
signatory of the agreements EA MLA and ILAC MRA, Accreditation No. AB 074

Table of contents

1	List of applicable standards	3
2	Range of tests performed	3
3	Ratings assigned by the manufacturer	4
4	Basic identifications data	4
5	Short-circuit withstand capability test	5
6	Photographs	10
7	Drawings	11
8	Uncertainty electrical and non electrical quantities in laboratory	13
9	Annex A--Routine test report of voltage instrument transformer before short-circuit withstand capability test ..	14
10	Annex B--Routine test report of voltage instrument transformer after short-circuit withstand capability test	18

TEST REPORT No. 8734/NZL/NBR/15

Test objects:	Voltage transformer EIMF-E145
Client:	ABB Sp. z o.o. ul. Leszno 59, 06-300 Przasnysz
Manufacturer:	ABB
Test specification:	Short-circuit withstand capability test
Normative document(s):	IEC 61869-3:2011
Reference/Order number:	504-034600/038
Date of tests completion:	October 2015
Test results:	POSITIVE

Authorised by

Michał Babiuch, M.Sc.

Head of Laboratories of the
Electrotechnical Institute

Przemysław Berowski, Ph.D.

WARSAWA, 16.11.2015

The Test Report applies only to the apparatus tested. The responsibility for conformity of any apparatus having the same designations with that tested rests with the Manufacturer.

© Only integral reproduction of this Test Report is permitted without written permission from Laboratory.

The Test Report comprises 21 sheets in total.

**1 List of applicable standards**

- IEC 61869-1:2009 Instrument transformers – Part 1: General requirements
- IEC 61869-3:2011 Instrument transformers – Part 3: Additional requirements for inductive voltage transformers

Tests were observed by:

Zbigniew Wesolowski ABB

2 Range of tests performed

- Short-circuit withstand capability test by IEC 61869-3:2011 clause 7.2.301

**3 Ratings assigned by the manufacturer**

Highest system voltage.....	U_m	145 kV
Rated frequency.....	f_n	50 Hz
Rated power-frequency withstand voltage.....		275 kV
Rated lightning-impulse withstand voltage.....		650 kV
Rated primary voltage:.....	U_1	145/√3 kV
Rated secondary voltage:.....	U_2 :	
• 1a-1n.....		115/√3 V
• 2a-2n.....		115/√3 V
• 3a-3n.....		115/√3 V
• da-dn.....		115 V

4 Basic identifications data

Test object:	Voltage transformer
Type:	EMF-EI45
Manufacturer:	ABB
Serial No.:	IHSE8851773
Year of manufacture:	2015
Rating plate:	Figure 2, page 11
Design documentation:	Dimensional drawing No. IHSE8851773

Detailed list of components specified in technical project:

Dimensional drawing No. IHSE8851773

168



5 Short-circuit withstand capability test

Test performed according to IEC 61869-3:2011 clause 7.2.301
 Condition of test object before test.....New
 Date of test.....22, 27 October 2015
 Ambient temperature.....17,6°C
 Test voltage.....66,4 V
 Frequency.....50 Hz
 Test object on testing stand.....Photo 2, page 10

Test results:

- winding 1a-1n..... Table 1, page 6, osc. 92073, page 7
- winding 3a-3n..... Table 2, page 6, osc. 92092, page 8
- winding da-dn..... Table 3, page 6, osc. 92094, page 9

Table 1 Test result

Tested secondary winding		1a-1n
Oscillogram	Nr	92073
Symmetrical, r.m.s. value of primary voltage	V	66,98
Symmetrical, r.m.s. value of current in primary winding	mA	617,32
Symmetrical, r.m.s. value of current in secondary winding	A	777,50
Duration of short-circuit	s	1,02

Table 2 Test result

Tested secondary winding		3a-3n
Oscillogram	Nr	92092
Symmetrical, r.m.s. value of primary voltage	V	66,42
Symmetrical, r.m.s. value of current in primary winding	mA	746,61
Symmetrical, r.m.s. value of current in secondary winding	A	941,13
Duration of short-circuit	s	1,01

Table 3 Test result

Tested secondary winding		da-dn
Oscillogram	Nr	92094
Symmetrical, r.m.s. value of primary voltage	V	115,46
Symmetrical, r.m.s. value of current in primary winding	mA	677,23
Symmetrical, r.m.s. value of current in secondary winding	A	493,49
Duration of short-circuit	s	1,01




Figure 1 Test circuit

G - Generator
 MB - Master Breaker
 MS - Making switch
 L - Resistors
 R - Resistors
 PT - Power transformer
 V - Voltage measurement recorder HIOKI no 131011561
 CM-1 - Current measurement - Rogowski coil type AMEC AmpFlex 30000-48-2-1, no NWM-801-25900/1
 CM-2 - Current measurement - Shunt no NWM 008-IL-38
 TO - Test object

Condition of tested object after test:

- No visibly damages was noted.
- Errors do not differ from those recorded before the tests by more than half the limits of error in its accuracy class.
- Test object withstand the dielectric tests with the test voltage reduced to 90% of those given.

Test result: Object passed the test




Figure 8/21

TEST REPORT No. 8734/NZL/NBR/15




Figure 1/21

TEST REPORT No. 8734/NZL/NBR/15





6 Photographs




Photo 1 Rating plate of voltage transformer





Photo 2 Test object during short-circuit withstand capability test

Handwritten signature



Handwritten signature

Handwritten signature



9 Annex A - Routine test report of voltage instrument transformer before short-circuit withstand capability test

A-N	ABB Sp. z o.o. 06-300 Prczaszyszc ul. Leszno 59	Routine test report of voltage instrument Transformer	TYPE: EMF-E145 Serial no: 1HSE8851773
	145/43 kV	145/275/650 kV Voltage factor: 1.9/8h	IEC 61869-3 50 Hz
Winding		Un [kV]	Class
1a - 1n	0,115/43	25	0,1
1a - 1n	0,115/43	25	1,0
2a - 2n	0,115/43	25	0,1
2a - 2n	0,115/43	25	1,0
3a - 3n	0,115/43	25	0,1/3P
3a - 3n	0,115/43	500	3,0/3P
da - dn	0,115	100	0,1
da - dn	0,115	300	3P

- Oil dielectric parameters check before filling (oil after treatment):
lg 8 acc. IEC 60247, breakdown voltage acc. IEC 60156
 - Verification of terminal markings
 - Pressure and tightness test: oil overpressure: 0,8 bar / 24h - no traces of oil leakage
 - Power-frequency withstand test on primary windings
 - Partial discharge measurement
 - Power-frequency withstand test on secondary windings
 - Determination of errors
 - Measurement of capacitance and dielectric dissipation factor - lg 8
 - Measurement of windings' resistance
- A: Up = 275kV / 80s, f = 120Hz; N: Up = 3kV / 60s, f = 50Hz
- Up = 3 kV/60s

Oil dielectric parameters check before filling (oil after treatment)

- Measurement of oil lg 8 according to IEC 60247
Tg 8 = 0,0908 %; electrical stress = 1kV/mm, f = 60Hz, oil temp. = 90C ±1C.
- Measurement of breakdown voltage according to IEC 60156
Mean breakdown voltage = 75,58 kV, Relative standard deviation = 4,68 %;
f = 50Hz, oil temp. = 22,8 °C, measurement without the stirrer, type of electrodes used: partially spherical.

Sample	Breakdown voltage [kV]
1	76,6
2	73,5
3	76,3
4	77,2
5	69,8
6	79,1



8 Uncertainty electrical and non electrical quantities in laboratory

Measured quantity	Range	Frequency	Measured parameter / uncertainty [%]	
Voltage U / Divider RC	0 ≤ U ≤ 1000 V	dc - 20kHz	RMS <± 1,5 Peak <± 1,0	
	1000 V ≤ U ≤ 10 kV	> 20kHz	RMS <± 2,0 Peak <± 2,0	
		> 20kHz	RMS <± 2,0 Peak <± 1,5	
		> 20kHz	RMS <± 2,0 Peak <± 2,5	
Current I / Shunt	U > 10 kV	50Hz - 20kHz	RMS <± 3,0 Peak <± 3,0	
	0 ≤ I ≤ 100 A	dc - 5kHz	RMS <± 1,5 Peak <± 1,0	
		> 5kHz	Joule integral <± 2,0 Peak - Peak/√8 <± 2,0	
	100 A ≤ I ≤ 10 kA	dc - 5kHz	RMS <± 2,0 Peak <± 1,5	
		> 5kHz	Joule integral <± 3,0 Peak - Peak/√8 <± 3,0	
	Current I / Current transformer	I > 10 kA	dc - 5kHz	RMS <± 2,0 Peak <± 1,5
		0 ≤ I ≤ 100 A	> 5kHz	RMS <± 2,5 Peak <± 2,0
			50Hz - 5kHz	Joule integral <± 2,0 Peak - Peak/√8 <± 2,0
		100 A ≤ I ≤ 10 kA	> 5kHz	RMS <± 2,5 Peak <± 2,0
			50Hz - 5kHz	Joule integral <± 3,0 Peak - Peak/√8 <± 3,0
10 kA ≤ I ≤ 30 kA		> 5kHz	RMS <± 2,5 Peak <± 2,0	
		50Hz - 5kHz	Joule integral <± 3,5 Peak - Peak/√8 <± 3,5	
Resistance R bridge, multimeter		20 μΩ ≤ R ≤ 600 μΩ		<± 5 %
		0,6 mΩ ≤ R ≤ 600 mΩ		<± 3 %
Frequency f oscilloscope, recorder TR		0,6 Ω ≤ R ≤ 100 MΩ		<± 1 %
	≤ 10 MHz		<± 0,2 %	
Time t oscilloscope, recorder TR	10 kHz ≤ f ≤ 1 MHz		<± 0,5 %	
	≤ 1 μs		<± 20 %	
Temperature T thermocouples	1 μs ≤ t ≤ 1 ms		<± 10 %	
	> 1 ms		<± 10 %	
Relative humidity	-50 °C ≤ t ≤ 100 °C		<± 0,2 °C - thermometer	
	-100 °C ≤ t ≤ 200 °C		<± 0,8 °C - thermocouples K, recorder	
Length Lengthmeter	20 % do 90% RH		<± 5 % RH	
	≤ 1 mm		<± 0,05 mm	
Gas pressure p	1 mm ≤ L ≤ 30 mm		<± 0,1 mm	
	> 30 mm		<± 5 %	
Atmosph. pressure	≤ 20 bar		<± 5 %	
	20 bar ≤ p ≤ 200 bar		<± 0,01 MPa	

173

Partial discharge measurement

- Measurement according to procedure A (PD test voltages were reached while decreasing the voltage after the power-frequency withstand test on primary winding)
Stress voltage: 275 kV / 80 s
Frequency: 120 Hz

Table with 2 columns: Test voltage, Level of partial discharge. Values: 1.2 Un = 174 kV, 0.5 pC; 1.2 Un / sqrt(3) = 100.5 kV, 0.8 pC

Remarks: background noise level: 0.5 (measured after voltage switch off), measuring circuit was calibrated with 5 pC (calibrating charge).

Verification of accuracy (epsilon U%), (Delta U min)
Date of measurement: 2015-10-20

Main data table for partial discharge measurement with multiple columns for different test conditions and results.

- at 1.9 Un winding da-dn is loaded with 100 VA, p.f. = 0.8 lag.
Measurements uncertainty: epsilon U = +/- 0.44%, Delta U = +/- 2.2 min



Verification of accuracy (epsilon U%), (Delta U min)
Date of measurement: 2015-10-20

Main data table for accuracy verification with multiple columns for different test conditions and results.

- at 1.9 Un winding da-dn is loaded with 100 VA, p.f. = 0.8 lag.
Measurements uncertainty: epsilon U = +/- 0.44%, Delta U = +/- 2.2 min



10 Annex B—Routine test report of voltage instrument transformer after short-circuit withstand capability test

ABB Sp. z o.o. 06-300 Przasnysz ul. Leszno 59		Routine test report of voltage instrument transformer after short-circuit withstand		TYPE: EMF-E145 Serial no: 1H5E8851773	
A-N	145/3 kV	145/275/650 kV	Voltage factor: 1.9/8h	IEC 61869-3	50 Hz
Winding	Un [kV]	Sn [VA]	Glass	Sth [VA]	
1a - 1n	0,115/3	25	0,1	1500	
1a - 1n	0,115/3	25	1,0	1500	
2a - 2n	0,115/3	25	0,1	1500	
2a - 2n	0,115/3	25	1,0	1500	
3a - 3n	0,115/3	25	0,1/3P	1500	
3a - 3n	0,115/3	500	3,0/3P	1500	
da - dn	0,115	100	1,0	450	
da - dn	0,115	300	3P	450	

- Oil dielectric parameters check before filling (oil after treatment):
lg δ acc. IEC 60247, breakdown voltage acc. IEC 60158
- Verification of terminal markings
- Pressure and tightness test: oil overpressure: 0,8 bar / 24h - no traces of oil leakage
- Power-frequency withstand test
- Partial discharge measurement on primary windings
- Power-frequency withstand test on secondary windings
- Determination of errors
- Measurement of capacitance and dielectric dissipation factor - lg δ
- Measurement of windings' resistance

Oil dielectric parameters check before filling (oil after treatment)

- Measurement of oil lg δ according to IEC 60247
Tg δ = 0,0909 %, electrical stress = 1kV/mm, f = 50Hz, oil temp. = 90C ±1C.

- Measurement of breakdown voltage according to IEC 60158
Mean breakdown voltage = 75,58 kV, Relative standard deviation = 4,98 %
f = 50Hz, oil temp. = 22,8 °C, measurement without the slimer, type of electrodes used: partially spherical.

Sample	Breakdown voltage [kV]
1	78,8
2	73,5
3	75,3
4	77,2
5	68,8
6	78,1



Measurement of capacitance and dielectric dissipation factor - tg δ
Temperature: 23 °C, Frequency: 50 Hz

Primary voltage	Tg δ [%]	Capacity [pF]	Leak current [mA]
10 kV	0,21	238	0,773
84 kV	0,24	238	6,309
84 kV	0,24	239	6,309

Measurement of windings' resistance

	R (23 °C)	Rat (75 °C)
A-N	18,20 kΩ	21,919 kΩ
1a-1n	53,000 mΩ	63,831 mΩ
2a-2n	51,700 mΩ	62,285 mΩ
3a-3n	33,100 mΩ	38,884 mΩ
da-dn	143,900 mΩ	173,307 mΩ

Przasnysz, 2015-10-20

Checked by: *[Signature]*



[Large handwritten signature]

175



Measurement of capacitance and dielectric dissipation factor - tg δ

Temperature: 23 °C, Frequency: 50 Hz

Primary voltage	Tg δ [%]	Capacity [pF]	Leak. current [mA]
10 kV	0.20	238	0.753
84 kV	0.21	238	6.343
84 kV	0.21	239	6.343


Measurement of windings' resistance

	R (23 °C)	Ref (75 °C)
A-N	17.70 kΩ	21.317 kΩ
1a-1n	62.000 mΩ	62.627 mΩ
2a-2n	50.500 mΩ	60.820 mΩ
3a-3n	32.760 mΩ	39.455 mΩ
da-dn	143.100 mΩ	172.344 mΩ

Checked by: *J. Krawczyk*

OC-4
KJ-58

Przasnysz, 2015-11-10




[Faint, illegible text]

[Handwritten mark]

177

[Large handwritten signature]



TEST REPORT No. EUR/44/E/16-1

TEST OBJECT: Voltage transformer type EMF-E072 Serial No. 2GGKV1190628 with porcelain insulator

MANUFACTURER: ABB Sp. z o.o. Division in Przasnysz, ul. Leszno 59, 06-300 Przasnysz

TESTS ORDERED BY: ABB Sp. z o.o., ul. Żegalska 1, 04-713 Warszawa order No. 4500774256 dated 07.09.2016

TYPE OF TESTS: Mechanical tests

TESTS PROCEDURE: According to IEC 61869-1:2007 p. 7.4.5

DATE OF TESTS: 18.10.2016

TESTS RESULT: Positive for:
 $F_k = 3600\text{ N}$

Tests result refers only to the test object

THE TESTS WERE WITNESSED BY:

Authorizing Test Engineer
Tomasz Kaczmarezyk
Tomasz Kaczmarezyk

HEAD OF LABORATORY
Lidia Gruza
Lidia Gruza

Warsaw, 24.11.2016

Publishing or reproducing of this report in other version than exact and complete without permission in writing from the laboratory is forbidden.

Contents

1. Test object	3
1.1. Description	3
1.2. Technical data	3
1.3. Technical documentation	3
1.4. Preparation for tests	3
2. Scope of tests	3
3. Test and measuring circuits	4
3. Tests and theirs detailed results	4
4. Test results evaluation	5
Annexes: 1. Photographs taken during the tests	8
2. Documentations delivered by orderer	8
3. Declaration of conformity	10

Report contents:

numbered pages	10
tables	1
photographs	5

Lidia Gruza

Tomasz Kaczmarezyk
179



1. TEST OBJECT

1.1 Description

Voltage transformer type EMF-E072 is used for supplying of measuring and protection circuits in the network of maximum operating voltage 72,5 kV and frequency 50 Hz. The transformer consists of voltage transformer mounted in porcelain enclosure immersed with transformer oil.

1.2 Technical data

The Manufacturer attributed the following construction data to the test object.

Maximum operating voltage 72,5 kV
Rated frequency 50 Hz
Rated static load 3600 N

1.3 Technical documentation

For the purpose of tests the order delivered the following technical documentation:

- "EMF-E072 dimensional drawing", no. 2GHV049349 A0001 approved 10.11.2016,
- rating plate,
- instrument transformer electrical diagram prepared by ABB Sp. z o.o. (Annex 2).

The laboratory proceeded the identification of test object on the base of above documentation and the rating plate. Conformity of manufacturing with constructional documentation No. PLO1/2016 is stated in manufacturer's declaration, copy of which presents Annex 3.

1.4 Preparation for tests

The test object was prepared for test by factory.

2. SCOPE OF TESTS

Test program, agreed with orderer, comprised mechanical tests of voltage transformer with static withstand test load of A terminal in three directions for:

$F_R = 3600 \text{ N}$

according to requirements of IEC 61869-1:2007 p. 7.4.5.

The test load shall be applied to the centre of the terminal. During the tests deflection of the voltage transformer shall be recorded.

3. TEST AND MEASURING CIRCUITS

For the tests the voltage transformer was completely assembled and filled with oil, installed in a vertical position on the frame rigidly fixed.

During the tests deflection of the transformer's terminal was recorded by laser displacement sensor (accuracy of measurement $\pm 0,1 \text{ mm}$) and the load was measured by electronic dynamometer.



3. TESTS AND THEIRS DETAILED RESULTS

The load was applied to the A terminal in three directions: Longitudinal, Transverse and Vertical (see photographs 1 to 3 in Annex 1). The load was increased and released smoothly (30 - 90 s) and was maintained for 60 s. Tests results are presented in table 1.

During the tests the following records were made:

- phot. 1 to 3 - voltage transformer during mechanical tests,
 - phot. 4 - A terminal after tests,
 - phot. 5 - voltage transformer after tests.
- (Annex 1 presents the photographs)

Table 1. Results of static load withstand tests at $F = 3650 \text{ N}$

Test No.	Terminal	Load direction	Test time	Observations
-	-	-	s	-
1	A	Longitudinal	60	During the static load deflection was 6,3 mm. Residual deflection was 0,1 mm.
2	A	Transverse	60	During the static load deflection was 5,8 mm. Residual deflection was 0,8 mm.
3	A	Vertical	60	During the static load deflection was 1,1 mm. Residual deflection was 0,1 mm.

After the tests no damage nor oil leak was stated.


4. TESTS RESULTS EVALUATION

According to criteria given in IEC 61869-1:2007 p. 7.4.5 the results of mechanical tests of tested voltage transformer is positive for:


$F_R = 3600 \text{ N}$.




ANNEX 1
Photographs taken during the tests




Phot. 1. Longitudinal load of A terminal



Phot. 2. Transverse load of A terminal



Phot. 3. Vertical load of A terminal



Phot. 4. A terminal after tests



[Handwritten signature]

[Handwritten signature]



ANNEX 2

Documentations delivered by orderer



Phot. 5. Voltage transformer after tests

182



ABB Voltage transformer

Type S/N Year

Insulation level Standard Insulation class Temp. range

fr F Transportation Fv


Attention: Hermetic device, do not unscrew or sampling according to the manufacturer's instruction.

Total weight Oil weight

Oil type Nynas Nyltro Lb70

1a-1n 110/5V 1-50VA M.0.2/3P 1300VAe
2a-2n 110/5V 1-50VA M.0.2/3P 1300VAe

Wings' terminal in the second box



ANNEX 3

Declaration of Conformity

ABB	Declaration of conformity	ABB Sp. z o.o. Dept. in Przasnysz POLAND
DECLARATION OF CONFORMITY No. PL.01/2016 (EN) (acc. to ISO/IEC 17050-1)		
Manufacturer:	ABB Sp. z o.o., Leszno 59 Str., 06-300 Przasnysz	
Product:	Voltage Instrument Transformer EMF-E072	
Above mentioned product conforms with the following standard :		
Standard	Title	Edition/Date
IEC 61869 - 3	Voltage Instrument Transformers	2016
Additional information: Serial numbers: 2GGKV1190628, 2GGKV1190629, 2GGKV1190649,		
Place and date of issue of declaration Przasnysz 07.11.2016		
Kierownik Wydziału Ciepły Produkcji i Zakładów Wyt. ABB Sp. z o.o. Krzysztof Lubczak	Dyrektor Łódzkiej Jednostki Branży Wysoch Napięć ABB Sp. z o.o. Paweł Rzebecki	(Name) (Signature)

183



TEST REPORT No. EUR/44/E/16-2

TEST OBJECT: Voltage transformer type EMF-E072 Serial No. 2GGKY1190629 with composite insulator

MANUFACTURER: ABB Sp. z o.o. Division in Przasnysz, ul. Leszno 59, 06-300 Przasnysz

TESTS ORDERED BY: ABB Sp. z o.o., ul. Żegaińska 1, 04-713 Warszawa order No. 4500774256 dated 07.09.2016

TYPE OF TESTS: Mechanical tests

TESTS PROCEDURE: According to IEC 61869-1:2007 p. 7.4.5

DATE OF TESTS: 18.10.2016

TESTS RESULT: Positive for:
F_k = 3600 N

Tests result refers only to the test object

THE TESTS WERE WITNESSED BY:

Authorizing
Test Engineer

Tomasz Kaczmarczyk

Tomasz Kaczmarczyk

HEAD OF LABORATORY

Lidia Gruza

Lidia Gruza

Warsaw, 24.11.2016

Publishing or reproducing of this report in other version than exact and complete without permission in writing from the laboratory is forbidden.

Contents

1. Test object	3
1.1. Description	3
1.2. Technical data	3
1.3. Technical documentation	3
1.4. Preparation for tests	3
2. Scope of tests	3
3. Test and measuring circuits	4
3. Tests and theirs detailed results	4
4. Test results evaluation	5
Annexes: 1. Photographs taken during the tests	8
2. Documentations delivered by orderer	10
3. Declaration of conformity	10

Report contents:

numbered pages	10
tables	1
photographs	5

3

185

[Handwritten signature]



1. TEST OBJECT

1.1 Description

Voltage transformer type EMF-E072 is used for supplying of measuring and protection circuits in the network of maximum operating voltage 72,5 kV and frequency 50 Hz. The transformer consists of voltage transformer mounted in composite enclosure immersed with transformer oil.

1.2 Technical data

The Manufacturer attributed the following construction data to the test object.

Maximum operating voltage 72,5 kV
Rated frequency 50 Hz
Rated static load 3600 N

1.3 Technical documentation

For the purpose of tests the orderer delivered the following technical documentation:

- "EMF-E072 dimensional drawing", no. 2GHV040937A0001 approved 10.11.2016,
- rating plate,
- instrument transformer electrical diagram prepared by ABB Sp. z o.o. (Annex 2).

The laboratory proceeded the identification of test object on the base of above documentation and the rating plate. Conformity of manufacturing with constructional documentation No. PLO1/2016 is stated in manufacturer's declaration, copy of which presents Annex 3.

1.4 Preparation for tests

The test object was prepared for test by factory.

2. SCOPE OF TESTS

Test program, agreed with orderer, comprised mechanical tests of voltage transformer with static withstand test load of A terminal in three directions for:

$F_R = 3600 \text{ N}$

according to requirements of IEC 61869-1:2007 p. 7.4.5.

The test load shall be applied to the centre of the terminal. During the tests deflection of the voltage transformer shall be recorded.

3. TEST AND MEASURING CIRCUITS

For the tests the voltage transformer was completely assembled and filled with oil, installed in a vertical position on the frame rigidly fixed.

During the tests deflection of the transformer's terminal was recorded by laser displacement sensor (accuracy of measurement $\pm 0,1 \text{ mm}$) and the load was measured by electronic dynamometer.



3. TESTS AND THEIRS DETAILED RESULTS

The load was applied to the A terminal in three directions: Longitudinal, Transverse and Vertical (see photographs 1 to 3 in Annex 1). The load was increased and released smoothly (30 - 90 s) and was maintained for 60 s. Tests results are presented in table 1.

During the tests the following records were made:

- phot. 1 to 3 - voltage transformer during mechanical tests,
- phot. 4 - A terminal after tests,
- phot. 5 - voltage transformer after tests.

(Annex 1 presents the photographs)

Table 1. Results of static load withstand tests at $F = 3650 \text{ N}$

Test No.	Terminal	Load direction	Test time	Observations
-	-	-	s	-
1	A	Longitudinal	60	During the static load deflection was 16,2 mm. Residual deflection was 0,9 mm.
2	A	Transverse	60	During the static load deflection was 17,3 mm. Residual deflection was 0,5 mm.
3	A	Vertical	60	During the static load deflection was 2,9 mm. Residual deflection was 0,0 mm.

After the tests no damage nor oil leak was stated.


4. TESTS RESULTS EVALUATION

According to criteria given in IEC 61869-1:2007 p. 7.4.5 the results of mechanical tests of tested voltage transformer is positive for:


$F_R = 3600 \text{ N}$.

ANNEX 1


Photographs taken during the tests




Phot. 1. Longitudinal load of A terminal



Phot. 2. Transverse load of A terminal



Phot. 3. Vertical load of A terminal



Phot. 4. A terminal after tests

M

187

ja



ABB Voltage transformer

Type EMF-E072 S/N 2GGKV190629

Insulation level 72,5/140/325 kV Standard IEC 61869-3

f_n 50Hz F 3,6kN FV 1,9 / 8h

Transportation Vertical

Insulation class A Temp. range -40/+40C

Year 2016

Attention: Hermetic device, do not unseat. Oil sampling according to the manufacturer's instruction.

A - N 66/√3 kV


1φ-in 110/√3V 1-50VA H.0.2/3P 1300VAh

2φ-2n 110/√3V 1-50VA H.0.2/3P 1300VAh

■ -- Windings' terminal in the second box

Total weight 170kg Oil weight 40kg

Oil type Nynas Nyltra Libra ISO-L-NTU0-2960130



ANNEX 3 Declaration of Conformity

ABB	Declaration of conformity	ABB Sp. z o.o. Dept. in Przasnysz POLAND
<p>DECLARATION OF CONFORMITY No. PL01/2016 (EN) (acc. to ISO/IEC 17050-1)</p> <p>Manufacturer: ABB Sp. z o.o., Leszno 59 Str., 06-300 Przasnysz</p> <p>Product: Voltage Instrument Transformer EMF-E072</p> <p>Above mentioned product conforms with the following standard:</p> <p>Standard IEC 61869 - 3 Title Voltage Instrument Transformers Edition/Date 2016</p> <p>Additional information: Serial numbers: 2GGKV190628, 2GGKV190629, 2GGKV190649,</p> <p>Place and date of issue of declaration Przasnysz 07.11.2016</p> <p>Kierownik, Jakielci Grupy Produkcji Fizykalnego WN ABB Sp. z o.o. Krzysztof Lubacki</p> <p>Dyrektor Łojasini, Jednostki Biznesu Wycechli Napiec ABB Sp. z o.o. Paweł Radzicki</p> <p>(Name) (Signature)</p>		


[Handwritten signature]

[Handwritten mark]

(

(

TEST REPORT No. EUR/44/E/16-3



TEST OBJECT: Voltage transformer type EMP-E072 Serial No. 2GGKV1190649 with composite insulator

MANUFACTURER: ABB Sp. z o.o. Division in Przasnysz, ul. Leszno 59, 06-300 Przasnysz

TESTS ORDERED BY: ABB Sp. z o.o., ul. Żegalska 1, 04-713 Warszawa order No. 4500774256 dated 07.09.2016

TYPE OF TESTS: Mechanical tests

TESTS PROCEDURE: According to IEC 61869-1:2007 p. 7.4.5

DATE OF TESTS: 21.11.2016

TESTS RESULT: Positive for:
 $F_k = 3600 \text{ N}$

Tests result refers only to the test object

THE TESTS WERE WITNESSED BY:

[Signature]

Authorizing
 Test Engineer
[Signature]
 Tomasz Kaczmareczyk

HEAD OF LABORATORY

[Signature]
 Lidia Gruza

Warsaw, 24.11.2016

191

Contents

1. Test object	3
1.1. Description	3
1.2. Technical data	3
1.3. Technical documentation	3
1.4. Preparation for tests	3
2. Scope of tests	3
3. Test and measuring circuits	3
3. Tests and theirs detailed results	4
4. Test results evaluation	4
Annexes: 1. Photographs taken during the tests	5
2. Documentations delivered by orderer	8
3. Declaration of conformity	10

Report contents:

numbered pages	10
tables	1
photographs	5

[Signature]



1. TEST OBJECT

1.1 Description

Voltage transformer type EMF-E072 is used for supplying of measuring and protection circuits in the network of maximum operating voltage 72,5 kV and frequency 50 Hz. The transformer consists of voltage transformer mounted in composite enclosure immersed with transformer oil.

1.2 Technical data

The Manufacturer attributed the following construction data to the test object.

Maximum operating voltage 72,5 kV
Rated frequency 50 Hz
Rated static load 3600 N

1.3 Technical documentation

For the purpose of tests the orderer delivered the following technical documentation:

- "EMF-E072 dimensional drawing", no. 2GHV038396P0001 approved 10.11.2016,
- rating plate,
- instrument transformer electrical diagram prepared by ABB Sp. z o.o. (Annex 2).

The laboratory proceeded the identification of test object on the base of above documentation and the rating plate. Conformity of manufacturing with constructional documentation No. PLO1/2016 is stated in manufacturer's declaration, copy of which presents Annex 3.

1.4 Preparation for tests

The test object was prepared for test by factory.

2. SCOPE OF TESTS

Test program, agreed with orderer, comprised mechanical tests of voltage transformer with static withstand test load of A terminal in three directions for:

$F_k = 3600 \text{ N}$

according to requirements of IEC 61869-1:2007 p. 7.4.5.

The test load shall be applied to the centre of the terminal. During the tests deflection of the voltage transformer shall be recorded.

3. TEST AND MEASURING CIRCUITS

For the tests the voltage transformer was completely assembled and filled with oil, installed in a vertical position on the frame rigidly fixed.

During the tests deflection of the transformer's terminal was recorded by laser displacement sensor (accuracy of measurement $\pm 0,1 \text{ mm}$) and the load was measured by electronic dynamometer.



3. TESTS AND THEIRS DETAILED RESULTS

The load was applied to the A terminal in three directions: Longitudinal, Transverse and Vertical (see photographs 1 to 3 in Annex 1). The load was increased and released smoothly (30 - 90 s) and was maintained for 60 s. Tests results are presented in table 1.

During the tests the following records were made:

- phot. 1 to 3 - voltage transformer during mechanical tests,
- phot. 4 - A terminal after tests,
- phot. 5 - voltage transformer after tests.

(Annex 1 presents the photographs)

Table 1. Results of static load withstand tests at $F = 3650 \text{ N}$

Test No.	Terminal	Load direction	Test time s	Observations
1	A	Longitudinal	60	During the static load deflection was 26,0 mm. Residual deflection was 0,9 mm.
2	A	Transverse	60	During the static load deflection was 26,1 mm. Residual deflection was 1,4 mm.
3	A	Vertical	60	During the static load deflection was 0,8 mm. Residual deflection was 0,2 mm.

After the tests no damage nor oil leak was stated.

4. TESTS RESULTS EVALUATION


According to criteria given in IEC 61869-1:2007 p. 7.4.5 the results of mechanical tests of tested voltage transformer is positive for:

$F_k = 3600 \text{ N}$.




ANNEX 1


Photographs taken during the tests




Phot. 1. Longitudinal load of A terminal



Phot. 2. Transverse load of A terminal



Phot. 3. Vertical load of A terminal



Phot. 4. A terminal after tests



[Handwritten signature]

[Handwritten mark]



ANNEX 2

Documentations delivered by orderer



Phot. 5. Voltage transformer after tests



ABB Voltage transformer

Type EMF-E072 S/N 2GGKV1190649

Insulation level 72,5/140/325 kV Standard IEC 61869-3

f₀ 50Hz F 3,6kN F_V 1,9 / 8h

Transportation Vertical

Temp. range -40/+40C

Year 2016

Attention:
Harmatic device, do not unseal.
Of sampling according to the manufacturer's instruction.

A - N 66/√3 kV

1c - In 110/√3V 1-50VA K.0,2/3P 1300VAh


2c - 2n 110/√3V 1-50VA K.0,2/3P 1300VAh

Windings' terminal in the second box

Total weight 170kg Oil weight 40kg

Nynas Nylro Libra

Oil type ISO-L-NTU0-2980130



ANNEX 3 Declaration of Conformity

ABB Declaration of conformity

ABB Sp. z o.o.
Dept. in Przasnysz
POLAND

DECLARATION OF CONFORMITY No. PL01/2016 (EN)
(acc. to ISO/IEC 17050-1)

Manufacturer: ABB Sp. z o.o., Leszno 59 Str., 06-300 Przasnysz

Product: Voltage Instrument Transformer EMF-E072

Above mentioned product conforms with the following standard :

Standard IEC 61869 - 3 Title Voltage Instrument Transformers Edition/Date 2016

Additional information:
Serial numbers: 2GGKV1190628, 2GGKV1190629, 2GGKV1190649,

Place and date of issue of declaration
Przasnysz 07.11.2016

Kierownik Wydziału Ciepły
Produkcji i Technologicznej WY
ABB Sp. z o.o.
Krzysztof Lubbecki

Dyrektor Technicznej Jednostki
Biznesu Wzrostu i Napię
ABB Sp. z o.o.
Paweł Kłoski

(Name) (Signature)

195

(

(



TEST REPORT No. EUR/44/E/16-4

TEST OBJECT: Voltage transformer type EMF-E145 Serial No. 2GGKV1190669 with composite insulator

MANUFACTURER: ABB Sp. z o.o. Division in Przasnysz, ul. Leszno 59, 06-300 Przasnysz

TESTS ORDERED BY: ABB Sp. z o.o., ul. Żegalska 1, 04-713 Warszawa order No. 4500774256 dated 07.09.2016

TYPE OF TESTS: Mechanical tests

TESTS PROCEDURE: According to IEC 61869-1:2007 p. 7.4.5

DATE OF TESTS: 12.12.2016

TESTS RESULT: Positive for:
 $F_R = 3600 \text{ N}$

Tests result refers only to the test object

THE TESTS WERE WITNESSED BY:

Authorizing Test Engineer
Tomasz Kaczmarczyk
Tomasz Kaczmarczyk

HEAD OF LABORATORY
Lidia Gruza
Lidia Gruza

Warsaw, 16.12.2016

Contents

1. Test object	3
1.1. Description	3
1.2. Technical data	3
1.3. Technical documentation	3
1.4. Preparation for tests	3
2. Scope of tests	3
3. Test and measuring circuits	4
3. Tests and theirs detailed results	4
4. Test results evaluation	5
Annexes: 1. Photographs taken during the tests	8
2. Documentations delivered by orderer	10
3. Declaration of conformity	10

Report contents:

numbered pages	10
tables	1
photographs	5

[Signature]

[Signature]



1. TEST OBJECT

1.1 Description

Voltage transformer type EMF-E145 is used for supplying of measuring and protection circuits in the network of maximum operating voltage 145 kV and frequency 50 Hz. The transformer consists of voltage transformer mounted in composite enclosure immersed with transformer oil.

1.2 Technical data

The Manufacturer attributed the following construction data to the test object.

Maximum operating voltage 145 kV
Rated frequency 50 Hz
Rated static load 3600 N

1.3 Technical documentation

For the purpose of tests the orderer delivered the following technical documentation:

- "EMF-E145 dimensional drawing", no. 2GHV036167A0001 approved 29.11.2016,
- rating plate,
- instrument transformer electrical diagram prepared by ABB Sp. z o.o. (Annex 2).

The laboratory proceeded the identification of test object on the base of above documentation and the rating plate. Conformity of manufacturing with constructional documentation No. PL02/2016 is stated in manufacturer's declaration, copy of which presents Annex 3.

1.4 Preparation for tests

The test object was prepared for test by factory.

2. SCOPE OF TESTS

Test program, agreed with orderer, comprised mechanical tests of voltage transformer with static withstand test load of A terminal in three directions for:

$F_R = 3600 \text{ N}$

according to requirements of IEC 61869-1:2007 p. 7.4.5.

The test load shall be applied to the centre of the terminal. During the tests deflection of the voltage transformer shall be recorded.

3. TEST AND MEASURING CIRCUITS

For the tests the voltage transformer was completely assembled and filled with oil, installed in a vertical position on the frame rigidly fixed.

During the tests deflection of the transformer's terminal was recorded by laser displacement sensor (accuracy of measurement $\pm 0,1 \text{ mm}$) and the load was measured by electronic dynamometer.



3. TESTS AND THEIRS DETAILED RESULTS

The load was applied to the A terminal in three directions: Longitudinal, Transverse and Vertical (see photographs 1 to 3 in Annex 1). The load was increased and released smoothly (30 - 90 s) and was maintained for 60 s. Tests results are presented in table 1.

During the tests the following records were made:

- phot. 1 to 3 - voltage transformer during mechanical tests,
 - phot. 4 - A terminal after tests,
 - phot. 5 - voltage transformer after tests.
- (Annex 1 presents the photographs)

Table 1. Results of static load withstand tests at $F = 3650 \text{ N}$

Test No.	Terminal	Load direction	Test time s	Observations
1	A	Longitudinal	60	During the static load deflection was 72,8 mm. Residual deflection was 2,7 mm.
2	A	Transverse	60	During the static load deflection was 75,8 mm. Residual deflection was 4,2 mm.
3	A	Vertical	60	During the static load deflection was 1,2 mm. Residual deflection was 0,9 mm.

After the tests no damage nor oil leak was stated.


4. TESTS RESULTS EVALUATION

According to criteria given in IEC 61869-1:2007 p. 7.4.5 the results of mechanical tests of tested voltage transformer is positive for:


$F_R = 3600 \text{ N}$.

ANNEX 1


Photographs taken during the tests




Phot. 1. Longitudinal load of A terminal.



Phot. 2. Transverse load of A terminal.



Phot. 3. Vertical load of A terminal.



Phot. 4. A terminal after tests



Handwritten mark

200



ANNEX 2

Documentations delivered by orderer



Phot. 5. Voltage transformer after tests



ANNEX 3

Declaration of Conformity

ABB Voltage transformer

Type EMF-E145 S/N 2GGKV1190669

Insulation level 145/275/650 KV Standard IEC 61869-3

fr 50Hz F 3.6kN FV 1.9 / Bh

Transportation Vertical

Insulation class A Temp range -40/+40C

Year 2016

Attention: Hermetic device, do not unseal. Oil sampling according to the manufacturer's instruction.

Total weight 280kg Oil weight 65kg

Oil type Nynas Nyltro Lbrg ISO-L-NTUO-2960130

A-N 145/√3 KV

1a-1n 115/√3V 100VA H.0.2/3P 1300VAh

2a-2n 115/√3V 100VA H.0.2/3P 1300VAh




ABB Declaration of conformity

ABB Sp. z o.o.
Dept. In Przasnysz
POLAND

DECLARATION OF CONFORMITY No. PL02/2016 (EN)
(acc. to ISO/IEC 17050-1)

Manufacturer: ABB Sp. z o.o., Leszno 59 Str., 06-300 Przasnysz

Product: Voltage Instrument Transformer EMF-E145

Above mentioned product conforms with the following standard :

Standard IEC 61869 - 3 Title Voltage Instrument Transformers Edition/Date 2016

Additional information:
Serial numbers: 2GGKV1190668, 2GGKV1190669, 2GGKV1190670,

Place and date of issue of declaration
Przasnysz 25.11.2016

Kierownik (Archiwizacja) Główny
Produkcji i Prowadzenia Wyn
ABB Sp. z o.o.
Krzysztof Lubbecki


Dyrektor (Archiwizacja) Główny
Biżnesu i Wyróżnień Należę
ABB Sp. z o.o.
Paweł Szargacki

(Name) (Signature)

2011

C

C



TEST REPORT No. EUR/44/E/16-5

TEST OBJECT: Voltage transformer type EMF-E145 Serial No. 2GGKV1190668 with porcelain insulator

MANUFACTURER: ABB Sp. z o.o. Division in Przasnysz, ul. Leszno 59, 06-300 Przasnysz

TESTS ORDERED BY: ABB Sp. z o.o., ul. Żegalska 1, 04-713 Warszawa order No. 4500774256 dated 07.09.2016

TYPE OF TESTS: Mechanical tests

TESTS PROCEDURE: According to IEC 61869-1:2007 p. 7.4.5

DATE OF TESTS: 12.12.2016

TESTS RESULT: Positive for:
 $F_R = 3600 N$

Tests result refers only to the test object

THE TESTS WERE WITNESSED BY:

Authorizing
Test Engineer

Tomasz Kaczmarczyk

Tomasz Kaczmarczyk

HEAD OF LABORATORY

Lidia Gruza

Lidia Gruza

Warsaw, 16.12.2016

Contents

1. Test object	3
1.1. Description	3
1.2. Technical data	3
1.3. Technical documentation	3
1.4. Preparation for tests	3
2. Scope of tests	3
3. Test and measuring circuits	4
3. Tests and theirs detailed results	4
4. Test results evaluation	5
Annexes: 1. Photographs taken during the tests	8
2. Documentations delivered by orderer	10
3. Declaration of conformity	10

Report contents:

numbered pages	10
tables	1
photographs	5

3

203



1. TEST OBJECT

1.1 Description

Voltage transformer type EMF-E145 is used for supplying of measuring and protection circuits in the network of maximum operating voltage 145 kV and frequency 50 Hz. The transformer consists of voltage transformer mounted in porcelain enclosure immersed with transformer oil.

1.2 Technical data

The Manufacturer attributed the following construction data to the test object.

Maximum operating voltage 145 kV
Rated frequency 50 Hz
Rated static load 3600 N

1.3 Technical documentation

For the purpose of tests the orderer delivered the following technical documentation:

- "EMF-E145 dimensional drawing", no. 2GHV040205A0001 approved 29.11.2016,
- rating plate,
- instrument transformer electrical diagram prepared by ABB Sp. z o.o. (Annex 2).

The laboratory proceeded the identification of test object on the base of above documentation and the rating plate. Conformity of manufacturing with constructional documentation No. PLO2/2016 is stated in manufacturer's declaration, copy of which presents Annex 3.

1.4 Preparation for tests

The test object was prepared for test by factory.

2. SCOPE OF TESTS

Test program, agreed with orderer, comprised mechanical tests of voltage transformer with static withstand test load of A terminal in three directions for:

$$F_R = 3600 \text{ N}$$

according to requirements of IEC 61869-1:2007 p. 7.4.5.

The test load shall be applied to the centre of the terminal. During the tests deflection of the voltage transformer shall be recorded.

3. TEST AND MEASURING CIRCUITS

For the tests the voltage transformer was completely assembled and filled with oil, installed in a vertical position on the frame rigidly fixed.

During the tests deflection of the transformer's terminal was recorded by laser displacement sensor (accuracy of measurement $\pm 0,1 \text{ mm}$) and the load was measured by electronic dynamometer.



3. TESTS AND THEIRS DETAILED RESULTS

The load was applied to the A terminal in three directions: Longitudinal, Transverse and Vertical (see photographs 1 to 3 in Annex 1). The load was increased and released smoothly (30 - 90 s) and was maintained for 60 s. Tests results are presented in table 1.

During the tests the following records were made:

- phot. 1 to 3 - voltage transformer during mechanical tests,
 - phot. 4 - A terminal after tests,
 - phot. 5 - voltage transformer after tests.
- (Annex 1 presents the photographs)

Table 1. Results of static load withstand tests at $F = 3650 \text{ N}$

Test No.	Terminal	Load direction	Test time	Observations
-	-	-	s	-
1	A	Longitudinal	60	During the static load deflection was 13,8 mm. Residual deflection was 0,6 mm.
2	A	Transverse	60	During the static load deflection was 11,7 mm. Residual deflection was 0,1 mm.
3	A	Vertical	60	During the static load deflection was 1,6 mm. Residual deflection was 0,2 mm.

After the tests no damage nor oil leak was stated.

4. TESTS RESULTS EVALUATION


According to criteria given in IEC 61869-1:2007 p. 7.4.5 the results of mechanical tests of tested voltage transformer is positive for:

$$F_R = 3600 \text{ N.}$$




ANNEX 1


Photographs taken during the tests




Phot. 1. Longitudinal load of A terminal



Phot. 2. Transverse load of A terminal



Phot. 3. Vertical load of A terminal



Phot. 4. A terminal after tests



Handwritten signature

Handwritten mark



ANNEX 2

Documentations delivered by orderer



Phot. 5. Voltage transformer after tests



ANNEX 3

Declaration of Conformity


ABB

ABB	Declaration of conformity	ABB Sp. z o.o. Dept. in Przasnysz POLAND
DECLARATION OF CONFORMITY No. PL02/2016 (EN) (acc. to ISO/IEC 17050-1)		
Manufacturer: ABB Sp. z o.o., Leszno 59 Str., 06-300 Przasnysz		
Product: Voltage Instrument Transformer EMF-E145		
Above mentioned product conforms with the following standard :		
Standard IEC 61869 - 3	Title Voltage Instrument Transformers	Edition/Date 2016
Additional information:		
Serial numbers: 2GGKV1190668, 2GGKV1190669, 2GGKV1190670,		
Place and date of issue of declaration Przasnysz 25.11.2016		
Kierownik: Jacek Gryby Produkcji: Przemysław WN ABB Sp. z o.o.		Dyrektor (sygnel) Jednostki Biznesu Wypokaz Napie ABB Sp. z o.o.
Krzysztof Lubicki (Name)		(Signature)

[Handwritten signature]

[Handwritten signature]

ABB Voltage transformer Type EMF-E145 S/N 2GGKV1190668	
Insulation level 145/275/650 kV Standard IEC 61869-3	fr 50Hz F 3.6kN Fv 1.9 / 8h
Transportation Vertical	Temp. range -40/+40C
Insulation class A	Year 2016
Attention: Hermetic device, do not unseal, or sampling according to the manufacturer's instruction.	
Total weight 350kg Oil weight 65kg	Oil type Nynas Nitro Libra ISO-L-NTUO-2960130
10-1n 115/5V 100VA M.0.2/3P 1300VAh 20-2n 115/5V 100VA M.0.2/3P 1300VAh	A-N 145/√3 kV



(

(

Contents

1. Test object	3
1.1. Description	3
1.2. Technical data	3
1.3. Technical documentation	3
1.4. Preparation for tests	3
2. Scope of tests	3
3. Test and measuring circuits	4
3. Tests and theirs detailed results	4
4. Test results evaluation	5
Annexes: 1. Photographs taken during the tests	8
2. Documentations delivered by orderer	10
3. Declaration of conformity	10



TEST REPORT No. EUR/44/E/16-6

TEST OBJECT: Voltage transformer type EMF-E145 Serial No. 2GGKV1190670 with composite insulator

MANUFACTURER: ABB Sp. z o.o. Division in Przasnysz, ul. Leszno 59, 06-300 Przasnysz

TESTS ORDERED BY: ABB Sp. z o.o., ul. Żegawska 1, 04-713 Warszawa order No. 4500774256 dated 07.09.2016

TYPE OF TESTS: Mechanical tests

TESTS PROCEDURE: According to IEC 61869-1:2007 p. 7.4.5

DATE OF TESTS: 21.12.2016

TESTS RESULT: Positive for:
F_R = 3600 N

Tests result refers only to the test object

THE TESTS WERE WITNESSED BY:

Authorizing
Test Engineer

Tomasz Kaczmarczyk

Tomasz Kaczmarczyk

HEAD OF LABORATORY

Lidia Gruza

Lidia Gruza

Warsaw, 23.12.2016

Report contents:

numbered pages	10
tables	1
photographs	5

[Handwritten signature]

[Handwritten signature]

[Handwritten mark]

209



1. TEST OBJECT

1.1 Description

Voltage transformer type EMF-E145 is used for supplying of measuring and protection circuits in the network of maximum operating voltage 145 kV and frequency 50 Hz. The transformer consists of voltage transformer mounted in composite enclosure immersed with transformer oil.

1.2 Technical data

The Manufacturer attributed the following construction data to the test object.

Maximum operating voltage 145 kV
Rated frequency 50 Hz
Rated static load 3600 N

1.3 Technical documentation

For the purpose of tests the orderer delivered the following technical documentation:

- "EMF-E145 dimensional drawing", no. 2GHV036269A0001 approved 29.11.2016,
- rating plate,
- instrument transformer electrical diagram prepared by ABB Sp. z o.o. (Annex 2).

The laboratory proceeded the identification of test object on the base of above documentation and the rating plate. Conformity of manufacturing with constructional documentation No. PL02/2016 is stated in manufacturer's declaration, copy of which presents Annex 3.

1.4 Preparation for tests

The test object was prepared for test by factory.

2. SCOPE OF TESTS

Test program, agreed with orderer, comprised mechanical tests of voltage transformer with static withstand test load of A terminal in three directions for:

$F_R = 3600 \text{ N}$

according to requirements of IEC 61869-1:2007 p. 7.4.5.

The test load shall be applied to the centre of the terminal. During the tests deflection of the voltage transformer shall be recorded.

3. TEST AND MEASURING CIRCUITS

For the tests the voltage transformer was completely assembled and filled with oil, installed in a vertical position on the frame rigidly fixed.

During the tests deflection of the transformer's terminal was recorded by laser displacement sensor (accuracy of measurement $\pm 0,1 \text{ mm}$) and the load was measured by electronic dynamometer.



3. TESTS AND THEIRS DETAILED RESULTS

The load was applied to the A terminal in three directions: Longitudinal, Transverse and Vertical (see photographs 1 to 3 in Annex 1). The load was increased and released smoothly (30 - 90 s) and was maintained for 60 s. Tests results are presented in table 1.

During the tests the following records were made:

- phot. 1 to 3 - voltage transformer during mechanical tests,
 - phot. 4 - A terminal after tests,
 - phot. 5 - voltage transformer after tests.
- (Annex 1 presents the photographs)

Table 1. Results of static load withstand tests at $F = 3650 \text{ N}$

Test No.	Terminal	Load direction	Test time s	Observations
1	A	Longitudinal	60	During the static load deflection was 39,9 mm. Residual deflection was 0,3 mm.
2	A	Transverse	60	During the static load deflection was 44,6 mm. Residual deflection was 1,7 mm.
3	A	Vertical	60	During the static load deflection was 4,1 mm. Residual deflection was 0,5 mm.

After the tests no damage nor oil leak was stated.


4. TESTS RESULTS EVALUATION

According to criteria given in IEC 61869-1:2007 p. 7.4.5 the results of mechanical tests of tested voltage transformer is positive for.


$F_R = 3600 \text{ N}$.

Photographs taken during the tests


ANNEX 1



Phot. 3. Vertical load of A terminal



Phot. 1. Longitudinal load of A terminal



Phot. 4. A terminal after tests



Phot. 2. Transverse load of A terminal

[Handwritten signature]



ANNEX 2

Documentations delivered by orderer



Phot. 5. Voltage transformer after tests



ANNEX 3

Declaration of Conformity

ABB	Declaration of conformity	ABB Sp. z o.o. Depl. in Przasnysz POLAND
DECLARATION OF CONFORMITY No. PL02/2016 (EN) (acc. to ISO/IEC 17050-1)		
Manufacturer:	ABB Sp. z o.o., Leszno 59 Str., 06-300 Przasnysz	
Product:	Voltage Instrument Transformer EMF-E145	
Above mentioned product conforms with the following standard :		
Standard	Title	Edition/Date
IEC 61869 - 3	Voltage Instrument Transformers	2016
Additional information: Serial numbers: 2GGKV1190668, 2GGKV1190669, 2GGKV1190670,		
Place and date of issue of declaration Przasnysz 25.11.2016		
Krzysztof Lubecki Production Protection Manager ABB Sp. z o.o.		Dyrektor Technol. Jednostki Biznesu/Wydział Napięć ABB Sp. z o.o.
Krzysztof Lubecki (Name)		Pawel Szajdecki (Signature)

[Handwritten signature]






ABB Voltage transformer	
Type EMF-E145	S/N 2GGKV1190670
Insulation level 145/275/850 kV	Standard IEC 61869-3
f _n 50Hz F 3,6kN	F _v 1,9 / 8h
Transportation Vertical	Temp. range -40/+40°C
Insulation class A	Year 2016
Attention: Hermetic device, do not unscrew. Oil sampling according to the manufacturer's instruction.	
Total weight 280kg	Oil weight 65kg
Oil type Nynas Nitro Lubrg ISO-L-NTU0-2960130	
1a-1n 115/√3V 100VA R.0,2/3P 1300VAh	
2a-2n 115/√3V 100VA R.0,2/3P 1300VAh	
A-N 145/√3 kV	

[Handwritten mark]

HIGH VOLTAGE LABORATORY



INSTYTUT ENERGETYKI



LABORATORY ACCREDITED
BY THE POLISH CENTRE FOR ACCREDITATION
Accreditation Certificate of Testing Laboratory
No AB 272

TEST REPORT
No EWN/45/E/16

Impulse voltage withstand test on primary terminal,
chopped impulse voltage withstand test on primary terminal,
of voltage instrument transformer type FY145a

Warsaw, May 2016



HIGH VOLTAGE LABORATORY
INSTYTUT ENERGETYKI

01-330 WARSZAWA, ul. Mory 8, tel. (22) 3451242
tel. fax. (22) 8368048, e-mail: ewn@ien.com.pl

EWN/45/E/16

Page 2/8

TEST REPORT EWN/45/E/16

TEST OBJECT: Voltage instrument transformer type PV145a

TEST CUSTOMER: ABB Sp. z o.o.
04-713 Warszawa, ul. Żegańska 1

MANUFACTURER: ABB Sp. z o.o.
04-713 Warszawa, ul. Żegańska 1

ORDER NO: 4500743552 (17.05.2016)

TEST TYPE: Impulse voltage withstand test on primary terminal,
Chopped impulse voltage withstand test on primary terminal

TEST PROCEDURE: According to: PN-EN 61869-1:2009 (IEC 61869-1:2007)
PN-EN 61869-3:2011 (IEC 61869-3:2011)

TEST DATE: 19.05.2016

TEST RESULT: Positive - details are presented in following parts of report

TEST PERFORMERS: Michał Molas, M. Sc. EE

Adam Wielonek, Tech.

AUTHORISATION: Jerzy Mikotajczyk, M. Sc. EE

HEAD OF LABORATORY: J. L. Milkowski, Prof., Ph. D. EE

	Signature
	Signature
	Signature
	Signature

Warsaw, May 2016.

Publication or reproduction of the Report in any other form than a complete copy thereof is forbidden without written consent of the Laboratory



1 COMPETENCE OF THE LABORATORY

The High Voltage Laboratory is in possession of accreditation issued by the Polish Centre for Accreditation (Accreditation Certificate of Testing Laboratory No AB 272) concerning following tests:

- Insulators and insulator strings
 - lightning and switching impulse tests
 - power frequency voltage 50 Hz tests
 - radio interference measurements
- Distribution substations
 - lightning and switching impulse tests
 - power frequency voltage 50 Hz tests
 - radio interference measurements
- Circuit breakers, switches
 - lightning and switching impulse tests
 - power frequency voltage 50 Hz tests
 - radio interference measurements
- Disconnectors
 - lightning and switching impulse tests
 - power frequency voltage 50 Hz tests
 - radio interference measurements
- Current and voltage transformers
 - lightning and switching impulse tests
 - power frequency voltage 50 Hz tests
 - radio interference measurements
- Power transformers
 - lightning and switching impulse tests
 - power frequency voltage 50 Hz tests
- Lightning arresters and limiters
 - lightning and switching impulse tests
 - power frequency voltage 50 Hz tests
- Cables and cable fittings
 - lightning and switching impulse tests
 - power frequency voltage 50 Hz tests
- Line and station fittings
 - radio interference measurements
- Occupational safety equipment
 - power frequency voltage 50 Hz tests

Full scope of accreditation of High Voltage Laboratory available on www.pca.gov.pl

CONTENTS

1	COMPETENCE OF THE LABORATORY	4
2	TEST OBJECT DESCRIPTION	5
3	SCOPE OF TESTS AGREED UPON	6
3.1	Impulse voltage withstand test on primary terminal	7
3.1.1	Method of testing and acceptance criteria	7
3.1.2	Test arrangement	7
3.1.3	Test conditions	7
3.1.4	Test results	8

Test report includes:

- 8 numbered pages;
- 2 figures;
- 1 photograph;
- 3 tables.

Attached to the test report:

- Annex 1: Dimensional drawing (1 page);
- Annex 2: Reports of routine test and determination of errors (8 pages);
- Annex 3: Lightning impulse test protocol (7 pages);



HIGH VOLTAGE LABORATORY
INSTYTUT ENERGETYKI

01-330 WARSZAWA, ul. Mory 8, tel. (22) 3451242
 tel. fax. (22) 8368048, e-mail: ewn@en.com.pl

EWN/45/E/16


Annex 1

ANNEX 1 for test report EWN/45/E/16

(1 page)

Dimensional drawing:

□ ID: 2GKV314360A0001





**HIGH VOLTAGE LABORATORY
INSTYTUT ENERGETYKI**

01-330 WARSZAWA, ul. Mory 8, tel. (22) 3451242
tel. fax. (22) 8368048, e-mail: ewn@ien.com.pl

EWN/45/E/16

Annex 2

ANNEX 2 for test report EWN/45/E/16

(8 pages)

Reports of routine test and determination of errors:

- Routine test report of voltage instrument transformer – before lightning impulse test
- Routine test report of voltage instrument transformer – after lightning impulse test

ABB Sp. z o.o. 06-300 Przasnysz ul. Leszno 69		Routine test report of voltage instrument transformer-before lightning impulse test		TYPE: PV 145a Serial no: 2GKP015V1188086
A-N 145-kV	Insulation level: 145/275/650 kV	Voltage factor: 1.9/8h		IEC 61869-3 50 Hz
Rating 1				
Winding	U_{sn} [kV]	S_{in} [VA]	Class	S_{th} [VA]
1a - 1n	0,115·√3	25	0,1	1500
2a - 2n	0,115·√3	25	0,1	1500
3a - 3n	0,115·√3	25	0,1	1500
da - dn	0,115	100	0,1	1500
			1,0	450
Rating 2				
Winding	U_{sn} [kV]	S_{in} [VA]	Class	S_{th} [VA]
1a - 1n	0,115·√3	25	1,0	1500
2a - 2n	0,115·√3	25	1,0	1500
3a - 3n	0,115·√3	500	1,0	1500
da - dn	0,115	300	1,0	1500
			3P	450

List of performed tests

1. Power-frequency withstand test on primary windings
 2. Partial discharge measurement
 3. Power-frequency withstand test on secondary windings
 4. Determination of errors
 5. Measurement of capacitance and dielectric dissipation factor - tg δ
 6. Measurement of windings' resistance
 7. Rating plate
- A: U_p = 275kV / 60s, f = 120Hz; N: U_p = 3kV / 60s, f = 50Hz
- U_p = 3 kV/60s

Partial discharge measurement

- Measurement according to procedure A (PD test voltages were reached while decreasing the voltage after the power-frequency withstand test on primary winding)
- Stress voltage: 275 kV / 60 s
- Frequency: 120 Hz

Test voltage	1,2 U _m = 174 kV	1,2 U _m / √3 = 100,5 kV
Level of partial discharge	0,6 pC	0,6 pC

- PD inception voltage: 230 kV
- PD extinction voltage: 225 kV

Remarks: background noise level: 0,5 (measured after voltage switch off), measuring circuit was calibrated with 5,1 pC (calibrating charge).

Verification of accuracy (± U%), (Δφ U min) – rating 1

Date of measurement: 2016-05-17
Ambient temperature: 31 +/- 2°C
Relative air humidity: 40 +/- 10%

Rating plate

ABB Voltage transformer

Type: PV 145a S/N: 2GKP015V1188086

Insulation level: 145/275/850 kV Standard: IEC 61869-3

Transportation: Vertical/horizontal F₁: 3.0 / 8.0

Insulation class: A Temp. range: -40/+10°C

Year: 2016

Total weight: 265 kg Oil weight: 62 kg

Oil type: Husko Nycro Libra ISO-L-N100-240030

Przasnysz, 2016-05-17

Checked by: *[Signature]*

Attention: Hermetic device, do not unseal, on opening accuracy is for manufacturer's instruction.

ABB Sp. z o.o. 06-300 Przasnysz ul. Leszno 59		Routine test report of voltage instrument transformer after lightning impulse test		TYPE: PV 145a Serial no: 2GKP015V1188086
A-N 145-3 kV	Insulation level: 145/275/850 kV	Voltage factor: 1.9/8h		IEC 61869-3 50 Hz
Rating 1				
Winding	Usn [kV]	Sn [VA]	Class	Shh [VA]
1a - 1n	0.115-3	25	0.1	1500
2a - 2n	0.115-3	25	0.1	1500
3a - 3n	0.115-3	25	0.1	1500
da - dn	0.115	100	1.0	1500
Rating 2				
Winding	Usn [kV]	Sn [VA]	Class	Shh [VA]
1a - 1n	0.115-3	25	1.0	1500
2a - 2n	0.115-3	25	1.0	1500
3a - 3n	0.115-3	500	1.0	1500
da - dn	0.115	300	3P	450

List of performed tests

1. Power-frequency withstand test on primary windings
 2. Partial discharge measurement
 3. Power-frequency withstand test on secondary windings
 4. Determination of errors
 5. Measurement of capacitance and dielectric dissipation factor - tg δ
 6. Measurement of windings' resistance
 7. Rating plate
- A: Up = 220kV / 60s, f = 120Hz; N: Up = 3kV / 60s, f = 50Hz
- Up = 3 kV/60s

Partial discharge measurement

- Measurement according to procedure A (PD test voltages were reached while decreasing the voltage after the power-frequency withstand test on primary winding)
- Stress voltage: 220 kV / 60 s
- Frequency: 120 Hz

Test voltage	1,2 Um = 174 kV	1,2 Um / 3 = 100.5 kV
Level of partial discharge	1 pC	0.6 pC

- PD inception voltage: >220 kV
- PD extinction voltage: >220 kV

Remarks: background noise level: 0.6 (measured after voltage switch off), measuring circuit was calibrated with 5.1 pC (calibrating charge).

Verification of accuracy (ε U%), (Δφ U min) - rating 1
 Date of measurement: 2016-05-30
 Ambient temperature: 31 +/- 2°C
 Relative air humidity: 40 +/- 10%

1a-1n: 25 VA		1a-1n: 6.25 VA		1a-1n: 6.25 VA		1a-1n: 6.25 VA	
2a-2n: 25VA; 3a-3n: 25VA		2a-2n: 25VA; 3a-3n: 500VA		2a-2n: 0 VA; 3a-3n: 0 VA		2a-2n: 0 VA; 3a-3n: 0 VA	
p.f. = 0.8 lag.		p.f. = 0.8 lag.		p.f. = 0.8 lag.		p.f. = 0.8 lag.	
ε U		0.8 Un		1.0 Un		1.2 Un	
Δφ U		-0.017		-0.016		-0.015	
ε U		0.8 Un		1.0 Un		1.2 Un	
Δφ U		1.8		1.8		1.8	
1a-1n: 6.25 VA		1a-1n: 6.25 VA		1a-1n: 6.25 VA		1a-1n: 6.25 VA	
2a-2n: 25VA; 3a-3n: 25VA		2a-2n: 25VA; 3a-3n: 500VA		2a-2n: 0 VA; 3a-3n: 0 VA		2a-2n: 0 VA; 3a-3n: 0 VA	
p.f. = 0.8 lag.		p.f. = 0.8 lag.		p.f. = 0.8 lag.		p.f. = 0.8 lag.	
ε U		0.8 Un		1.0 Un		1.2 Un	
Δφ U		0.019		0.020		0.021	
ε U		0.8 Un		1.0 Un		1.2 Un	
Δφ U		1.7		1.7		1.7	
1a-1n: 6.25 VA		1a-1n: 6.25 VA		1a-1n: 6.25 VA		1a-1n: 6.25 VA	
2a-2n: 25VA; 3a-3n: 25VA		2a-2n: 25VA; 3a-3n: 500VA		2a-2n: 0 VA; 3a-3n: 0 VA		2a-2n: 0 VA; 3a-3n: 0 VA	
p.f. = 0.8 lag.		p.f. = 0.8 lag.		p.f. = 0.8 lag.		p.f. = 0.8 lag.	
ε U		0.8 Un		1.0 Un		1.2 Un	
Δφ U		-0.023		-0.021		-0.021	
ε U		0.8 Un		1.0 Un		1.2 Un	
Δφ U		1.8		1.7		1.7	

1a-1n: 25 VA		1a-1n: 6.25 VA		1a-1n: 6.25 VA		1a-1n: 6.25 VA	
2a-2n: 25VA; 3a-3n: 25VA		2a-2n: 25VA; 3a-3n: 500VA		2a-2n: 0 VA; 3a-3n: 0 VA		2a-2n: 0 VA; 3a-3n: 0 VA	
p.f. = 0.8 lag.		p.f. = 0.8 lag.		p.f. = 0.8 lag.		p.f. = 0.8 lag.	
ε U		0.8 Un		1.0 Un		1.2 Un	
Δφ U		-0.022		-0.020		-0.019	
ε U		0.8 Un		1.0 Un		1.2 Un	
Δφ U		1.8		1.8		1.8	
1a-1n: 6.25 VA		1a-1n: 6.25 VA		1a-1n: 6.25 VA		1a-1n: 6.25 VA	
2a-2n: 25VA; 3a-3n: 25VA		2a-2n: 25VA; 3a-3n: 500VA		2a-2n: 0 VA; 3a-3n: 0 VA		2a-2n: 0 VA; 3a-3n: 0 VA	
p.f. = 0.8 lag.		p.f. = 0.8 lag.		p.f. = 0.8 lag.		p.f. = 0.8 lag.	
ε U		0.8 Un		1.0 Un		1.2 Un	
Δφ U		0.019		0.020		0.021	
ε U		0.8 Un		1.0 Un		1.2 Un	
Δφ U		1.7		1.7		1.7	

1a-1n: 25 VA		1a-1n: 6.25 VA		1a-1n: 6.25 VA		1a-1n: 6.25 VA	
2a-2n: 25VA; 3a-3n: 25VA		2a-2n: 25VA; 3a-3n: 500VA		2a-2n: 0 VA; 3a-3n: 0 VA		2a-2n: 0 VA; 3a-3n: 0 VA	
p.f. = 0.8 lag.		p.f. = 0.8 lag.		p.f. = 0.8 lag.		p.f. = 0.8 lag.	
ε U		0.8 Un		1.0 Un		1.2 Un	
Δφ U		-0.023		-0.021		-0.021	
ε U		0.8 Un		1.0 Un		1.2 Un	
Δφ U		1.8		1.7		1.7	
1a-1n: 6.25 VA		1a-1n: 6.25 VA		1a-1n: 6.25 VA		1a-1n: 6.25 VA	
2a-2n: 25VA; 3a-3n: 25VA		2a-2n: 25VA; 3a-3n: 500VA		2a-2n: 0 VA; 3a-3n: 0 VA		2a-2n: 0 VA; 3a-3n: 0 VA	
p.f. = 0.8 lag.		p.f. = 0.8 lag.		p.f. = 0.8 lag.		p.f. = 0.8 lag.	
ε U		0.8 Un		1.0 Un		1.2 Un	
Δφ U		0.019		0.020		0.021	
ε U		0.8 Un		1.0 Un		1.2 Un	
Δφ U		1.7		1.7		1.7	

1a-1n: 25 VA		1a-1n: 6.25 VA		1a-1n: 6.25 VA		1a-1n: 6.25 VA	
2a-2n: 25VA; 3a-3n: 25VA		2a-2n: 25VA; 3a-3n: 500VA		2a-2n: 0 VA; 3a-3n: 0 VA		2a-2n: 0 VA; 3a-3n: 0 VA	
p.f. = 0.8 lag.		p.f. = 0.8 lag.		p.f. = 0.8 lag.		p.f. = 0.8 lag.	
ε U		0.8 Un		1.0 Un		1.2 Un	
Δφ U		-0.022		-0.020		-0.019	
ε U		0.8 Un		1.0 Un		1.2 Un	
Δφ U		1.8		1.8		1.8	

1a-1n: 25 VA		1a-1n: 6.25 VA		1a-1n: 6.25 VA		1a-1n: 6.25 VA	
2a-2n: 25VA; 3a-3n: 25VA		2a-2n: 25VA; 3a-3n: 500VA		2a-2n: 0 VA; 3a-3n: 0 VA		2a-2n: 0 VA; 3a-3n: 0 VA	
p.f. = 0.8 lag.		p.f. = 0.8 lag.		p.f. = 0.8 lag.		p.f. = 0.8 lag.	
ε U		0.8 Un		1.0 Un		1.2 Un	
Δφ U		-0.058		-0.056		-0.055	
ε U		0.8 Un		1.0 Un		1.2 Un	
Δφ U		0.7		0.7		0.7	
1a-1n: 6.25 VA		1a-1n: 6.25 VA		1a-1n: 6.25 VA		1a-1n: 6.25 VA	
2a-2n: 25VA; 3a-3n: 25VA		2a-2n: 25VA; 3a-3n: 500VA		2a-2n: 0 VA; 3a-3n: 0 VA		2a-2n: 0 VA; 3a-3n: 0 VA	
p.f. = 0.8 lag.		p.f. = 0.8 lag.		p.f. = 0.8 lag.		p.f. = 0.8 lag.	
ε U		0.8 Un		1.0 Un		1.2 Un	
Δφ U		-0.022		-0.020		-0.019	
ε U		0.8 Un		1.0 Un		1.2 Un	
Δφ U		0.6		0.6		0.6	
1a-1n: 6.25 VA		1a-1n: 6.25 VA		1a-1n: 6.25 VA		1a-1n: 6.25 VA	
2a-2n: 25VA; 3a-3n: 25VA		2a-2n: 25VA; 3a-3n: 500VA		2a-2n: 0 VA; 3a-3n: 0 VA		2a-2n: 0 VA; 3a-3n: 0 VA	
p.f. = 0.8 lag.		p.f. = 0.8 lag.		p.f. = 0.8 lag.		p.f. = 0.8 lag.	
ε U		0.8 Un		1.0 Un		1.2 Un	
Δφ U		-0.064		-0.062		-0.062	
ε U		0.8 Un		1.0 Un		1.2 Un	
Δφ U		0.5		0.5		0.5	
1a-1n: 6.25 VA		1a-1n: 6.25 VA		1a-1n: 6.25 VA		1a-1n: 6.25 VA	
2a-2n: 25VA; 3a-3n: 25VA		2a-2n: 25VA; 3a-3n: 500VA		2a-2n: 0 VA; 3a-3n: 0 VA		2a-2n: 0 VA; 3a-3n: 0 VA	
p.f. = 0.8 lag.		p.f. = 0.8 lag.		p.f. = 0.8 lag.		p.f. = 0.8 lag.	
ε U		0.8 Un		1.0 Un		1.2 Un	
Δφ U		0.5		0.5		0.5	

1a-1n: 25 VA		1a-1n: 6.25 VA		1a-1n: 6.25 VA		1a-1n: 6.25 VA	
2a-2n: 25VA; 3a-3n: 25VA		2a-2n: 25VA; 3a-3n: 500VA		2a-2n: 0 VA; 3a-3n: 0 VA		2a-2n: 0 VA; 3a-3n: 0 VA	
p.f. = 0.8 lag.		p.f. = 0.8 lag.		p.f. = 0.8 lag.		p.f. = 0.8 lag.	
ε U		0.8 Un		1.0 Un		1.2 Un	
Δφ U		-0.063		-0.061		-0.061	
ε U		0.8 Un		1.0 Un		1.2 Un	
Δφ U		0.2		0.3		0.3	
1a-1n: 6.25 VA		1a-1n: 6.25 VA		1a-1n: 6.25 VA		1a-1n: 6.25 VA	
2a-2n: 25VA; 3a-3n: 25VA		2a-2n: 25VA; 3a-3n: 500VA		2a-2n: 0 VA; 3a-3n: 0 VA		2a-2n: 0 VA; 3a-3n: 0 VA	
p.f. = 0.8 lag.		p.f. = 0.8 lag.		p.f. = 0.8 lag.		p.f. = 0.8 lag.	
ε U		0.8 Un		1.0 Un		1.2 Un	
Δφ U		-0.033		-0.032		-0.031	
ε U		0.8 Un		1.0 Un		1.2 Un	
Δφ U		0.4		0.4		0.4	
1a-1n: 6.25 VA		1a-1n: 6.25 VA		1a-1n: 6.25 VA		1a-1n: 6.25 VA	
2a-2n: 25VA; 3a-3n: 25VA		2a-2n: 25VA; 3a-3n: 500VA		2a-2n: 0 VA; 3a-3n: 0 VA		2a-2n: 0 VA; 3a-3n: 0 VA	
p.f. = 0.8 lag.		p.f. = 0.8 lag.		p.f. = 0.8 lag.		p.f. = 0.8 lag.	
ε U		0.8 Un		1.0 Un		1.2 Un	
Δφ U		-0.116		-0.053		0.023	
ε U		0.8 Un		1.0 Un		1.2 Un	
Δφ U		-1.4		-1.0		-0.4	

1a-1n: 25 VA		1a-1n: 6.25 VA		1a-1n: 6.25 VA		1a-1n: 6.25 VA	
2a-2n: 25VA; 3a-3n: 25VA		2a-2n: 25VA; 3a-3n: 500VA		2a-2n: 0 VA; 3a-3n: 0 VA		2a-2n: 0 VA; 3a-3n: 0 VA	
p.f. = 0.8 lag.		p.f. = 0.8 lag.		p.f. = 0.8 lag.		p.f. = 0.8 lag.	
ε U		0.8 Un		1.0 Un		1.2 Un	
Δφ U		-0.033		-0.032		-0.031	
ε U		0.8 Un		1.0 Un		1.2 Un	
Δφ U		0.4		0.4		0.4	
1a-1n: 6.25 VA		1a-1n: 6.25 VA		1a-1n: 6.25 VA		1a-1n: 6.25 VA	
2a-2n: 25VA; 3a-3n: 25VA		2a-2n: 25VA; 3a-3n: 500VA		2a-2n: 0 VA; 3a-3n: 0 VA		2a-2n: 0 VA; 3a-3n: 0 VA	
p.f. = 0.8 lag.		p.f. = 0.8 lag.		p.f. = 0.8 lag.		p.f. = 0.8 lag.	
ε U		0.8 Un		1.0 Un		1.2 Un	
Δφ U		-0.033		-0.032		-0.031	
ε U		0.8 Un		1.0 Un		1.2 Un	
Δφ U		0.4		0.4		0.4	

1a-1n: 25 VA		1a-1n: 6.25 VA		1a-1n: 6.25 VA		1a-1n: 6.25 VA	
2a-2n: 25VA; 3a-3n: 25VA		2a-2n: 25VA; 3a-3n: 500VA		2a-2n: 0 VA; 3a-3n: 0 VA		2a-2n: 0 VA; 3a-3n: 0 VA	
p.f. = 0.8 lag.		p.f. = 0.8 lag.		p.f. = 0.8 lag.		p.f. = 0.8 lag.	
ε U		0.8 Un		1.0 Un		1.2 Un	
Δφ U		-0.433		-0.431		-0.431	
ε U		0.8 Un		1.0 Un		1.2 Un	
Δφ U		-9.6		-9.6		-9.5	

Measurements uncertainty: $U_{res} = \pm 0.015\%$, $U_{loss} = \pm 1.5\%$ min

Verification of accuracy ($\epsilon U\%$), ($\Delta\phi U$ min) - rating 2
 Date of measurement: 2016-05-30
 Ambient temperature: 31 +/- 2°C
 Relative air humidity: 40 +/- 10%

Measurement of capacitance and dielectric dissipation factor - tg δ
 Temperature: 26 °C, Frequency: 50 Hz

Primary voltage	Iq δ	Capacity	Leak current
10 kV	0.2	239	0.895
63 kV	0.2	239	6.316
71 kV	0.2	239	6.868

Measurement of windings' resistance

	R (28 °C)	Rct (20 °C)	Rct (75 °C)
A-N	18.50 kΩ	17.918 kΩ	21.917 kΩ
1a-1n	53.7 mΩ	52.012 mΩ	63.618 mΩ
2a-2n	52 mΩ	50.365 mΩ	61.605 mΩ
3a-3n	33.8 mΩ	32.737 mΩ	40.043 mΩ
6a-6n	147.6 mΩ	142.959 mΩ	174.863 mΩ

223

224

Rating plate

ABB Voltage transformer

Type PV 145a S/N 20KPO15V1188086

Insulation level 145/225/650 kV Standard IEC 61860-3


% 50Hz F 3.5 IAR FV 1.5 / BR

Transportation: vertical/horizontal

Insulation class A Temp. range -40/+40°C


Year 2018

Attention: Handle device, do not unseal. Oil sampling according to the manufacturer's instruction.

Checked by: 

1a-1p	115/33	23VA	M.01	1500VAB
2a-2b	115/33	23VA	M.01	1500VAB
3a-3b	115/33	23VA	M.01	1500VAB
4a-4b	115/33	23VA	M.01	1500VAB
5a-5b	115/33	23VA	M.01	1500VAB
6a-6b	115/33	23VA	M.01	1500VAB
7a-7b	115/33	23VA	M.01	1500VAB
8a-8b	115/33	23VA	M.01	1500VAB
9a-9b	115/33	23VA	M.01	1500VAB
10a-10b	115/33	23VA	M.01	1500VAB
11a-11b	115/33	23VA	M.01	1500VAB
12a-12b	115/33	23VA	M.01	1500VAB
13a-13b	115/33	23VA	M.01	1500VAB
14a-14b	115/33	23VA	M.01	1500VAB
15a-15b	115/33	23VA	M.01	1500VAB
16a-16b	115/33	23VA	M.01	1500VAB
17a-17b	115/33	23VA	M.01	1500VAB
18a-18b	115/33	23VA	M.01	1500VAB
19a-19b	115/33	23VA	M.01	1500VAB
20a-20b	115/33	23VA	M.01	1500VAB
21a-21b	115/33	23VA	M.01	1500VAB
22a-22b	115/33	23VA	M.01	1500VAB
23a-23b	115/33	23VA	M.01	1500VAB
24a-24b	115/33	23VA	M.01	1500VAB
25a-25b	115/33	23VA	M.01	1500VAB
26a-26b	115/33	23VA	M.01	1500VAB
27a-27b	115/33	23VA	M.01	1500VAB
28a-28b	115/33	23VA	M.01	1500VAB
29a-29b	115/33	23VA	M.01	1500VAB
30a-30b	115/33	23VA	M.01	1500VAB
31a-31b	115/33	23VA	M.01	1500VAB
32a-32b	115/33	23VA	M.01	1500VAB
33a-33b	115/33	23VA	M.01	1500VAB
34a-34b	115/33	23VA	M.01	1500VAB
35a-35b	115/33	23VA	M.01	1500VAB
36a-36b	115/33	23VA	M.01	1500VAB
37a-37b	115/33	23VA	M.01	1500VAB
38a-38b	115/33	23VA	M.01	1500VAB
39a-39b	115/33	23VA	M.01	1500VAB
40a-40b	115/33	23VA	M.01	1500VAB
41a-41b	115/33	23VA	M.01	1500VAB
42a-42b	115/33	23VA	M.01	1500VAB
43a-43b	115/33	23VA	M.01	1500VAB
44a-44b	115/33	23VA	M.01	1500VAB
45a-45b	115/33	23VA	M.01	1500VAB
46a-46b	115/33	23VA	M.01	1500VAB
47a-47b	115/33	23VA	M.01	1500VAB
48a-48b	115/33	23VA	M.01	1500VAB
49a-49b	115/33	23VA	M.01	1500VAB
50a-50b	115/33	23VA	M.01	1500VAB
51a-51b	115/33	23VA	M.01	1500VAB
52a-52b	115/33	23VA	M.01	1500VAB
53a-53b	115/33	23VA	M.01	1500VAB
54a-54b	115/33	23VA	M.01	1500VAB
55a-55b	115/33	23VA	M.01	1500VAB
56a-56b	115/33	23VA	M.01	1500VAB
57a-57b	115/33	23VA	M.01	1500VAB
58a-58b	115/33	23VA	M.01	1500VAB
59a-59b	115/33	23VA	M.01	1500VAB
60a-60b	115/33	23VA	M.01	1500VAB
61a-61b	115/33	23VA	M.01	1500VAB
62a-62b	115/33	23VA	M.01	1500VAB
63a-63b	115/33	23VA	M.01	1500VAB
64a-64b	115/33	23VA	M.01	1500VAB
65a-65b	115/33	23VA	M.01	1500VAB
66a-66b	115/33	23VA	M.01	1500VAB
67a-67b	115/33	23VA	M.01	1500VAB
68a-68b	115/33	23VA	M.01	1500VAB
69a-69b	115/33	23VA	M.01	1500VAB
70a-70b	115/33	23VA	M.01	1500VAB
71a-71b	115/33	23VA	M.01	1500VAB
72a-72b	115/33	23VA	M.01	1500VAB
73a-73b	115/33	23VA	M.01	1500VAB
74a-74b	115/33	23VA	M.01	1500VAB
75a-75b	115/33	23VA	M.01	1500VAB
76a-76b	115/33	23VA	M.01	1500VAB
77a-77b	115/33	23VA	M.01	1500VAB
78a-78b	115/33	23VA	M.01	1500VAB
79a-79b	115/33	23VA	M.01	1500VAB
80a-80b	115/33	23VA	M.01	1500VAB
81a-81b	115/33	23VA	M.01	1500VAB
82a-82b	115/33	23VA	M.01	1500VAB
83a-83b	115/33	23VA	M.01	1500VAB
84a-84b	115/33	23VA	M.01	1500VAB
85a-85b	115/33	23VA	M.01	1500VAB
86a-86b	115/33	23VA	M.01	1500VAB
87a-87b	115/33	23VA	M.01	1500VAB
88a-88b	115/33	23VA	M.01	1500VAB
89a-89b	115/33	23VA	M.01	1500VAB
90a-90b	115/33	23VA	M.01	1500VAB
91a-91b	115/33	23VA	M.01	1500VAB
92a-92b	115/33	23VA	M.01	1500VAB
93a-93b	115/33	23VA	M.01	1500VAB
94a-94b	115/33	23VA	M.01	1500VAB
95a-95b	115/33	23VA	M.01	1500VAB
96a-96b	115/33	23VA	M.01	1500VAB
97a-97b	115/33	23VA	M.01	1500VAB
98a-98b	115/33	23VA	M.01	1500VAB
99a-99b	115/33	23VA	M.01	1500VAB
100a-100b	115/33	23VA	M.01	1500VAB

Przasnysz, 2016-05-30



HIGH VOLTAGE LABORATORY
INSTYTUT ENERGETYKI
 01-330 WARSZAWA, ul. Mory 8, tel. (22) 3451242
 tel. fax. (22) 8368048, e-mail: ewn@ien.com.pl

EWN/45/E/16
 Annex 3

ANNEX 3 for test report EWN/45/E/16
 (8 pages)

Lightning impulse test protocol:
 □ ewn45e16



Test - object - data

WNR ewn45e16 TR-No. 2GKP0115V118808D.-No. 4500743552

test object PV145a vector group BIL 650
output kVA
voltage 145 KV frequency 50 Hz

customer ABB Sp. z o. o. ul. Żegamska 1, 04-713 Warszawa

Li lightning-impulso

no.	Up [kV]	T1[µs]	T2[µs]	Tc[µs]	Ip [A]	remark
1	-325.3	1.22	45.4		-363.6	LI: A - RW(50.0%)
2	-648.1	1.23	45.8		-453	LI: A - FW(100.0%)
3	-375	1.22		3.48	-625.2	LI: A - CRW(57.5%)
4	-744.8	1.24		3.44	-1122	LI: A - CFW(115.0%)
5	-745.3	1.24		3.4	-1123	LI: A - CFW(115.0%)
6	-647.7	1.23	45.7		-537.8	LI: A - FW(100.0%)
7	-648	1.23	45.8		-361.4	LI: A - FW(100.0%)
8	-648.2	1.23	45.8		-393.7	LI: A - FW(100.0%)
9	-648.3	1.23	45.8		-412.2	LI: A - FW(100.0%)
10	-648	1.23	45.8		-493.4	LI: A - FW(100.0%)
11	-646.9	1.24	45.9		-465.1	LI: A - FW(100.0%)
12	-648	1.23	45.9		-531.1	LI: A - FW(100.0%)
13	-648.3	1.23	45.8		-498.6	LI: A - FW(100.0%)
14	-648.2	1.23	45.9		-305.8	LI: A - FW(100.0%)
15	-648.2	1.23	45.9		-346.5	LI: A - FW(100.0%)
16	-648.7	1.23	45.8		-394.9	LI: A - FW(100.0%)
17	-648.9	1.23	45.8		-353	LI: A - FW(100.0%)
18	-648.1	1.23	45.9		-481.3	LI: A - FW(100.0%)
19	-648	1.23	45.8		-460	LI: A - FW(100.0%)
20	323.8	1.23	45.5		326.4	LI: A - RW(50.0%)
21	649.9	1.23	45.9		425.5	LI: A - FW(100.0%)
22	650.2	1.23	45.8		364.9	LI: A - FW(100.0%)
23	650.2	1.23	45.6		424.7	LI: A - FW(100.0%)
24	649.5	1.23	45.9		476.2	LI: A - FW(100.0%)
25	649.9	1.23	45.9		323.1	LI: A - FW(100.0%)
26	649.9	1.22	45.8		433.1	LI: A - FW(100.0%)
27	649.6	1.23	45.9		538.4	LI: A - FW(100.0%)
28	649.4	1.23	45.9		349.9	LI: A - FW(100.0%)
29	649.3	1.23	45.7		396.1	LI: A - FW(100.0%)



30	649.2	1.23	45.9	367.3	LI: A - FW(100.0%)
31	649.1	1.22	45.9	459.3	LI: A - FW(100.0%)
32	649.6	1.22	45.9	376.5	LI: A - FW(100.0%)
33	648.6	1.22	45.9	343.2	LI: A - FW(100.0%)
34	648.1	1.23	45.9	540.2	LI: A - FW(100.0%)
35	648.8	1.23	45.8	396.1	LI: A - FW(100.0%)

225

226




HIGH VOLTAGE LABORATORY

POLAND 01-330 WARSZAWA, ul. Mory 8
fax: (+4822) 836-80-48, mail: ewn@len.com.pl

project : ewn45e16

page 3




HIGH VOLTAGE LABORATORY

POLAND 01-330 WARSZAWA, ul. Mory 8
fax: (+4822) 836-80-48, mail: ewn@len.com.pl

project : ewn45e16

page 4






HIGH VOLTAGE LABORATORY

POLAND 01-330 WARSZAWA, ul. Mory 8
fax: (+4822) 836-80-48, mail: ewn@en.com.pl

project: ewn45e16

page 5



[Handwritten signature]
227




HIGH VOLTAGE LABORATORY

POLAND 01-330 WARSZAWA, ul. Mory 8
fax: (+4822) 836-80-48, mail: ewn@en.com.pl


project: ewn45e16

page 6



[Handwritten signature]

HIGH VOLTAGE LABORATORY



INSTYTUT ENERGETYKI



LABORATORY ACCREDITED
BY THE POLISH CENTRE FOR ACCREDITATION
Accreditation Certificate of Testing Laboratory
No AB 272

TEST REPORT
No EWN/109/E/15-1

Impulse voltage withstand test on primary terminal,
chopped impulse voltage withstand test on primary terminal,
transmitted overvoltage test,
discharge capacitor test
of voltage instrument transformer type EMF-EI23

Warsaw, October 2015



HIGH VOLTAGE LABORATORY INSTYTUT ENERGETYKI

01-330 WARSZAWA, ul. Mory 8, tel. (22) 3451242
tel. fax. (22) 8368048, e-mail: ewn@enl.com.pl

EWN/109/E/15-1

Page 2/13

TEST REPORT EWN/109/E/15-1

TEST OBJECT: Voltage instrument transformer type EMF-EI23

TEST CUSTOMER: ABB Sp. z o.o.
04-713 Warszawa, ul. Żegalska 1

MANUFACTURER: ABB

ORDER NO: 4500678253 (15.09.2015)

TEST TYPE: Impulse voltage withstand test on primary terminal,
Chopped impulse voltage withstand test on primary terminal,
Transmitted overvoltage test,
Discharge capacitor test

TEST PROCEDURE: According to: PN-EN/IEC 61869-1
PN-EN/IEC 61869-3
Internal ABB specifications

TEST DATE: 05.10.2015 – 14.10.2015

TEST RESULT: POSITIVE - details are presented in following parts of report

TEST PERFORMERS: Michał Molas, M. Sc. EE

Adam Wielonek, Tech.

AUTHORISATION: Jerzy Mikotańczyk, M. Sc. EE

HEAD OF LABORATORY: J. L. Mikulski, Prof., Ph. D. EE

	Signature
	Signature
	Signature
	Signature

Warsaw, October 2015.
Publication or reproduction of the Report in any other form than a complete copy thereof is forbidden without written consent of the Laboratory



HIGH VOLTAGE LABORATORY
INSTYTUT ENERGETYKI

01-330 WARSZAWA, ul. Mory 8, tel. (22) 3451242
tel. fax. (22) 8368048, e-mail: ewn@ten.com.pl

EWN/109/E/15-1

Page 3/13

CONTENTS

1	COMPETENCE OF THE LABORATORY	4
2	TEST OBJECT DESCRIPTION	5
3	SCOPE OF TESTS AGREED UPON	6
4	TYPE TEST	7
4.1	Impulse voltage withstand test on primary terminal	7
4.1.1	Method of testing and acceptance criteria	7
4.1.2	Test arrangement	7
4.1.3	Test conditions	7
4.1.4	Test results	9
5	SPECIAL TESTS	9
5.1	Chopped impulse test on the primary winding	9
5.2	Transmitted overvoltage test	9
5.2.1	Method of testing and acceptance criteria	9
5.2.2	Test arrangement	9
5.2.3	Test conditions	10
5.2.4	Test results	11
6	ADDITIONAL TESTS	11
6.1	Discharge capacitor test	11
6.1.1	Method of testing and acceptance criteria	11
6.1.2	Test arrangement	12
6.1.3	Test conditions	12
6.1.4	Test results	12

Test report includes:

13	numbered pages;
4	figures;
1	photograph;
7	tables.

Attached to the test report:

- Annex 1: Documents provided by ABB Sp. z o.o. used as base of identification of test object (3 pages);
- Annex 2: Reports of routine test and determination of errors (8 pages);
- Annex 3: Lightning impulse test protocol (3 pages);
- Annex 4: Transmitted overvoltage test protocol (4 pages);



HIGH VOLTAGE LABORATORY
INSTYTUT ENERGETYKI

01-330 WARSZAWA, ul. Mory 8, tel. (22) 3451242
tel. fax. (22) 8368048, e-mail: ewn@ten.com.pl

EWN/109/E/15-1

Page 4/13

1 COMPETENCE OF THE LABORATORY


The High Voltage Laboratory is in possession of accreditation issued by the Polish Centre for Accreditation (Accreditation Certificate of Testing Laboratory No AB 272) concerning following tests:

Insulators and insulator strings	- lightning and switching impulse tests
	- power frequency voltage 50 Hz tests
	- radio interference measurements
Distribution substations	- lightning and switching impulse tests
	- power frequency voltage 50 Hz tests
	- radio interference measurements
Circuit breakers, disconnectors	- lightning and switching impulse tests
	- power frequency voltage 50 Hz tests
	- radio interference measurements
Insulators	- lightning and switching impulse tests
	- power frequency voltage 50 Hz tests
	- radio interference measurements
<u>Current and voltage transformers</u>	- <u>lightning and switching impulse tests</u>
	- <u>power frequency voltage 50 Hz tests</u>
Power transformers	- lightning and switching impulse tests
	- power frequency voltage 50 Hz tests
Lightning arresters and limiters	- lightning and switching impulse tests
	- power frequency voltage 50 Hz tests
Cables and cable fittings	- lightning and switching impulse tests
	- power frequency voltage 50 Hz tests
Line and station fittings	- radio interference measurements
Occupational safety equipment	- power frequency voltage 50 Hz tests

Full scope of accreditation of High Voltage Laboratory available on www.pca.gov.pl

Note


Tests described in sub-clauses 5.2 and 6.1 of this Report don't comply with the scope of Laboratory accreditation.

	HIGH VOLTAGE LABORATORY INSTYTUT ENERGETYKI 01-330 WARSZAWA, ul. Mory 8, tel. (22) 3451242 tel. fax. (22) 8368048, e-mail: ewn@ten.com.pl	EWN/109/E/15-1
		Page 5/13

2 TEST OBJECT DESCRIPTION

The tested objects was instrument transformer type EMF-E123 manufactured by ABB sp. z o.o. 04-713 Warszawa, Żegańska 1 St. (Fabryka Aparatury Wysokich i Średnich Napięć, 06-300 Przasnysz, Leszno 59 St.), with the following parameters:

- Prototype 3 – EMF-E123
 Serial number: 1HSE8851774
- Highest voltage for equipment 126 kV
 - Rated primary voltage 115000 / $\sqrt{3}$ V
 - Insulation level 230 / 550 kV
 - Frequency 50 Hz
 - Temperature range -40 – +40 °C
 - Total mass 248 kg



Phot. 1: Tested voltage transformer EMF-E123

	HIGH VOLTAGE LABORATORY INSTYTUT ENERGETYKI 01-330 WARSZAWA, ul. Mory 8, tel. (22) 3451242 tel. fax. (22) 8368048, e-mail: ewn@ten.com.pl	EWN/109/E/15-1
		Page 6/13

3 SCOPE OF TESTS AGREED UPON

Test plan for voltage instrument transformer type EMF-E123 was consulted with the Customer. Tab. 1 includes the list of performed tests and requirements, which tested object should comply with.

Tab. 1: Scope of tests of voltage instrument transformer


Item	Performed tests	Requirement
TYPE TESTS		
1	Impulse voltage withstand test on primary terminal	PN-EN/IEC 61869-1, p.7.2.3
SPECIAL TESTS		
2	Chopped impulse voltage test on primary terminal	PN-EN/IEC 61869-1, p.7.4.1
3	Transmitted overvoltage test	PN-EN/IEC 61869-1, p.7.4.4
ADDITIONAL TESTS		
4	Discharge capacitor test	C=6µF, U=1.1· $\sqrt{2}$ ·115/ $\sqrt{3}$ No breakdown and temperature rise over 65 K.

Determination of errors of transformer, performed to prove the positive results of consecutive tests, was carried out on the premises of Factory Laboratory of ABB Sp. z o.o. in the presence of a representative of the High Voltage Department of Institute of Power Engineering. Detailed results are presented in Annex 2.

Tests were carried out according to:

- IEC 61869-1:2007 „Instrument transformers - Part 1: General requirements” (equiv. with: PN-EN 61869-1:2009 “Przekładniki – Część 1: Wymagania ogólne”)
- IEC 61869-3:2011 „Instrument transformers - Part 3: Additional requirements for inductive voltage transformers” (equiv. with: PN-EN 61869-3:2011 “Przekładniki – Część 3: Wymagania szczególne dotyczące przekładników napięciowych indukcyjnych”)

232



HIGH VOLTAGE LABORATORY
INSTYTUT ENERGETYKI
 01-330 WARSZAWA, ul. Mory 8, tel. (22) 3451242
 tel. fax. (22) 8368048, e-mail: ewn@ien.com.pl

EWN/109/E/15-1
 Page 7/13

4 TYPE TEST

4.1 Impulse voltage withstand test on primary terminal

4.1.1 Method of testing and acceptance criteria

According to IEC 61869-1 clause 7.4.1 lightning impulse test (for negative polarity) can be combined with chopped impulse voltage test. For positive polarity lightning impulse test was performed according to IEC 61869-1 clause 7.2.3 (1.5 impulse method).

It is considered that the instrument transformer passed the test with a positive result if analysis of the waveforms recorded during the test does not indicate failure of internal insulation of instrument transformer.

4.1.2 Test arrangement

Arrangement for testing with full lightning impulse 1,2/50 μs and chopped lightning impulse was based on Marx impulse generator made by HAEFELY. Voltage measurement was performed with impulse voltage measuring system Dr Strauss TR-AS 200-14, in connection with a capacitive voltage divider (impulse peak value measuring uncertainty doesn't exceed 2% of the measured value for the confidence interval 95% and coverage factor k=2). Simplified diagram of the measurement system is shown in the Fig. 1.





Fig. 1: Simplified diagram of the lightning impulse measurement system (for one step of the generator):
 IG - impulse generator; VD - voltage divider; G, R_g, R_{ch} - generator elements; CD - chopping device;
 IT - instrument transformer (general schematic representation); R_{det}, R_{ch} - detection resistance

4.1.3 Test conditions

Test conditions for full lightning impulse 1,2/50 μs test and chopped lightning impulse test (parameters of the measurement system, values of test voltages and sequence of impulses applications) are presented in Tab. 2 and Tab. 3. The influence of atmospheric condition on test voltage value was not taken into consideration.



HIGH VOLTAGE LABORATORY
INSTYTUT ENERGETYKI
 01-330 WARSZAWA, ul. Mory 8, tel. (22) 3451242
 tel. fax. (22) 8368048, e-mail: ewn@ien.com.pl

EWN/109/E/15-1
 Page 8/13

Tab. 2: Parameters of the lightning impulse measurement system

IMPULSE GENERATOR	
Number of steps	n - 5
General capacitance	C _g μF 0,150
Discharge resistance	R _d Ω 445
Damping resistance	R ₁ Ω 160
VOLTAGE DIVIDER	
HV unit capacitance	C ₁ ' pF ~1200
LV unit capacitance	C ₁ '' μF 1,103
Scale factor	ϕ _v - 927,0
DETECTION RESISTORS	
Detection resistance	R _{det} Ω 0,707
	R _{ch} Ω 2,970

Tab. 3: Values of test voltages and sequence of impulses applications

Full impulse test voltage	RW = 275 kV FW = 550 kV
Chopped impulse test voltage	CRW = 316,25 kV CFW = 478,26 kV
Sequence of impulses	Positive polarity 1 reduced full impulse (RW), 15 full impulses (FW). Negative polarity 1 reduced full impulse (RW), 1 full impulse (FW), 1 reduced chopped impulse (CRW), 2 chopped impulses (CFW), 14 full impulses (FW).
Registration	Transients of test voltage (channel 1) Current flowing through secondary winding 1a-1n (channel 2) Current flowing through primary winding screen E (channel 3)




Fig. 2. Simplified diagram of the transmitted overvoltage measurement system IG – impulse generator; VD – voltage divider; C_f , R_f – generator elements; C_s – front shaping capacitor; IT – instrument transformer (general schematic representation);

5.2.3 Test conditions

Test conditions for transmitted overvoltage test (parameters of the measurement system and value of test voltage) are presented in Tab. 4. The influence of atmospheric condition on test voltage value was not taken into consideration.

Tab. 4. Parameters of the transmitted overvoltage measurement system and parameters of the test voltage

IMPULSE GENERATOR	
Number of steps	n - 1
General capacitance	C_f μF 0,750
Discharge resistance	R_f Ω 150
Damping resistance	R_d Ω 89
VOLTAGE DIVIDER	
HV unit resistance	R_{c1} Ω 10098,96
LV unit resistance	R_{c2} Ω 10,06
Scale factor	ϕ_v - 1005
FRONT SHAPING CAPACITOR	
Front shaping capacitor	C_s pF 500
PARAMETERS OF THE TEST VOLTAGE	
Peak value of applied voltage	U_1 kV 16,3
Conventional front time	T_1 μs 0,48
Time to half-value	T_2 μs 73

[Handwritten signature]

4.1.4 Test results

Oscillograms registered during the tests don't indicate any failures of the transformers' insulation (Annex 3). Comparison of the accuracy verification before and after the lightning impulse test of the transformers don't indicate significant changes of the transformers' metrological characteristics (Annex 2).

TEST RESULT: POSITIVE

5 SPECIAL TESTS

5.1 Chopped impulse voltage withstand test on primary terminal

Chopped impulse test on the primary winding was combined with the negative polarity lightning impulse test. Detailed results of this test are presented in Section 4.1 and Annex 3 of this report.

TEST RESULT: POSITIVE

5.2 Transmitted overvoltage test

5.2.1 Method of testing and acceptance criteria

Transmitted overvoltage test was performed according to IEC 61869-3, IEC 61869-1 clause 7.4.4 and 6.11.4. During the test type „A” impulse (U_1) was applied between the primary terminal A and earth. Measurements of transmitted voltage (U_2) were carried out for all the secondary windings of the voltage instrument transformer.

It is considered that the instrument voltage transformer passed the test with a positive result if the value of the transmitted voltage (U_2) does not exceed 1.6 kV (IEC 61869-3 clause 6.11.4 Table 9).

5.2.2 Test arrangement

Arrangement for transmitted overvoltage measurement was based on one step of Marx impulse generator made by HAEFELY. Measurement of the voltage U_1 applied to the primary terminal of the instrument transformer was performed with impulse voltage measuring system Dr. Strauss TR-AS 200-14, in connection with a resistive voltage divider Siemens SMR 10/770. The transmitted voltage U_2 measurement was also performed with impulse voltage measuring system Dr. Strauss TR-AS 200-14. For both measured voltages U_1 and U_2 impulse peak value measuring uncertainty doesn't exceed 2% of the measured value for the confidence interval 95% and coverage factor $k=2$. Simplified diagram of the measurement system is shown in the Fig. 2.

[Handwritten signature]

5.2.4 Test results

Results of the transmitted overvoltage measurement are presented in Tab. 5. The oscillograms of all applied and registered impulses are present in Annex 4 of hereby Report.

Tab. 5: Transmitted overvoltage measurement results

terminal	U ₁ kV	U ₂ V	U ₃ V	U ₄ V	U ₅ %
1a - 1n	16,29	129	1272,5		79,5
2a - 2n	16,27	135	1333,3		83,3
3a - 3n	16,25	133	1315,2		82,2
4a - 4n	16,32	111	1092,9		68,3
da - dn	16,27	88	869,1		54,3

Note:
 U₁ - peak value of applied voltage
 U₂ - maximal value of transmitted voltage
 U₃ - maximal value of transmitted voltage
 U₄ - specified overvoltage U_p=1,6·U_m·√2/√3
 U₅ - percent of permissible overvoltage U_{res}=U₄/1600·100%

TEST RESULT: POSITIVE

6 ADDITIONAL TESTS

6.1 Discharge capacitor test

6.1.1 Method of testing and acceptance criteria

Discharge capacitor test was performed according to internal ABB specifications. Test consists of ten capacitor discharges. Before tests and before each discharge the resistance of winding was measured and rise of the temperature was calculated. The discharges were performed at two-minute intervals (the shortest possible time required to complete measurements and charge the capacitor). In order to determine the cooling characteristics of the transformer additional measurements were performed (3 measurements of the resistance of winding performed within 15 minutes after the last discharge). It is considered that the instrument voltage transformer passed the test with a positive result if:

- calculated rise of the temperature is less than 65 K;
- instrument transformer behavior during testing does not indicate any damages;
- there was no damage of instrument transformer after the test;
- metrological properties of instrument transformer after the test are comply assigned accuracy classes.

6.1.2 Test arrangement

Discharge capacitor test was carried out in a measuring system shown in the Fig. 3. For the measured arithmetic mean voltage values uncertainty in this system doesn't exceed 2% of the measured value for the confidence interval 95% and coverage factor k=2.




Fig. 3: Simplified diagram of the discharge capacitor measurement system: HT - high voltage transformer; HR - high voltage rectifier; VD - voltage divider; C - discharge capacitor; R_p - dumping resistance (R_p=14,5 Ω);

6.1.3 Test conditions

Test conditions for discharge capacitor test are presented in Tab. 6.

Ambient temperature	°C	6,1
Air pressure	hPa	1013
Relative humidity	%	50,0
Winding temperature	°C	6,1±1
Test voltage	kV	1,1·11,5·√2/√3 = 103,3
Capacitance	µF	6

6.1.4 Test results

Results of the discharge capacitor test are presented in Tab. 7.

Tab. 7: Rise of the temperature during discharge capacitor test

t	min	0	2	4	6	8	10	12	14	16	18	20	22	24	26
R	Ω	13040	13190	13360	13470	13620	13740	13860	13990	14100	14200	14310	14420	14530	14660
ΔR	Ω	0	150	320	430	580	700	840	950	1060	1160	1270	1390	1510	1660
ΔT	°C	0,0	2,9	6,1	8,0	10,8	12,8	15,3	17,1	18,9	20,6	22,4	24,3	26,2	30,2



HIGH VOLTAGE LABORATORY
INSTYTUT ENERGETYKI
01-330 WARSZAWA, ul. Mory 8, tel. (22) 3451242
tel. fax. (22) 8368048, e-mail: ewn@ien.com.pl

EWN/109/E/15-1

Annex 1



HIGH VOLTAGE LABORATORY
INSTYTUT ENERGETYKI
01-330 WARSZAWA, ul. Mory 8, tel. (22) 3451242
tel. fax. (22) 8368048, e-mail: ewn@ien.com.pl

EWN/109/E/15-1

Page 13/13




Fig. 4: Rise of the temperature during discharge capacitor test

TEST RESULT: POSITIVE

ANNEX 1 for test report EWN/109/E/15-1

(3 pages)

Documents provided by ABB Sp. z o.o. used as base of identification of test

object:

- Declaration of conformity – No. 100/2015 (EN),
- Rating plate – Document No. 1HSE 22040-PCC,
- Technical drawing – Document id. 1HSE8851774.

235

236


ABB	Declaration of conformity	ABB Sp. z o.o. Dept. In Przysnysz POLAND
DECLARATION OF CONFORMITY No. 100/2015 (EN) (acc. to ISO/IEC 17050-1)		
Manufacturer:	ABB	
Product:	Voltage Instrument Transformer EMF-E123	
Above mentioned product conforms with the following standard :		
Standard	Title	Edition/Date
IEC 61869 - 3	Voltage Instrument Transformers	2015
Additional information:		
Serial numbers: 1HSE 8851774;		
Place and date of issue of declaration		
Przysnysz 05.10.2015		
 (Name)	Kierownik Operacyjny PPHV ABB Sp. z o.o. Oddział w Przysnyszu (Signature)	Kierownik ds. Zaspiegania i Jakości ABB Sp. z o.o. Oddział w Przysnyszu Krzysztof Lubacki

ABB ABB AB

Voltage transformer EMF-E123

Serial number Production year

Type Made in Sweden

Rated primary voltage Frequency

Highest voltage for equipment Temperature range

Total mass

1HSE 88504-5

Serial number: 1HSE 88504-5

Insulation oil: (IEC 61039) LINTOS-298) 80 kg

Voltage factor: 1.5 / 4h

Terminal	Voltage V	Class	Burden VA	Total burden VA	Thermal limit VA
A-N	11500/√3	0.1	25	100	1000+0
1a-1a	115/√3	0.1	25	575	1000+0
2a-2a	115/√3	0.1	25	575	1000+0
3a-3a	115/√3	0.1	25	575	1000+0
4a-4a	115/√3	0.1	25	575	1000+0
1b-1b	115/√3	0.2/3P	500	1000	1000+0
2b-2b	115/√3	0.2/3P	500	1000	1000+0
3b-3b	115/√3	0.2/3P	500	1000	1000+0
4b-4b	115/√3	0.2/3P	500	1000	1000+0
1c-1c	115	1.0	100	375	450+0
2c-2c	115	1.0	100	375	450+0

Serial number 1HSE mmmmm = 1HSE 8851774
 Production year yyyy = Actual year for production

Proposed	Responsible department	Title
Approved	File over department	Rating plate
Revision	Order No.	Language
B	E90000012-30	CEL
	Document No.	Sheet
	1HSE 22040-PCC	1
		1

This document is issued by means of a computerized system. The digitally signed data is electronically approved. The approved document has a date entered in the Approved field. A manual signature is not required.



HIGH VOLTAGE LABORATORY
INSTYTUT ENERGETYKI
 01-330 WARSZAWA, ul. Mory 8, tel. (22) 3451242
 tel. fax. (22) 8368048, e-mail: ewn@en.com.pl

EWN/109/E/15-1

Annex 2


ANNEX 2 for test report EWN/109/E/15-1

(8 pages)

Reports of routine test and determination of errors:

- Routine test report of voltage instrument transformer EMF-123 (1HSE8851774),
- Routine test report of voltage instrument transformer EMF-123 (1HSE8851774) after lightning impulse,

[Handwritten signature]



Verification of accuracy ϵ U%, Δp U (min)

Date of measurement: 2015-10-01

Ambient temperature: 24 +/-

Relative air humidity: 28 +/-

1a-1n: 25 VA		1a-1n: 25 VA		1a-1n: 25 VA		p.f. = 0,8 lag.	
2a-2n: 25VA; 3a-3n: 500VA; 4a-4n: 25VA		2a-2n: 0 VA; 3a-3n: 0 VA; 4a-4n: 0 VA		2a-2n: 0 VA; 3a-3n: 0 VA; 4a-4n: 0 VA		p.f. = 0,8 lag.	
ϵ U	0,8 Un	1,0 Un	1,0 Un	1,0 Un	1,0 Un	1,0 Un	1,2 Un
Δp U	-0,427	-0,425	-0,426	-0,039	-0,039	-0,039	-0,039
Δp U	-4,68	-4,62	-4,60	3,3	3,3	3,3	3,4
1a-1n: 6,25 VA		1a-1n: 6,25 VA		1a-1n: 6,25 VA		p.f. = 0,8 lag.	
2a-2n: 25VA; 3a-3n: 500VA; 4a-4n: 25VA		2a-2n: 0 VA; 3a-3n: 0 VA; 4a-4n: 0 VA		2a-2n: 0 VA; 3a-3n: 0 VA; 4a-4n: 0 VA		p.f. = 0,8 lag.	
ϵ U	0,8 Un	1,0 Un	1,0 Un	1,0 Un	1,0 Un	1,0 Un	1,2 Un
Δp U	-0,385	-0,383	-0,384	0,003	0,003	0,003	0,003
Δp U	-5,03	-5,04	-5,03	2,9	2,9	2,9	2,9
2a-2n: 25 VA		2a-2n: 25 VA		2a-2n: 25 VA		p.f. = 0,8 lag.	
1a-1n: 25VA; 3a-3n: 500VA; 4a-4n: 25VA		1a-1n: 0 VA; 3a-3n: 0 VA; 4a-4n: 0 VA		1a-1n: 0 VA; 3a-3n: 0 VA; 4a-4n: 0 VA		p.f. = 0,8 lag.	
ϵ U	0,8 Un	1,0 Un	1,0 Un	1,0 Un	1,0 Un	1,0 Un	1,2 Un
Δp U	-0,444	-0,442	-0,442	-0,050	-0,050	-0,050	-0,050
Δp U	-5,19	-5,13	-5,12	3,2	3,2	3,2	3,2
2a-2n: 6,25 VA		2a-2n: 6,25 VA		2a-2n: 6,25 VA		p.f. = 0,8 lag.	
1a-1n: 25VA; 3a-3n: 500VA; 4a-4n: 25VA		1a-1n: 0 VA; 3a-3n: 0 VA; 4a-4n: 0 VA		1a-1n: 0 VA; 3a-3n: 0 VA; 4a-4n: 0 VA		p.f. = 0,8 lag.	
ϵ U	0,8 Un	1,0 Un	1,0 Un	1,0 Un	1,0 Un	1,0 Un	1,2 Un
Δp U	-5,57	-5,53	-5,51	2,8	2,8	2,8	2,9
3a-3n: 500 VA		3a-3n: 25 VA		3a-3n: 25 VA		p.f. = 0,8 lag.	
1a-1n: 25VA; 2a-2n: 25VA; 4a-4n: 25VA		1a-1n: 0 VA; 2a-2n: 0 VA; 4a-4n: 0 VA		1a-1n: 0 VA; 2a-2n: 0 VA; 4a-4n: 0 VA		p.f. = 0,8 lag.	
ϵ U	0,02 Un	0,05 Un	0,8 Un	0,8 Un	0,8 Un	0,8 Un	1,2 Un
Δp U	-1,076	-0,999	-0,913	-0,913	-0,913	-0,913	-0,913
Δp U	5,61	4,81	5,03	5,14	5,19	5,18	5,18
3a-3n: 125 VA		3a-3n: 6,25 VA		3a-3n: 6,25 VA		p.f. = 0,8 lag.	
1a-1n: 25VA; 2a-2n: 25VA; 4a-4n: 25VA		1a-1n: 0 VA; 2a-2n: 0 VA; 4a-4n: 0 VA		1a-1n: 0 VA; 2a-2n: 0 VA; 4a-4n: 0 VA		p.f. = 0,8 lag.	
ϵ U	0,02 Un	0,05 Un	0,8 Un	0,8 Un	0,8 Un	0,8 Un	1,2 Un
Δp U	-0,428	-0,352	-0,268	-0,268	-0,268	-0,268	-0,268
Δp U	3,01	2,26	2,44	2,47	2,49	2,49	2,44
4a-4n: 25 VA		4a-4n: 25 VA		4a-4n: 25 VA		p.f. = 0,8 lag.	
1a-1n: 25VA; 2a-2n: 25VA; 3a-3n: 500VA		1a-1n: 0 VA; 2a-2n: 0 VA; 3a-3n: 0 VA		1a-1n: 0 VA; 2a-2n: 0 VA; 3a-3n: 0 VA		p.f. = 0,8 lag.	
ϵ U	0,02 Un	0,05 Un	0,8 Un	0,8 Un	0,8 Un	0,8 Un	1,2 Un
Δp U	-0,848	-0,570	-0,478	-0,477	-0,476	-0,476	-0,476
Δp U	5,88	6,80	6,18	6,10	6,09	6,09	6,10
4a-4n: 6,25 VA		4a-4n: 6,25 VA		4a-4n: 6,25 VA		p.f. = 0,8 lag.	
1a-1n: 25VA; 2a-2n: 25VA; 3a-3n: 500VA		1a-1n: 0 VA; 2a-2n: 0 VA; 3a-3n: 0 VA		1a-1n: 0 VA; 2a-2n: 0 VA; 3a-3n: 0 VA		p.f. = 0,8 lag.	
ϵ U	0,02 Un	0,05 Un	0,8 Un	0,8 Un	0,8 Un	0,8 Un	1,2 Un
Δp U	-0,602	-0,522	-0,432	-0,429	-0,428	-0,428	-0,428
Δp U	-6,18	-6,88	-6,60	-6,54	-6,51	-6,51	-6,51
4a-4n: 300 VA		4a-4n: 75 VA		4a-4n: 75 VA		p.f. = 0,8 lag.	
1a-1n: 25VA; 2a-2n: 25VA; 3a-3n: 500VA; 4a-4n: 300 VA		1a-1n: 0 VA; 2a-2n: 0 VA; 3a-3n: 0 VA; 4a-4n: 0 VA		1a-1n: 0 VA; 2a-2n: 0 VA; 3a-3n: 0 VA; 4a-4n: 0 VA		p.f. = 0,8 lag.	
ϵ U	0,02 Un	0,05 Un	1,0 Un	1,0 Un	1,0 Un	1,0 Un	1,9 Un
Δp U	-0,970	-0,892	-0,802	-0,822	-0,822	-0,822	-0,822
Δp U	-2,67	-3,4	-3,01	-3,01	-3,01	-3,01	-2,6

at 1,9 Un winding da-dn is loaded with 300 VA, p.f. = 0,8
 Measurements uncertainty: ϵ U = ± 0,044 %, Δp U = ± 2,2 min

Partial discharge measurement

- Measurement according to procedure A (PD test voltages were reached while decreasing the voltage after the power-frequency withstand test on primary winding)

Stress voltage: 230 kV / 60 s

Frequency: 120 Hz

Test voltage	1,2 Un = 151,2 kV	1,2 Un / $\sqrt{3}$ = 87,2 kV
Level of partial discharge	0,6 pC	0,6 pC

Remarks: background noise level: 0,6 (measured after voltage switch off), measuring circuit was calibrated with 5 pC (calibrating charge).

Measurement of capacitance and dielectric dissipation factor - tg δ

Temperature: 25 °C, Frequency: 50

Primary voltage	Tg δ [%]	Capacity [pF]	Leak current [mA]
10 kV	0,2	217	0,735
66,4 kV	0,2	217	4,567
72,7 kV	0,2	217	4,97

Measurement of windings' resistance

	R [25 °C]	Rct [75 °C]
A-N	13,50 k Ω	16,100 k Ω
1a-1n	79,600 m Ω	94,929 m Ω
2a-2n	78,100 m Ω	93,140 m Ω
3a-3n	51,600 m Ω	61,537 m Ω
4a-4n	50,500 m Ω	60,225 m Ω
da-dn	148,900 m Ω	177,574 m Ω

Checked by: *S. Blazewicz*

OG-4
KW-58




ABB Sp. z o.o. 06-300 Pizaszysz ul. Leszno 59		Routine test report of voltage instrument transformer after lightning impulse		TYPE: EMF-E123
A-N 115±3 kV 128/230/550 kV		Voltage factor: 1,9/8h		Serial no: 1HSE8851774
		IEC 61869-3		50 Hz

Winding	Usn [kV]	Sn [VA]	Class	Sth [VA]
1a - 1n	0,115±3	25	0,1	1000
1a - 1n	0,115±3	25	1,0	1000
2a - 2n	0,115±3	25	0,2	1000
2a - 2n	0,115±3	25	1,0	1000
3a - 3n	0,115±3	500	0,2/3P	1000
3a - 3n	0,115±3	25	3,0/3P	1000
4a - 4n	0,115±3	25	0,2/3P	1000
4a - 4n	0,115±3	25	3,0/3P	1000
da - dn	0,115	100	1,0	450
da - dn	0,115	300	3P	450

- Oil dielectric parameters check before filling (oil after treatment):
tg δ acc. IEC 60247, breakdown voltage acc. IEC 60156
 - Verification of terminal markings
 - Pressure and tightness test: oil overpressure: 0,8 bar / 24h - no traces of oil leakage
 - Power-frequency withstand test on primary windings
 - Partial discharge measurement
 - Power-frequency withstand test on secondary windings
 - Determination of errors
 - Measurement of capacitance and dielectric dissipation factor - tg δ
 - Measurement of windings' resistance
- At: Up = 184kV / 60s, f = 120Hz; N: Up = 3kV / 60s, f = 50Hz
- Up = 3 kV/60s

Oil dielectric parameters check before filling (oil after treatment)

- Measurement of oil tg δ according to IEC 60247
Tg δ = 0,1653 %; electrical stress = 1kV/mm, f = 50Hz, oil temp. = 90C ±1C.

- Measurement of breakdown voltage according to IEC 60156
Mean breakdown voltage = 81,75 kV, Relative standard deviation = 3,82 %;
f = 50Hz, oil temp. = 25 °C, measurement without the stirrer, type of electrodes used: partially spherical

Sample	Breakdown voltage [kV]
1	82,5
2	80,2
3	81,3
4	87,5
5	78,4
6	80,6

Verification of accuracy ± U%, (Δp U min)
Date of measurement: 2015-11-10
Ambient temperature: 24 +/- 2°C
Relative air humidity: 28 +/- 10%

1a-1n: 25 VA		1a-1n: 25 VA		1a-1n: 25 VA		1a-1n: 25 VA	
ε U	Δp U	ε U	Δp U	ε U	Δp U	ε U	Δp U
0,8 Un	1,0 Un	0,8 Un	1,0 Un	0,8 Un	1,0 Un	0,8 Un	1,0 Un
-0,088	-0,098	-0,088	-0,098	-0,088	-0,098	-0,088	-0,098
2,1	2,1	2,1	2,1	2,1	2,1	2,1	2,1
1a-1n: 6,25 VA		1a-1n: 6,25 VA		1a-1n: 6,25 VA		1a-1n: 6,25 VA	
ε U	Δp U	ε U	Δp U	ε U	Δp U	ε U	Δp U
0,8 Un	1,0 Un	0,8 Un	1,0 Un	0,8 Un	1,0 Un	0,8 Un	1,0 Un
-0,056	-0,054	-0,054	-0,054	-0,054	-0,054	-0,054	-0,054
1,7	1,7	1,7	1,7	1,7	1,7	1,7	1,7
2a-2n: 25 VA		2a-2n: 25 VA		2a-2n: 25 VA		2a-2n: 25 VA	
ε U	Δp U	ε U	Δp U	ε U	Δp U	ε U	Δp U
0,8 Un	1,0 Un	0,8 Un	1,0 Un	0,8 Un	1,0 Un	0,8 Un	1,0 Un
-0,108	-0,107	-0,107	-0,106	-0,106	-0,106	-0,106	-0,106
2,0	2,0	2,0	2,0	2,0	2,0	2,0	2,0
3a-3n: 25 VA		3a-3n: 25 VA		3a-3n: 25 VA		3a-3n: 25 VA	
ε U	Δp U	ε U	Δp U	ε U	Δp U	ε U	Δp U
0,8 Un	1,0 Un	0,8 Un	1,0 Un	0,8 Un	1,0 Un	0,8 Un	1,0 Un
-0,067	-0,066	-0,066	-0,065	-0,065	-0,065	-0,065	-0,065
1,6	1,6	1,6	1,6	1,6	1,6	1,6	1,6
4a-4n: 25 VA		4a-4n: 25 VA		4a-4n: 25 VA		4a-4n: 25 VA	
ε U	Δp U	ε U	Δp U	ε U	Δp U	ε U	Δp U
0,8 Un	1,0 Un	0,8 Un	1,0 Un	0,8 Un	1,0 Un	0,8 Un	1,0 Un
-0,067	-0,066	-0,066	-0,065	-0,065	-0,065	-0,065	-0,065
1,6	1,6	1,6	1,6	1,6	1,6	1,6	1,6
da-dn: 100 VA		da-dn: 100 VA		da-dn: 100 VA		da-dn: 100 VA	
ε U	Δp U	ε U	Δp U	ε U	Δp U	ε U	Δp U
0,8 Un	1,0 Un	0,8 Un	1,0 Un	0,8 Un	1,0 Un	0,8 Un	1,0 Un
0,040	0,042	0,042	0,042	0,042	0,042	0,042	0,042
2,4	2,4	2,4	2,4	2,4	2,4	2,4	2,4

* at 1,9 Un winding da-dn is loaded with 100 VA; p.f. = 0,8 lag.
Measurements uncertainty: ε U = ± 0,044 %, Δp U = ± 2,2 min

Verification of accuracy $\pm U\%$, ($\Delta\phi$ U min)

Date of measurement: 2015-11-10
 Ambient temperature: 24 +/- 2°C
 Relative air humidity: 28 +/- 10%

1a-1n: 25 VA		1a-1n: 25 VA		p.f. = 0,8 lag.	
2a-2n: 25VA; 3a-3n: 500VA; 4a-4n: 25VA		2a-2n: 0 VA; 3a-3n: 0 VA; 4a-4n: 0 VA		p.f. = 0,8 lag.	
ε U	0,8 Un	1,0 Un	1,0 Un	1,2 Un	1,2 Un
$\Delta\phi$ U	-0,432	-0,431	-0,430	-0,442	-0,442
$\Delta\phi$ U	-4,9	-4,9	-4,9	-5,3	-5,3
1a-1n: 6,25 VA		1a-1n: 6,25 VA		p.f. = 0,8 lag.	
2a-2n: 25VA; 3a-3n: 500VA; 4a-4n: 25VA		2a-2n: 0 VA; 3a-3n: 0 VA; 4a-4n: 0 VA		p.f. = 0,8 lag.	
ε U	0,8 Un	1,0 Un	1,0 Un	1,2 Un	1,2 Un
$\Delta\phi$ U	-0,330	-0,389	-0,389	-0,408	-0,408
$\Delta\phi$ U	-5,3	-5,3	-5,3	-5,8	-5,8
2a-2n: 25 VA		2a-2n: 25 VA		p.f. = 0,8 lag.	
1a-1n: 25VA; 3a-3n: 500VA; 4a-4n: 25VA		1a-1n: 0 VA; 3a-3n: 0 VA; 4a-4n: 0 VA		p.f. = 0,8 lag.	
ε U	0,8 Un	1,0 Un	1,0 Un	1,2 Un	1,2 Un
$\Delta\phi$ U	-0,450	-0,449	-0,448	-0,408	-0,408
$\Delta\phi$ U	-5,4	-5,4	-5,4	-5,8	-5,8
2a-2n: 6,25 VA		2a-2n: 6,25 VA		p.f. = 0,8 lag.	
1a-1n: 25VA; 3a-3n: 500VA; 4a-4n: 25VA		1a-1n: 0 VA; 3a-3n: 0 VA; 4a-4n: 0 VA		p.f. = 0,8 lag.	
ε U	0,8 Un	1,0 Un	1,0 Un	1,2 Un	1,2 Un
$\Delta\phi$ U	-0,409	-0,408	-0,408	-0,408	-0,408
$\Delta\phi$ U	-5,8	-5,8	-5,8	-5,8	-5,8
3a-3n: 500 VA		3a-3n: 500 VA		p.f. = 0,8 lag.	
1a-1n: 25VA; 2a-2n: 25VA; 4a-4n: 25VA		1a-1n: 0 VA; 2a-2n: 0 VA; 4a-4n: 0 VA		p.f. = 0,8 lag.	
ε U	0,02 Un	0,05 Un	0,8 Un	1,0 Un	1,2 Un
$\Delta\phi$ U	-1,068	-1,015	-0,926	-0,925	-0,928
$\Delta\phi$ U	5,5	4,9	4,9	5,0	5,0
3a-3n: 125 VA		3a-3n: 125 VA		p.f. = 0,8 lag.	
1a-1n: 25VA; 2a-2n: 25VA; 4a-4n: 25VA		1a-1n: 0 VA; 2a-2n: 0 VA; 4a-4n: 0 VA		p.f. = 0,8 lag.	
ε U	0,02 Un	0,05 Un	0,8 Un	1,0 Un	1,2 Un
$\Delta\phi$ U	-0,436	-0,359	-0,273	-0,272	-0,272
$\Delta\phi$ U	3,0	2,3	2,3	2,4	2,4
4a-4n: 25 VA		4a-4n: 25 VA		p.f. = 0,8 lag.	
1a-1n: 25VA; 2a-2n: 25VA; 3a-3n: 500VA		1a-1n: 0 VA; 2a-2n: 0 VA; 3a-3n: 0 VA		p.f. = 0,8 lag.	
ε U	0,02 Un	0,05 Un	0,8 Un	1,0 Un	1,2 Un
$\Delta\phi$ U	-0,641	-0,568	-0,475	-0,474	-0,474
$\Delta\phi$ U	-6,1	-6,8	-6,6	-6,5	-6,5
4a-4n: 6,25 VA		4a-4n: 6,25 VA		p.f. = 0,8 lag.	
1a-1n: 25VA; 2a-2n: 25VA; 3a-3n: 500VA		1a-1n: 0 VA; 2a-2n: 0 VA; 3a-3n: 0 VA		p.f. = 0,8 lag.	
ε U	0,02 Un	0,05 Un	0,8 Un	1,0 Un	1,2 Un
$\Delta\phi$ U	-0,804	-0,526	-0,434	-0,433	-0,433
$\Delta\phi$ U	-6,4	-7,0	-6,9	-6,8	-6,8
da-dn: 300 VA		da-dn: 300 VA		p.f. = 0,8 lag.	
1a-1n: 25VA; 2a-2n: 25VA; 3a-3n: 500VA; 4a-4n: 25VA		1a-1n: 0 VA; 2a-2n: 0 VA; 3a-3n: 0 VA; 4a-4n: 0 VA		p.f. = 0,8 lag.	
ε U	0,02 Un	0,05 Un	1,0 Un	1,0 Un	1,9 Un
$\Delta\phi$ U	-0,907	-0,822	-0,727	-0,737	-0,737
$\Delta\phi$ U	-5,1	-5,7	-5,4	-5,3	-5,3

*: at 1,9 Un winding da-dn is loaded with 300 VA, p.f. = 0,8 lag.

Measurements uncertainty: $\varepsilon U \pm 0,044\%$, $\Delta\phi U \pm 2,2$ min

Partial discharge measurement

- Measurement according to procedure A (PD test voltages were reached while decreasing the voltage after the power-frequency withstand test on primary winding)
 Stress voltage: 184 kV / 60 s
 Frequency: 120 Hz

Test voltage	1,2 Um = 151,2 kV	1,2 Um / $\sqrt{3}$ = 87,2 kV
Level of partial discharge	0,6 pC	0,6 pC

Remarks: background noise level: 0,6 (measured after voltage switch off), measuring circuit was calibrated with 5 pC (calibrating charge).

Measurement of capacitance and dielectric dissipation factor - tg δ

Temperature: 25 °C, Frequency: 60

Primary voltage	Tg δ	Capacity [pF]	Leak current [mA]
10 kV	0,2	217	0,71
66,4 kV	0,2	217	4,534
72,7 kV	0,21	217	4,814


Measurement of windings' resistance

	R (23 °C)	Ret (75 °C)
A-N	13,30 k Ω	16,018 k Ω
1a-1n	77,900 m Ω	93,820 m Ω
2a-2n	76,100 m Ω	91,652 m Ω
3a-3n	50,200 m Ω	60,459 m Ω
4a-4n	49,530 m Ω	59,652 m Ω
da-dn	146,100 m Ω	175,957 m Ω

OGA
K1-58


Przasnysz, 2015-11-10

Checked by: *[Signature]*



[Handwritten signature]

212

 **HIGH VOLTAGE LABORATORY**
INSTYTUT ENERGETYKI
 01-330 WARSZAWA, ul. Mory 8, tel. (22) 3451242
 tel. fax. (22) 8368048, e-mail: ewn@ken.com.pl

EWN/109/E/15-1
 Annex 3

HIGH VOLTAGE LABORATORY



POLAND 01-330 WARSZAWA, ul. Mory 8
fax: (+4822) 836-80-48, mail: ewn@ken.com.pl

Próba udarem uciętym 1,2/50us

project: ewn109e15-1a test date 05-10-2015 page 1

Test - object - data

WNR	EWN/109/E/15-1a	TR-No. 1HSE8851774	O.-No. 4500678253
test object	EMF-E123	vector group	
output	123 kVA	BIL	550
voltage	123 KV	frequency	50 Hz
customer	ABB Sp. z o. o. ul. Zeganska 1, 04-713 Warszawa		

ANNEX 3 for test report EWN/109/E/15-1
 (8 pages)
 Lightning impulse test protocol:
 □ ewn109e15-1a

Próba udarem ucietym 1,2/50us
 project: ewm109e15-1a

Próba udarem ucietym 1,2/50us
 project: ewm109e15-1a

LI lightning-impulse		T1[us]		T2[us]		Tc[us]		Ip [A]		remark	
no.	Up [kV]	T1[us]	T2[us]	Tc[us]	Ip [A]	LI	LI	LI	LI	LI	LI
1	-276.3	1.15	44.8		-264.6	LI: A - RW(50.0%)					
2	-550.7	1.16	45		-212.1	LI: A - FW(100.0%)					
3	-317.9	1.16		3.59	682.2	LI: A - CRW(57.5%)					
4	-632.6	1.17		3.45	-1460	LI: A - CFW(115.0%)					
5	-632.2	1.17		3.58	-1450	LI: A - CFW(115.0%)					
6	-550	1.17	45.1		-216.1	LI: A - FW(100.0%)					
7	-549.8	1.17	45.1		-188.6	LI: A - FW(100.0%)					
8	-550	1.16	45.1		-216.6	LI: A - FW(100.0%)					
9	-550.3	1.17	45.1		-207.8	LI: A - FW(100.0%)					
10	-550.3	1.17	45.1		-213.7	LI: A - FW(100.0%)					
11	-550.6	1.16	45.1		-235	LI: A - FW(100.0%)					
12	-550.3	1.17	45.1		-195.6	LI: A - FW(100.0%)					
13	-550	1.17	45.1		-197.2	LI: A - FW(100.0%)					
14	-550.2	1.17	45.1		-204	LI: A - FW(100.0%)					
15	-550.3	1.16	45.1		-220.5	LI: A - FW(100.0%)					
16	-550.4	1.17	45.1		-198.6	LI: A - FW(100.0%)					
17	-550.5	1.17	45.2		-185.1	LI: A - FW(100.0%)					
18	-550.5	1.16	45.2		-205.7	LI: A - FW(100.0%)					
19	-550.2	1.16	45.2		-205	LI: A - FW(100.0%)					
20	277.2	1.16	45		257	LI: A - RW(50.0%)					
21	553	1.16	45.1		271.5	LI: A - FW(100.0%)					
22	553	1.16	45.1		303.3	LI: A - FW(100.0%)					
23	552.9	1.16	45.1		319.5	LI: A - FW(100.0%)					
24	552.8	1.16	45.1		322.7	LI: A - FW(100.0%)					
25	552.8	1.16	45.2		341.5	LI: A - FW(100.0%)					
26	552.6	1.16	45.2		310.1	LI: A - FW(100.0%)					
27	552.6	1.16	45.2		298.8	LI: A - FW(100.0%)					
28	552.6	1.16	45.2		347.1	LI: A - FW(100.0%)					
29	552.6	1.16	45.2		266.8	LI: A - FW(100.0%)					
30	552.5	1.16	45.2		351.4	LI: A - FW(100.0%)					
31	552.5	1.16	45.2		279.2	LI: A - FW(100.0%)					
32	552.3	1.16	45.2		268.9	LI: A - FW(100.0%)					
33	552.5	1.16	45.2		329.4	LI: A - FW(100.0%)					
34	552.3	1.16	45.2		365.3	LI: A - FW(100.0%)					
35	552.3	1.16	45.2		361.7	LI: A - FW(100.0%)					




HIGH VOLTAGE LABORATORY

POLAND 01-330 WARSZAWA, ul. Mory 8
fax: (+4822) 896-80-48, mail: ewn@iem.com.pl

Próba udarem ucietym 1,2/50us
project : ewn109e15-1a

page 4




HIGH VOLTAGE LABORATORY

POLAND 01-330 WARSZAWA, ul. Mory 8
fax: (+4822) 896-80-48, mail: ewn@iem.com.pl

Próba udarem ucietym 1,2/50us
project : ewn109e15-1a

page 5






HIGH VOLTAGE LABORATORY

POLAND 01-330 WARSZAWA, ul. Mory 8
fax (+4822) 836-90-48, mail: ewm@len.com.pl

Próba udarem uciętym 1,2/50us

project: ewm109e15-1a




HIGH VOLTAGE LABORATORY

POLAND 01-330 WARSZAWA, ul. Mory 8
fax (+4822) 836-90-48, mail: ewm@len.com.pl

Próba udarem uciętym 1,2/50us

project: ewm109e15-1a





HIGH VOLTAGE LABORATORY

POLAND 01-330 WARSZAWA, ul. Mory 8
fax: (+4822) 836-80-48, mail: ewm@hvl.com.pl

project: ewn109e15-1b

test date 07-10-2015

page 1

Test - object - data

test date 07-10-2015
factory ser.-no. 1HSE3851774
test object EMF-E123
order-no. 4500678253

Climate - Data

temperature 9.1 °C humidity 49 %
air-pressure 1007 hPa



HIGH VOLTAGE LABORATORY

POLAND 01-330 WARSZAWA, ul. Mory 8
fax: (+4822) 836-80-48, mail: ewm@hvl.com.pl

project: ewn109e15-1b

page 2

U lightning-impulse


no.	Up [kV]	T1 [µs]	T2 [µs]	Tc [µs]	Up [V]	remark
1	16.29	0.48	72.6	-129.6	-129.6	1a - 1n
2	16.29	0.48	72.6	-129.6	-129.6	1a - 1n zoom
3	16.27	0.48	72.5	-135.7	-135.7	2a - 2n
4	16.27	0.48	72.5	-135.7	-135.7	2a - 2n zoom
5	16.25	0.48	72.7	-133.6	-133.6	3a - 3n
6	16.25	0.48	72.7	-133.6	-133.6	3a - 3n zoom
7	16.32	0.48	72.2	-111.3	-111.3	4a - 4n
8	16.32	0.48	72.2	-111.3	-111.3	4a - 4n zoom
9	16.27	0.48	72.6	-88.33	-88.33	da - dn
10	16.27	0.48	72.6	-88.33	-88.33	da - dn zoom

24




project: ewm109e15-1b

page 3



project: ewm109e15-1b

page 4



248

HIGH VOLTAGE LABORATORY



INSTYTUT ENERGETYKI



LABORATORY ACCREDITED
BY THE POLISH CENTRE FOR ACCREDITATION
Accreditation Certificate of Testing Laboratory
No AB 272

TEST REPORT
No EWN/109/E/15-2

Impulse voltage withstand test on primary terminal,
chopped impulse voltage withstand test on primary terminal,
transmitted overvoltage test,
of voltage instrument transformer type EMF-E072

Warsaw, October 2015



HIGH VOLTAGE LABORATORY INSTYTUT ENERGETYKI

01-330 WARSZAWA, ul. Mocy 8, tel. (22) 3451242
tel. fax. (22) 8368048, e-mail: ewn@ien.com.pl

EWN/109/E/15-2

Page 2/10

TEST REPORT EWN/109/E/15-2

TEST OBJECT: Voltage instrument transformer type EMF-E072

TEST CUSTOMER: ABB Sp. z o.o.
04-713 Warszawa, ul. Żegalska 1

MANUFACTURER: ABB

ORDER NO: 4500678253 (15.09.2015)

TEST TYPE: Impulse voltage withstand test on primary terminal,
Chopped impulse voltage withstand test on primary terminal,
Transmitted overvoltage test

TEST PROCEDURE: According to:
PN-EN/IEC 61869-1
PN-EN/IEC 61869-3
Internal ABB specifications

TEST DATE: 05.10.2015 – 14.10.2015

TEST RESULT: POSITIVE - details are presented in following parts of report

TEST PERFORMERS: Michał Molas, M. Sc. EE

Adam Wielonek, Tech.

AUTHORISATION: Jerzy Mikołajczyk, M. Sc. EE

HEAD OF LABORATORY: J. L. Mikulski, Prof., Ph. D. EE

	Signature
	Signature
	Signature
	Signature

Warsaw, October 2015.

Publication or reproduction of the Report in any other form than a complete copy thereof is forbidden without written consent of the Laboratory



CONTENTS

1	COMPETENCE OF THE LABORATORY	4
2	TEST OBJECT DESCRIPTION	5
3	SCOPE OF TESTS AGREED UPON	5
4	TYPE TEST	6
4.1	Impulse voltage withstand test on primary terminal	6
4.1.1	Method of testing and acceptance criteria	6
4.1.2	Test arrangement	6
4.1.3	Test conditions	7
4.1.4	Test results	8
5	SPECIAL TESTS	8
5.1	Chopped impulse voltage withstand test on primary terminal	8
5.2	Transmitted overvoltage test	8
5.2.1	Method of testing and acceptance criteria	8
5.2.2	Test arrangement	9
5.2.3	Test conditions	9
5.2.4	Test results	10

Test report includes:

10	numbered pages;
4	figures;
1	photograph;
7	tables.

Attached to the test report:

- Annex 1: Documents provided by ABB Sp. z o.o. used as base of identification of test object (3 pages);
- Annex 2: Reports of routine test and determination of errors (6 pages);
- Annex 3: Lightning impulse test protocol (8 pages);
- Annex 4: Transmitted overvoltage test protocol (3 pages);



1 COMPETENCE OF THE LABORATORY

The High Voltage Laboratory is in possession of accreditation issued by the Polish Centre for Accreditation (Accreditation Certificate of Testing Laboratory No AB 272) concerning following tests:

Insulators and insulator strings	- lightning and switching impulse tests
	- power frequency voltage 50 Hz tests
	- radio interference measurements
Distribution substations	- lightning and switching impulse tests
	- power frequency voltage 50 Hz tests
	- radio interference measurements
Circuit breakers, disconnectors	- lightning and switching impulse tests
	- power frequency voltage 50 Hz tests
	- radio interference measurements
Insulators	- lightning and switching impulse tests
	- power frequency voltage 50 Hz tests
	- radio interference measurements
<u>Current and voltage transformers</u>	- <u>lightning and switching impulse tests</u>
	- <u>power frequency voltage 50 Hz tests</u>
Power transformers	- lightning and switching impulse tests
	- power frequency voltage 50 Hz tests
Lightning arresters and limiters	- lightning and switching impulse tests
	- power frequency voltage 50 Hz tests
Cables and cable fittings	- lightning and switching impulse tests
	- power frequency voltage 50 Hz tests
Line and station fittings	- radio interference measurements
Occupational safety equipment	- power frequency voltage 50 Hz tests

Full scope of accreditation of High Voltage Laboratory available on www.pca.gov.pl

Note

Tests described in sub-clause 5.2 of this Report don't comply with the scope of Laboratory accreditation.




2 TEST OBJECT DESCRIPTION

The tested object was instrument voltage transformer EMF-E072 manufactured by ABB sp. z o.o. 04-713 Warszawa, Żegalska 1 St. (Fabryka Aparatury Wysokich i Średnich Napięć, 06-300 Przasnysz, Leszno 59 St.), with the following parameters:

Prototype 4 – EMF-E072

Serial number: IHSE851776

- Highest voltage for equipment 72.5 kV
- Rated primary voltage 66000 / $\sqrt{3}$ V
- Insulation level 140 / 325 kV
- Frequency 50 Hz
- Temperature range -40 – +40 °C
- Total mass 160 kg



Phot. 1: Tested voltage transformer EMF-E072

3 SCOPE OF TESTS AGREED UPON

Test plan for voltage instrument transformer type EMF-E072 was consulted with the Customer. Tab. 1 includes the list of performed tests and requirements, which tested objects should comply with.



Tab. 1: Scope of tests of voltage instrument transformer

Item	Performed tests	Requirement
TYPE TESTS		
1	Impulse voltage withstand test on primary terminal	PN-EN/IEC 61869-1, p.7.2.3
SPECIAL TESTS		
2	Chopped impulse voltage test on primary terminal	PN-EN/IEC 61869-1, p.7.4.1
3	Transmitted overvoltage test	PN-EN/IEC 61869-1, p.7.4.4

Determination of errors of transformer, performed to prove the positive results of consecutive tests, was carried out on the premises of Factory Laboratory of ABB Sp. z o.o. in the presence of a representative of the High Voltage Department of Institute of Power Engineering. Detailed results are presented in Annex 2.

Tests were carried out according to:

- IEC 61869-1:2007 „Instrument transformers - Part 1: General requirements” (equiv. with: PN-EN 61869-1:2009 “Przekładniki – Część 1: Wymagania ogólne”)
- IEC 61869-3:2011 „Instrument transformers - Part 3: Additional requirements for inductive voltage transformers” (equiv. with: PN-EN 61869-3:2011 “Przekładniki – Część 3: Wymagania szczególne dotyczące przekładników napięciowych indukcyjnych”)

4 TYPE TEST

4.1 Impulse voltage withstand test on primary terminal

4.1.1 Method of testing and acceptance criteria

According to IEC 61869-1 clause 7.4.1 lightning impulse test (for negative polarity) can be combined with chopped impulse voltage test. For positive polarity lightning impulse test was performed according to IEC 61869-1 clause 7.2.3 (15 impulse method).

It is considered that the instrument transformer passed the test with a positive result if analysis of the waveforms recorded during the test does not indicate failure of internal insulation of instrument transformer.

4.1.2 Test arrangement

Arrangement for testing with full lightning impulse 1,2/50 μ s and chopped lightning impulse was based on Marx impulse generator made by HAERFELY. Voltage measurement was performed with impulse voltage measuring system Dr. Strauss TR-AS 200-14, in connection with a capacitive voltage divider (impulse peak value measuring uncertainty doesn't exceed 2% of the measured value for the confidence interval 95% and coverage factor $k=2$). Simplified diagram of the measurement system is shown in the Fig. 1




Fig. 1: Simplified diagram of the lightning impulse measurement system (for one step of the generator);
 IG - impulse generator; VD - voltage divider; G, Rg, Rst - generator elements; CD - chopping device;
 IT - instrument transformer (general schematic representation); Rd, Rst - detection resistance

4.1.3 Test conditions

Test conditions for full lightning impulse 1,2/50 μs test and chopped lightning impulse test (parameters of the measurement system, values of test voltages and sequence of impulses applications) are presented in Tab. 2 and Tab. 3. The influence of atmospheric condition on test voltage value was not taken into consideration.

Tab. 2: Parameters of the lightning impulse measurement system

IMPULSE GENERATOR	
Number of steps	n = 4
General capacitance	C _g = 0.187 μF
Discharge resistance	R _d = 356 Ω
Damping resistance	R _g = 128 Ω
VOLTAGE DIVIDER	
HV unit capacitance	C _{1'} = ~2400 pF
LV unit capacitance	C _{2''} = 1.103 μF
Scale factor	δ _v = 460.7
DETECTION RESISTORS	
Detection resistance	R _{st} = 0.707 Ω
	R _{sd} = 2.970 Ω

Tab. 3: Values of test voltages and sequence of impulses applications

Full impulse test voltage	RW = 162,5 kV FW = 325,0 kV
Chopped impulse test voltage	CRW = 186,87 kV CFW = 373,75 kV
Sequence of impulses	Positive polarity 1 reduced full impulse (RW), 15 full impulses (FW) Negative polarity 1 reduced full impulse (RW), 1 full impulse (FW), 1 reduced chopped impulse (CRW), 2 chopped impulses (CFW), 14 full impulses (FW).
Registration	Transients of test voltage (channel 1) Current flowing through secondary winding 1a-1n (channel 2) Current flowing through primary winding screen E (channel 3)

4.1.4 Test results

Oscillograms registered during the tests don't indicate any failures of the transformers' insulation (Annex 2). Comparison of the accuracy verification before and after the lightning impulse test of the transformers (Annex 3) don't indicate significant changes of the transformers' metrological characteristics.

TEST RESULT: POSITIVE

5 SPECIAL TESTS

5.1 Chopped impulse voltage withstand test on primary terminal

Chopped impulse test on the primary winding was combined with the negative polarity lightning impulse test. Detailed results of this test are presented in Section 4.1 and Annex 3 of this report.

TEST RESULT: POSITIVE

5.2 Transmitted overvoltage test

5.2.1 Method of testing and acceptance criteria

Transmitted overvoltage test was performed according to IEC 61869-3, IEC 61869-1 clause 7.4.4 and 6.11.4. During the test type „A” impulse (U₁) was applied between the primary terminal A and earth. Measurements of transmitted voltage (U₂) were carried out for all the secondary windings of the voltage instrument transformer.



It is considered that the instrument voltage transformer passed the test with a positive result if the value of the transmitted voltage (U_s) does not exceed 1,6 kV (IEC 61869-3 clause 6.1.1.4 Table 9).

5.2.2 Test arrangement

Arrangement for transmitted overvoltage measurement was based on one step of Marx impulse generator made by HAEFELY. Measurement of the voltage U_1 applied to the primary terminal of the instrument transformer was performed with impulse voltage measuring system Dr. Strauss TR-AS 200-14, in connection with a resistive voltage divider Siemens SMR 10/770. The transmitted voltage U_2 measurement was also performed with impulse voltage measuring system Dr. Strauss TR-AS 200-14. For both measured voltages U_1 and U_2 impulse peak value measuring uncertainty doesn't exceed 2% of the measured value for the confidence interval 95% and coverage factor $k=2$. Simplified diagram of the measurement system is shown in the

Fig. 2.




Fig. 2: Simplified diagram of the transmitted overvoltage measurement system IG - impulse generator; VD - voltage divider; C_f , R_f , R_v - generator elements; C_s - front shaping capacitor; IT - instrument transformer (general schematic representation).

5.2.3 Test conditions

Test conditions for transmitted overvoltage test (parameters of the measurement system and value of test voltage) are presented in Tab. 4. The influence of atmospheric condition on test voltage value was not taken into consideration.



Tab. 4: Parameters of the transmitted overvoltage measurement system and parameters of the test voltage

IMPULSE GENERATOR	
Number of steps	1
General capacitance	C_g μ F 0,750
Discharge resistance	R_d Ω 150
Damping resistance	R_k Ω 89
VOLTAGE DIVIDER	
HV unit resistance	$R_{u'}$ Ω 10098,96
LV unit resistance	$R_{u''}$ Ω 10,06
Scale factor	ϕ_v - 1005
FRONT SHAPING CAPACITOR	
Front shaping capacitor	C_s pF 500
PARAMETERS OF THE TEST VOLTAGE	
Peak value of applied voltage	U_1 kV 18,8
Conventional front time	T_1 μ s 0,50
Time to half-value	T_2 μ s 73

5.2.4 Test results

Results of the transmitted overvoltage measurement are presented in Tab. 5. The oscillograms of all applied and registered impulses are present in Annex 4 of hereby Report.

Tab. 5: Transmitted overvoltage measurement results

terminal	U_1 kV	U_2 V	U_1 V	U_{100} %
1a - 1n	18,77	159	801,8	50,1
2a - 2n	18,78	195	981,4	61,3
da - dn	18,80	158	798,0	49,9

Note:
 U_1 - peak value of applied voltage
 U_2 - maximal value of transmitted voltage
 U_3 - maximal value of transmitted voltage for specified overvoltage U_p
 U_p - specified overvoltage $U_p = 1,6 \cdot U_{100} \cdot \sqrt{2} / \sqrt{3}$
 U_{100} - percent of permissible overvoltage $U_{100} = U_1 / 1600 \cdot 100\%$

TEST RESULT: POSITIVE



HIGH VOLTAGE LABORATORY
INSTYTUT ENERGETYKI

01-330 WARSZAWA, ul. Mory 5, tel. (22) 3451242
 tel. fax. (22) 8368048, e-mail: evn@ien.com.pl

EWN/109/E/15-2

Annex 1

ANNEX 1 for test report EWN/109/E/15-2
 (3 pages)

Documents provided by ABB Sp. z o.o. used as base of identification of test object:

- Declaration of conformity – No. 097/2015 (EN),
- Rating plate – Document No. 1HSE 22040-PCC,
- Technical drawing – Document id. 1HSE8851776.



Declaration of conformity

ABB Sp. z o.o.
 Dept. in Przasnysz
 POLAND

DECLARATION OF CONFORMITY No. 097/2015 (EN)
 (acc. to ISO/IEC 17050-1)

Manufacturer: ABB

Product: Voltage Instrument Transformer EMF-E072

Above mentioned product conforms with the following standard :

Standard	Title	Edition/Date
IEC 61869 - 3	Voltage Instrument Transformers	2015

Additional information:

Serial numbers: 1HSE 8851776;

Place and date of issue of declaration

Przasnysz 05.10.2015

Kierownik Operacyjny PRN
 ABB Sp. z o.o.
 Oddział w Przasnyszu

Kierownik ds. Zapewnienia Jakości
 ABB Sp. z o.o.
 Oddział w Przasnyszu

[Handwritten Signature]
 (Name)

[Handwritten Signature]
 (Signature)



**HIGH VOLTAGE LABORATORY
INSTYTUT ENERGETYKI**

01-330 WARSZAWA, ul. Mory 8, tel. (22) 3451242
tel. fax. (22) 8368048, e-mail: ewzn@ien.com.pl

EWN/109/E/15-2

Annex 2

ANNEX 2 for test report EWN/109/E/15-2
(6 pages)

Reports of routine test and determination of errors:

- Routine test report of voltage instrument transformer EMF-072 (1HSE8851776),
- Routine test report of voltage instrument transformer EMF-072 (1HSE8851776) after lightning impulse,

ABB Sp. z o.o. 06-300 Przasnysz ul. Leszno 59		Routine test report of voltage instrument transformer		TYPE: EMF-E072
A-N	66:√3 kV	72,5/140/325 kV	Voltage factor: 1.9/8h	Serial no: 1HSE8851776
Winding		Usn [kV]	Sn [VA]	Class
1a - 1n	0,11:√3	20	20	0,2
1a - 1n	0,11:√3	25	25	0,5
2a - 2n	0,11:√3	20	20	0,2
2a - 2n	0,11:√3	120	120	0,5/3P
da - dn	0,11	50	50	1
da - dn	0,11	100	100	3P
				Sth [VA]
				1000
				1000
				1400
				1400
				1100
				1100

1. Oil dielectric parameters check before filling (oil after treatment):
tg δ acc. IEC 60247, breakdown voltage acc. IEC 60156
2. Verification of terminal markings
3. Pressure and tightness test: oil overpressure: 0.8 bar/24h - no traces of oil leakage on primary windings
4. Power-frequency withstand test
- A: Up = 140kV/60s, f = 120Hz; N: Up = 3kV/60s, f = 50Hz
- Up = 3 kV/60s
5. Partial discharge measurement
6. Power-frequency withstand test on secondary windings
7. Determination of errors
8. Measurement of capacitance and dielectric dissipation factor - tgδ
9. Measurement of windings' resistance

-
-
-
-
-
-
-
-
-

Oil dielectric parameters check before filling (oil after treatment)

- Measurement of oil tg δ according to IEC
Tg δ = 0.1653 %, electrical stress = 1kV/mm, f = 50Hz, oil temp. = 90C ±1C.
- Measurement of breakdown voltage according to IEC 60156
Mean breakdown voltage = 81.75 kV, Relative standard deviation = 3.82
f = 50Hz, oil temp. = 25 °C, measurement without the stirrer, type of electrodes used: partially spherical.

Sample	Breakdown voltage [kV]
1	82.5
2	80.2
3	81.3
4	87.5
5	78.4
6	80.6

Partial discharge measurement

- Measurement according to procedure A (PD test voltages were reached while decreasing the voltage after the power-frequency withstand test on primary winding)
- Stress voltage: 140 kV / 60 s
- Frequency: 120 Hz

Test voltage	1,2 Un = 87,0 kV	1,2 Un / $\sqrt{3}$ = 50,2 kV
Level of partial discharge	0,6 pC	0,6 pC

Remarks: background noise level: 0,6 (measured after voltage switch off), measuring circuit was calibrated with 5 pC (calibrating charge).

Verification of accuracy ε (U%), $\Delta\phi$ (U min)

Date of measurement: 2015-10-01
 Ambient temperature: 23 +/-
 Relative air humidity: 21 +/-

1a-1n: 20 VA		1a-1n: 20 VA		1a-1n: 20 VA		1a-1n: 20 VA	
2a-2n: 20 VA		2a-2n: 0 VA		2a-2n: 20 VA		2a-2n: 0 VA	
ε U	0,8 Un	1,0 Un	1,2 Un	0,8 Un	1,0 Un	1,2 Un	1,2 Un
$\Delta\phi$ U	-0,0688	-0,005	-0,004	-0,052	-0,051	-0,05	-0,05
$\Delta\phi$ U	2,28	2,34	2,39	3,42	3,47	3,53	3,53
1a-1n: 5 VA		1a-1n: 5 VA		1a-1n: 5 VA		1a-1n: 5 VA	
2a-2n: 20 VA		2a-2n: 0 VA		2a-2n: 20 VA		2a-2n: 0 VA	
ε U	0,8 Un	1,0 Un	1,2 Un	0,8 Un	1,0 Un	1,2 Un	1,2 Un
$\Delta\phi$ U	-0,027	-0,025	-0,024	0,012	0,014	0,015	0,015
$\Delta\phi$ U	2,38	2,43	2,49	3,2	3,26	3,32	3,32
1a-1n: 20 VA		1a-1n: 20 VA		1a-1n: 20 VA		1a-1n: 20 VA	
2a-2n: 20 VA		2a-2n: 0 VA		2a-2n: 20 VA		2a-2n: 0 VA	
ε U	0,8 Un	1,0 Un	1,2 Un	0,8 Un	1,0 Un	1,2 Un	1,2 Un
$\Delta\phi$ U	-0,0615	-0,059	-0,059	-0,022	-0,020	-0,019	-0,019
$\Delta\phi$ U	1,95	2,01	2,06	2,77	2,82	2,88	2,88
1a-1n: 5 VA		1a-1n: 5 VA		1a-1n: 5 VA		1a-1n: 5 VA	
2a-2n: 20 VA		2a-2n: 0 VA		2a-2n: 20 VA		2a-2n: 0 VA	
ε U	0,8 Un	1,0 Un	1,2 Un	0,8 Un	1,0 Un	1,2 Un	1,2 Un
$\Delta\phi$ U	-0,017	-0,016	-0,015	0,022	0,0236	0,0245	0,0245
$\Delta\phi$ U	2,25	2,30	2,35	3,07	3,12	3,18	3,18
da-dn: 50 VA		da-dn: 12,5 VA		da-dn: 12,5 VA		da-dn: 12,5 VA	
1a-1n: 20 VA; 2a-2n: 20 VA		1a-1n: 0 VA; 2a-2n: 0 VA		1a-1n: 0 VA; 2a-2n: 0 VA		1a-1n: 0 VA; 2a-2n: 0 VA	
ε U	0,02 Un	0,05 Un	1,0 Un	0,02 Un	0,05 Un	1,0 Un	1,9 Un
$\Delta\phi$ U	-0,125	-0,071	0,0052	-0,043	0,007	0,083	0,077
$\Delta\phi$ U	2,84	2,01	1,59	4,70	3,81	3,22	3,56

Measurements uncertainty: $\varepsilon U \pm 0,044\%$, $\Delta\phi U \pm 2,2$ min

Verification of accuracy ε (U%), ($\Delta\phi$ U min)

Date of measurement: 2015-10-01
 Ambient temperature: 23 +/- 2°C
 Relative air humidity: 21 +/- 10%

1a-1n: 25 VA		1a-1n: 25 VA		1a-1n: 25 VA		1a-1n: 25 VA	
2a-2n: 0 VA		2a-2n: 0 VA		2a-2n: 0 VA		2a-2n: 0 VA	
ε U	0,8 Un	1,0 Un	1,2 Un	0,8 Un	1,0 Un	1,2 Un	1,2 Un
$\Delta\phi$ U	-0,308	-0,306	-0,306	-0,0748	-0,0725	-0,0716	-0,0716
$\Delta\phi$ U	-1,41	-1,35	-1,30	3,51	3,57	3,63	3,63
1a-1n: 6,25 VA		1a-1n: 6,25 VA		1a-1n: 6,25 VA		1a-1n: 6,25 VA	
2a-2n: 0 VA		2a-2n: 0 VA		2a-2n: 0 VA		2a-2n: 0 VA	
ε U	0,8 Un	1,0 Un	1,2 Un	0,8 Un	1,0 Un	1,2 Un	1,2 Un
$\Delta\phi$ U	-0,228	-0,226	-0,225	0,0067	0,0086	0,0094	0,0094
$\Delta\phi$ U	-1,69	-1,64	-1,57	3,24	3,29	3,36	3,36
1a-1n: 120 VA		1a-1n: 120 VA		1a-1n: 120 VA		1a-1n: 120 VA	
2a-2n: 0 VA		2a-2n: 0 VA		2a-2n: 0 VA		2a-2n: 0 VA	
ε U	0,02 Un	0,05 Un	0,8 Un	0,02 Un	0,05 Un	0,8 Un	1,2 Un
$\Delta\phi$ U	-0,48	-0,431	-0,360	-0,358	-0,358	-0,358	-0,311
$\Delta\phi$ U	1,11	0,23	-0,19	-0,14	-0,07	-0,81	0,88
1a-1n: 25 VA		1a-1n: 25 VA		1a-1n: 25 VA		1a-1n: 25 VA	
2a-2n: 30 VA		2a-2n: 0 VA		2a-2n: 30 VA		2a-2n: 0 VA	
ε U	0,02 Un	0,05 Un	0,8 Un	1,2 Un	1,9 Un	1,9 Un	1,9 Un
$\Delta\phi$ U	-0,210	-0,168	-0,099	-0,097	-0,299	-0,299	-0,299
$\Delta\phi$ U	2,82	1,97	1,56	1,62	1,67	2,12	2,60
da-dn: 100 VA		da-dn: 25 VA		da-dn: 25 VA		da-dn: 25 VA	
1a-1n: 25 VA; 2a-2n: 120 VA		1a-1n: 0 VA; 2a-2n: 0 VA		1a-1n: 0 VA; 2a-2n: 0 VA		1a-1n: 0 VA; 2a-2n: 0 VA	
ε U	0,02 Un	0,05 Un	1,0 Un	1,9 Un	1,9 Un	1,9 Un	1,9 Un
$\Delta\phi$ U	-0,51	-0,46	-0,383	-0,39	0,044	0,098	0,17
$\Delta\phi$ U	-1,46	-2,21	-2,49	-2,11	4,85	3,32	3,67

* at 1,9 Un winding da-dn is loaded with 100 VA, p.f. = 0,8 lag.

Measurements uncertainty: $\varepsilon U \pm 0,044\%$, $\Delta\phi U \pm 2,2$ min

Measurement of capacitance and dielectric dissipation factor - tg δ


Primary voltage	Tg δ	Capacity [pF]	Leak current [mA]
10 kV	0,3	225	0,73
38,1 kV	0,3	225	2,685
41,8 kV	0,3	225	2,951

Measurement of windings' resistance

	R (23 °C)	Ret (75 °C)
A-N	12,20 k Ω	14,693 k Ω
1a-1n	116,200 m Ω	139,947 m Ω
2a-2n	47,860 m Ω	57,665 m Ω
da-dn	218,900 m Ω	263,634 m Ω

Checked by: J. Kozłowski

Przeanyasz, 2015-10-01



INSTITUTE OF POWER ENGINEERING
 Certification Department
 Witnessed Reviewed
 Date: 10-10-2015
 Dept: Sign. In. Exp. Inst. Politechniki

[Handwritten signature]

257

ABB Sp. z o.o. 06-300 Przasnysz ul. Leszno 59		Routine test report of voltage instrument transformer after lightning impulse		TYPE: EMF-E072
A-N	66:√3 kV	72,5/140/325 kV	Serial no: 1HSE8851776	IEC 61869-3
		Voltage factor: 1.9/8h	50 Hz	
Winding	Usn [kV]	Sn [VA]	Class	Sth [VA]
1a - 1n	0,11:√3	20	0,2	1000
1a - 1n	0,11:√3	25	0,5	1000
2a - 2n	0,11:√3	20	0,2	1400
2a - 2n	0,11:√3	120	0,5/3P	1400
da - dh	0,11	50	1	1100
da - dh	0,11	100	3P	1100

- Oil dielectric parameters check before filling (oil after treatment):
 ϵ δ acc. IEC 60247, breakdown voltage acc. IEC 60158
- Verification of terminal markings
- Pressure and tightness test: oil overpressure: 0,8 bar / 24h - no traces of oil leakage
- Power-frequency withstand test on primary windings
- Power-frequency withstand test on secondary windings
- Partial discharge measurement
- Power-frequency withstand test on secondary windings
- Determination of errors
- Measurement of capacitance and dielectric dissipation factor - tg δ
- Measurement of windings' resistance

- A: Up = 112 kV / 60s, f = 120Hz; N: Up = 3kV / 60s, f = 50Hz
 - Up = 3 kV / 60s

Oil dielectric parameters check before filling (oil after treatment)

- Measurement of oil tg δ according to IEC
 Tg δ = 0.1653 %; electrical stress = 1kV/mm, f = 50Hz, oil temp. = 90C ±1C.
 - Measurement of breakdown voltage according to IEC 60158
 Mean breakdown voltage = 81.75 kV, Relative standard deviation = 3.82
 f = 50Hz, oil temp. = 25 °C, measurement without the stirrer, type of electrodes used: partially spherical.

Sample	Breakdown voltage [kV]
1	82.5
2	80.2
3	81.3
4	87.5
5	78.4
6	80.6

Partial discharge measurement

- Measurement according to procedure A
 (PD test voltages were reached while decreasing the voltage after the power-frequency withstand test on primary winding)
 Stress voltage: 112 kV / 60 s
 Frequency: 120 Hz

Test voltage	1,2 Un = 37,0 kV	1,2 Un / √3 = 50,2 kV
Level of partial discharge	0,6 pC	

Remarks: background noise level: 0,6 (measured after voltage switch off), measuring circuit was calibrated with 5 pC (calibrating charge).

Verification of accuracy ϵ U%, $\Delta\phi$ U min)

Date of measurement: 2015-11-10
 Ambient temperature: 24 +/-
 Relative air humidity: 33 +/-

1a-1n: 25 VA		1a-1n: 25 VA		1a-1n: 25 VA		1a-1n: 25 VA	
2a-2n: 120 VA		2a-2n: 0 VA		2a-2n: 0 VA		2a-2n: 0 VA	
ϵ U	0,8 Un	1,0 Un	1,2 Un	0,8 Un	1,0 Un	1,2 Un	1,2 Un
$\Delta\phi$ U	-0,097	-0,095	-0,094	-0,079	-0,054	-0,053	-0,053
$\Delta\phi$ U	2,6	2,6	2,7	3,5	3,5	3,5	3,5
1a-1n: 6,25 VA		1a-1n: 6,25 VA		1a-1n: 6,25 VA		1a-1n: 6,25 VA	
2a-2n: 120 VA		2a-2n: 0 VA		2a-2n: 0 VA		2a-2n: 0 VA	
ϵ U	0,8 Un	1,0 Un	1,2 Un	0,8 Un	1,0 Un	1,2 Un	1,2 Un
$\Delta\phi$ U	-0,097	-0,035	-0,035	0,022	0,011	0,012	0,012
$\Delta\phi$ U	2,4	2,4	2,5	3,1	3,3	3,3	3,3
2a-2n: 120 VA		2a-2n: 120 VA		2a-2n: 120 VA		2a-2n: 120 VA	
1a-1n: 25 VA		1a-1n: 0 VA		1a-1n: 0 VA		1a-1n: 0 VA	
ϵ U	0,02 Un	0,05 Un	0,8 Un	1,0 Un	1,2 Un	1,0 Un	1,0 Un
$\Delta\phi$ U	-0,162	-0,136	-0,063	-0,081	-0,060	-0,166	-0,166
$\Delta\phi$ U	4,1	3,0	2,0	2,0	2,1	2,1	2,1
2a-2n: 30 VA		2a-2n: 30 VA		2a-2n: 30 VA		2a-2n: 30 VA	
1a-1n: 25 VA		1a-1n: 0 VA		1a-1n: 0 VA		1a-1n: 0 VA	
ϵ U	0,02 Un	0,05 Un	0,8 Un	1,0 Un	1,2 Un	1,0 Un	1,0 Un
$\Delta\phi$ U	-0,139	-0,094	-0,020	-0,018	-0,017	-0,123	-0,123
$\Delta\phi$ U	4,4	3,3	2,3	2,3	2,4	2,4	2,4
da-dn: 100 VA		da-dn: 120 VA		da-dn: 120 VA		da-dn: 120 VA	
1a-1n: 25 VA; 2a-2n: 120 VA		1a-1n: 0 VA; 2a-2n: 0 VA		1a-1n: 0 VA; 2a-2n: 0 VA		1a-1n: 0 VA; 2a-2n: 0 VA	
ϵ U	0,02 Un	0,05 Un	1,0 Un	1,0 Un	1,0 Un	1,0 Un	1,0 Un
$\Delta\phi$ U	-0,138	-0,029	0,004	-0,002	-0,002	-0,002	-0,002
$\Delta\phi$ U	3,5	2,9	1,5	1,5	1,5	1,5	1,5

* at 1,9 Un winding da-dn is loaded with 100 VA, p.f. = 0,8
 Measurements uncertainty: ϵ U ± 0,044 %, $\Delta\phi$ U ± 2,2 min



HIGH VOLTAGE LABORATORY
INSTYTUT ENERGETYKI
 01-330 WARSZAWA, ul. Mory 8, tel. (22) 3451242
 tel. fax. (22) 5358048, e-mail: ewn@ten.com.pl

EWN/109/E/15-2

Annex 3

Verification of accuracy ε (1%), ($\Delta\phi$ U min)
 Date of measurement: 2015-10-01
 Ambient temperature: 23 +/- 2°C
 Relative air humidity: 21 +/- 10%

1a-1n: 25 VA		1a-1n: 25 VA		1a-1n: 25 VA		p.f. = 0,8 lag.	
2a-2n: 120 VA		0,8 Un		1,0 Un		1,2 Un	
ε U	-0,311	1,0 Un	1,2 Un	1,0 Un	1,2 Un	1,2 Un	1,9 Un*
$\Delta\phi$ U	-1,4	-0,310	-0,309	-0,080	-0,077	-0,077	-0,516
1a-1n: 6.25 VA		1a-1n: 6.25 VA		1a-1n: 6.25 VA		p.f. = 0,8 lag.	
2a-2n: 120 VA		0,8 Un		1,0 Un		1,2 Un	
ε U	-0,231	1,0 Un	1,2 Un	1,0 Un	1,2 Un	1,2 Un	1,9 Un*
$\Delta\phi$ U	-1,7	-0,229	-0,228	0,001	0,003	0,004	-0,256
2a-2n: 120 VA		0,8 Un		1,0 Un		1,2 Un	
ε U	-0,231	1,0 Un	1,2 Un	1,0 Un	1,2 Un	1,2 Un	1,9 Un*
$\Delta\phi$ U	-1,7	-0,229	-0,228	0,001	0,003	0,004	-0,256
1a-1n: 25 VA		1a-1n: 25 VA		1a-1n: 25 VA		p.f. = 0,8 lag.	
2a-2n: 120 VA		0,02 Un		0,05 Un		0,8 Un	
ε U	-0,493	0,8 Un	1,0 Un	0,8 Un	1,0 Un	1,0 Un	1,2 Un
$\Delta\phi$ U	1,7	-0,494	-0,367	-0,365	-0,364	-0,364	-0,566
2a-2n: 30 VA		0,02 Un		0,05 Un		0,8 Un	
ε U	-0,292	0,8 Un	1,0 Un	0,8 Un	1,0 Un	1,0 Un	1,2 Un
$\Delta\phi$ U	3,5	0,7	-0,2	-0,2	-0,1	-0,1	-3,8
1a-1n: 25 VA		1a-1n: 25 VA		1a-1n: 25 VA		p.f. = 0,8 lag.	
2a-2n: 120 VA		0,02 Un		0,05 Un		0,8 Un	
ε U	-0,292	0,8 Un	1,0 Un	0,8 Un	1,0 Un	1,0 Un	1,2 Un
$\Delta\phi$ U	3,5	-0,183	-0,107	-0,105	-0,104	-0,304	-0,304
da-dn: 100 VA		da-dn: 100 VA		da-dn: 100 VA		p.f. = 0,8 lag.	
1a-1n: 25 VA; 2a-2n: 120 VA		0,02 Un		0,05 Un		0,8 Un	
ε U	-0,581	1,0 Un	1,9 Un	1,0 Un	1,9 Un	1,0 Un	1,9 Un
$\Delta\phi$ U	-1,1	-0,469	-0,383	-0,388	-0,388	-0,169	0,164
1a-1n: 25 VA; 2a-2n: 120 VA		0,02 Un		0,05 Un		0,8 Un	
ε U	-0,581	1,0 Un	1,9 Un	1,0 Un	1,9 Un	1,0 Un	1,9 Un
$\Delta\phi$ U	-1,1	-0,469	-0,383	-0,388	-0,388	-0,169	0,164

* at 1,9 Un winding da-dn is loaded with 100 VA, p.f. = 0,8 lag.
 Measurements uncertainty: ε U = ± 0,044 %, $\Delta\phi$ U = ± 2,2 min

Measurement of capacitance and dielectric dissipation factor - tg δ
 Temperature: 23 °C, Frequency: 50 Hz

Primary voltage	Tg δ	Capacity [pF]	Leak current [mA]
10 kV	0,3	225	0,735
38,1 kV	0,3	225	2,715
41,8 kV	0,3	225	2,952

Measurement of windings' resistance

	R (23 °C)	Rct (75 °C)
A-N	12,00 k Ω	14,452 k Ω
1a-1n	111,700 m Ω	134,527 m Ω
2a-2n	47,220 m Ω	56,870 m Ω
da-dn	217,000 m Ω	261,346 m Ω

Checked by: *Y. Blazynski*

Przeznaczony: 2015-11-10

INSTITUTE OF POWER ENGINEERING
 Certification Department
 Witnessed Reviewed
 Data / Sign. M. St. Enc. Jacek Mikolajczyk

for



Próba udarem ucietym 1,2/50us

project: ewm109e15-2a test date 05-10-2015

Test - object - data

WNR EWN/109E/15-2a TR-No. 1HSE8851776 O.-No. 4500678253
 test object EMF-E072 vector group
 output kVA BIL
 voltage 72.5 kV frequency 325 Hz 50 Hz
 customer ABB Sp. z o. o. ul. Zeganska 1, 04-713 Warszawa



Próba udarem ucietym 1,2/50us

project: ewm109e15-2a

Lightning-impulse


no.	Up [kV]	T1[us]	T2[us]	Tc[us]	Ip [A]	remark
1	-163.2	1.16	45.3		-215.6	LI: A - RW(50.0%)
2	-327.5	1.13	45.1		-315.5	LI: A - FW(100.0%)
3	-188.3	1.14		3.52	-248.5	LI: A - CRW(57.5%)
4	-376.8	1.13		3.48	467.8	LI: A - CFW(115.0%)
5	-374.4	1.13		3.47	365.5	LI: A - CFW(115.0%)
6	-327.6	1.13	45.2		-282.4	LI: A - FW(100.0%)
7	-327.7	1.13	45.2		-298.8	LI: A - FW(100.0%)
8	-327.5	1.13	45.2		-304.9	LI: A - FW(100.0%)
9	-327.9	1.13	45.2		-289	LI: A - FW(100.0%)
10	-327.4	1.13	45.2		-278.3	LI: A - FW(100.0%)
11	-327.8	1.13	45.2		-311.7	LI: A - FW(100.0%)
12	-327.9	1.13	45.1		-298.2	LI: A - FW(100.0%)
13	-327.6	1.13	45.2		-297.9	LI: A - FW(100.0%)
14	-327.5	1.13	45.2		-305.9	LI: A - FW(100.0%)
15	-327.4	1.13	45.2		-316.3	LI: A - FW(100.0%)
16	-327.7	1.13	45.2		-316.4	LI: A - FW(100.0%)
17	-327.4	1.13	45.2		-300.5	LI: A - FW(100.0%)
18	-327.5	1.13	45.3		-290.4	LI: A - FW(100.0%)
19	-327.6	1.13	45.3		-305.7	LI: A - FW(100.0%)
20	162.7	1.15	45.2		173.6	LI: A - RW(50.0%)
21	325.4	1.13	45.2		339.3	LI: A - FW(100.0%)
22	325.4	1.13	45.3		339.5	LI: A - FW(100.0%)
23	325.4	1.13	45.2		327.1	LI: A - FW(100.0%)
24	325.4	1.13	45.2		339.5	LI: A - FW(100.0%)
25	325.4	1.13	45.2		323.9	LI: A - FW(100.0%)
26	325.3	1.13	45.2		339.4	LI: A - FW(100.0%)
27	325.1	1.13	45.3		331.2	LI: A - FW(100.0%)
28	325.2	1.13	45.2		335.1	LI: A - FW(100.0%)
29	325.3	1.13	45.3		339.4	LI: A - FW(100.0%)
30	325.3	1.13	45.3		339.5	LI: A - FW(100.0%)
31	325.5	1.14	45.2		330.9	LI: A - FW(100.0%)
32	325.2	1.13	45.2		336.2	LI: A - FW(100.0%)
33	325.1	1.13	45.3		331.5	LI: A - FW(100.0%)
34	325.1	1.13	45.3		335.4	LI: A - FW(100.0%)
35	325.2	1.13	45.2		339.5	LI: A - FW(100.0%)



HIGH VOLTAGE LABORATORY

POLAND 01-330 WARSZAWA, ul. Mory 8
fax (+4822) 838-80-48, mail: ewm@len.com.pl


Próba udarem uciełytym 1,2/50us
project: ewm109e15-2a



HIGH VOLTAGE LABORATORY

POLAND 01-330 WARSZAWA, ul. Mory 8
fax (+4822) 838-80-48, mail: ewm@len.com.pl




Próba udarem uciełytym 1,2/50us
project: ewm109e15-2a













Próba udarem uciętym 1,2/50us

project : ewm109e15-2a



Próba udarem uciętym 1,2/50us

project : ewm109e15-2a



14

263



HIGH VOLTAGE LABORATORY
INSTYTUT ENERGETYKI
 01-330 WARSZAWA, ul. Mory 8, tel. (22) 3451242
 tel. fax. (22) 8368048, e-mail: ewn@ten.com.pl

EWN/109/E/15-2

Annex 4

POLAND 01-330 WARSZAWA, ul. Mory 8
 fax: (+4822) 836-80-48, mail: ewn@ten.com.pl

HIGH VOLTAGE LABORATORY

project: ewn109e15-2b

test date 06-10-2015

page 1

Test - object - data

test date 06-10-2015
 factory ser.-no. 1HSE6851776
 test object EMF-E072
 order-no. 4500678253
 specification
 test-field

Climate - Data

temperature	14 °C	humidity	78 %
		atm-pressure	1004 hPa

ANNEX 4 for test report EWN/109/E/15-2

(3 pages)

Transmitted overvoltage test protocol:

□ ewn109e15-2b

264



project: ewn109e15-2b




page 2

U lightning-impulse						
no.	Up [kV]	T1 [µs]	T2 [µs]	Tc [µs]	Up [V]	remark
1	18.77	0.5	73.5		158.9	1a - 1n
2	18.77	0.5	73.5		158.9	1a - 1n zoom
3	18.78	0.51	73.6		194.6	2a - 2h
4	18.78	0.51	73.6		194.6	2a - 2h zoom
5	18.8	0.5	73.6		158.4	da - dn
6	18.8	0.5	73.6		158.4	da - dn zoom



project: ewn109e15-2b

page 3



my

265


ju

[Handwritten signature]

HIGH VOLTAGE LABORATORY



INSTYTUT ENERGETYKI



LABORATORY ACCREDITED
BY THE POLISH CENTRE FOR ACCREDITATION
Accreditation Certificate of Testing Laboratory
No AB 272

TEST REPORT
No EWN/109/E/15-3

Impulse voltage withstand test on primary terminal,
chopped impulse voltage withstand test on primary terminal,
transmitted overvoltage test,
of voltage instrument transformer type EMF-E084

Warsaw, October 2015



HIGH VOLTAGE LABORATORY
INSTYTUT ENERGETYKI

01-330 WARSZAWA, ul. Mory 8, tel. (22) 3451242
tel. fax. (22) 8368048, e-mail: ewn@ien.com.pl

EWN/109/E/15-3

Page 2/10

TEST REPORT EWN/109/E/15-3

TEST OBJECT: Voltage instrument transformer type EMF-E084

TEST CUSTOMER: ABB Sp. z o.o.
04-713 Warszawa, ul. Żegalska 1

MANUFACTURER: ABB

ORDER NO: 4500678253 (15.09.2015)

TEST TYPE: Impulse voltage withstand test on primary terminal,
Chopped impulse voltage withstand test on primary terminal,
Transmitted overvoltage test

TEST PROCEDURE: According to:
FN-EN/IEC 61869-1
FN-EN/IEC 61869-3
Internal ABB specifications

TEST DATE: 05.10.2015 - 14.10.2015

TEST RESULT: POSITIVE - details are presented in following parts of report

TEST PERFORMERS:

Michał Molas, M. Sc. EE

Adam Wielonek, Tech.

AUTHORISATION:

Jerzy Mikołajczyk, M. Sc. EE

HEAD OF LABORATORY:

J. L. Mikuński, Prof., Ph. D. EE

	Signature
	Signature
	Signature
	Signature

Warsaw, October 2015.

Publication or reproduction of this Report in any other form than a complete copy thereof is forbidden without written consent of the Laboratory

267



CONTENTS

1	COMPETENCE OF THE LABORATORY	4
2	TEST OBJECT DESCRIPTION	5
3	SCOPE OF TESTS AGREED UPON	5
4	TYPE TEST	6
4.1	Impulse voltage withstand test on primary terminal	6
4.1.1	Method of testing and acceptance criteria	6
4.1.2	Test arrangement	6
4.1.3	Test conditions	7
4.1.4	Test results	8
5	SPECIAL TESTS	8
5.1	Chopped impulse voltage withstand test on primary terminal	8
5.2	Transmitted overvoltage test	8
5.2.1	Method of testing and acceptance criteria	8
5.2.2	Test arrangement	9
5.2.3	Test conditions	9
5.2.4	Test results	10

Test report includes:

- 10 numbered pages;
- 4 figures;
- 1 photograph;
- 7 tables.

Attached to the test report:

- Annex 1: Documents provided by ABB Sp. z o.o. used as base of identification of test object (3 pages);
- Annex 2: Reports of routine test and determination of errors (4 pages);
- Annex 3: Lightning impulse test protocol (8 pages);
- Annex 4: Transmitted overvoltage test protocol (3 pages);



1 COMPETENCE OF THE LABORATORY

The High Voltage Laboratory is in possession of accreditation issued by the Polish Centre for Accreditation (Accreditation Certificate of Testing Laboratory No AB 272) concerning following tests:

Insulators and insulator strings	- lightning and switching impulse tests
	- power frequency voltage 50 Hz tests
	- radio interference measurements
Distribution substations	- lightning and switching impulse tests
	- power frequency voltage 50 Hz tests
	- radio interference measurements
Circuit breakers, disconnectors	- lightning and switching impulse tests
	- power frequency voltage 50 Hz tests
	- radio interference measurements
Insulators	- lightning and switching impulse tests
	- power frequency voltage 50 Hz tests
	- radio interference measurements
<u>Current and voltage transformers</u>	- <u>lightning and switching impulse tests</u>
	- <u>power frequency voltage 50 Hz tests</u>
Power transformers	- lightning and switching impulse tests
	- power frequency voltage 50 Hz tests
Lightning arresters and limiters	- lightning and switching impulse tests
	- power frequency voltage 50 Hz tests
Cables and cable fittings	- lightning and switching impulse tests
	- power frequency voltage 50 Hz tests
Line and station fittings	- radio interference measurements
Occupational safety equipment	- power frequency voltage 50 Hz tests

Full scope of accreditation of High Voltage Laboratory available on www.pcn.gov.pl

Note

Tests described in sub-clause 5.2 of this Report don't comply with the scope of Laboratory accreditation.


2 TEST OBJECT DESCRIPTION

The tested object was instrument voltage transformer EMF-E084 manufactured by ABB sp. z o.o. 04-713 Warszawa, Żegańska 1 St. (Fabryka Aparatury Wysokich i Średnich Napięć, 06-300 Przasnysz, Leszno 59 St.), with the following parameters:

Prototype 5 – EMF-E084

Serial number: 1HSE851777

- Highest voltage for equipment 84 kV
- Rated primary voltage 77000 / $\sqrt{3}$ V
- Insulation level 150 / 380 kV
- Frequency 50 Hz
- Temperature range -40 – +40 °C
- Total mass 190 kg



Phot. 1: Tested voltage transformer EMF-E084

3 SCOPE OF TESTS AGREED UPON

Test plan for voltage instrument transformer type EMF-E084 was consulted with the Customer. Tab. 1 includes the list of performed tests and requirements, which tested objects should comply with.

Tab. 1: Scope of tests of voltage instrument transformer

Item	Performed tests	Requirement
TYPE TESTS		
1	Impulse voltage withstand test on primary terminal	PN-EN/IEC 61869-1, p.7.2.3
SPECIAL TESTS		
2	Chopped impulse voltage test on primary terminal	PN-EN/IEC 61869-1, p.7.4.1
3	Transmitted overvoltage test	PN-EN/IEC 61869-1, p.7.4.4

Determination of errors of transformer, performed to prove the positive results of consecutive tests, was carried out on the premises of Factory Laboratory of ABB Sp. z o.o. in the presence of a representative of the High Voltage Department of Institute of Power Engineering. Detailed results are presented in Annex 2.

Tests were carried out according to:

- IEC 61869-1:2007 „Instrument transformers - Part 1: General requirements” (equiv. with: PN-EN 61869-1:2009 “Przekładniki – Część 1: Wymagania ogólne”)
- IEC 61869-3:2011 „Instrument transformers - Part 3: Additional requirements for inductive voltage transformers” (equiv. with: PN-EN 61869-3:2011 “Przekładniki – Część 3: Wymagania szczególne dotyczące przekładników napięciowych indukcyjnych”)

4 TYPE TEST

4.1 Impulse voltage withstand test on primary terminal


4.1.1 Method of testing and acceptance criteria

According to IEC 61869-1 clause 7.4.1 lightning impulse test (for negative polarity) can be combined with chopped impulse voltage test. For positive polarity lightning impulse test was performed according to IEC 61869-1 clause 7.2.3 (1.5 impulse method).

It is considered that the instrument transformer passed the test with a positive result if analysis of the waveforms recorded during the test does not indicate failure of internal insulation of instrument transformer.

4.1.2 Test arrangement

Arrangement for testing with full lightning impulse 1.2/50 μ s and chopped lightning impulse was based on Marx impulse generator made by HAEFELY. Voltage measurement was performed with impulse voltage measuring system Dr. Strauss TR-AS 200-14, in connection with a capacitive voltage divider (impulse peak value measuring uncertainty doesn't exceed 2% of the measured value for the confidence interval 95% and coverage factor $k=2$). Simplified diagram of the measurement system is shown in the Fig. 1.






Fig. 1. Simplified diagram of the lightning impulse measurement system (for one step of the generator);
 IG - impulse generator; VD - voltage divider; C_g , R_g , R_1 , R_2 - generator elements; CD - chopping device;
 IT - instrument transformer (general schematic representation); R_{1p} , R_{2p} - detection resistance

4.1.3 Test conditions

Test conditions for full lightning impulse 1,2/50 μ s test and chopped lightning impulse test (parameters of the measurement system, values of test voltages and sequences of impulses applications) are presented in Tab. 2 and Tab. 3. The influence of atmospheric condition on test voltage value was not taken into consideration.

Tab. 2. Parameters of the lightning impulse measurement system

IMPULSE GENERATOR	
Number of steps	n - 4
General capacitance	C_g μ F 0,187
Discharge resistance	R_d Ω 356
Damping resistance	R_1 Ω 128
VOLTAGE DIVIDER	
HV unit capacitance	C_{v1} pF -2400
LV unit capacitance	C_{v2} μ F 1,103
Scale factor	δ_v - 460,7
DETECTION RESISTORS	
Detection resistance	R_{d1} Ω 2,970
	R_{d2} Ω 0,707

Tab. 3. Values of test voltages and sequence of impulses applications

Full impulse test voltage	RW = 190 kV
Chopped impulse test voltage	FW = 380 kV
	CRW = 218,5 kV
	CFW = 437,0 kV
Sequence of impulses	Positive polarity
	1 reduced full impulse (RW), 15 full impulses (FW).
Registration	Negative polarity
	1 reduced full impulse (RW), 1 full impulse (FW), 1 reduced chopped impulse (CRW), 2 chopped impulses (CFW), 14 full impulses (FW).
Registration	Transients of test voltage (channel 1)
	Current flowing through secondary winding 1a-1n (channel 2) Current flowing through primary winding screen E (channel 3)

4.1.4 Test results

Oscillograms registered during the tests don't indicate any failures of the transformers' insulation (Annex 2). Comparison of the accuracy verification before and after the lightning impulse test of the transformers (Annex 3) don't indicate significant changes of the transformers' metrological characteristics.

TEST RESULT: POSITIVE

5 SPECIAL TESTS

5.1 Chopped impulse voltage withstand test on primary terminal

Chopped impulse test on the primary winding was combined with the negative polarity lightning impulse test. Detailed results of this test are presented in Section 4.1 and Annex 3 of this report.

TEST RESULT: POSITIVE

5.2 Transmitted overvoltage test

5.2.1 Method of testing and acceptance criteria

Transmitted overvoltage test was performed according to IEC 61869-3, IEC 61869-1 clause 7.4.4 and 6.1.1.4. During the test type „A” impulse (U_1) was applied between the primary terminal A and earth. Measurements of transmitted voltage (U_2) were carried out for all the secondary windings of the voltage instrument transformer.



It is considered that the instrument voltage transformer passed the test with a positive result if the value of the transmitted voltage (U_s) does not exceed 1,6 kV (IEC 61869-3 clause 6.11.4 Table 9).

5.2.2 Test arrangement

Arrangement for transmitted overvoltage measurement was based on one step of Marx impulse generator made by HAEFELY. Measurement of the voltage U_1 , applied to the primary terminal of the instrument transformer was performed with impulse voltage measuring system Dr. Strauss TR-AS 200-14, in connection with a resistive voltage divider Siemens SMR 10/770. The transmitted voltage U_2 measurement was also performed with impulse voltage measuring system Dr. Strauss TR-AS 200-14. For both measured voltages U_1 and U_2 impulse peak value measuring uncertainty doesn't exceed 2% of the measured value for the confidence interval 95% and coverage factor $k=2$. Simplified diagram of the measurement system is shown in the Fig. 2.

Fig. 2.




Fig. 2: Simplified diagram of the transmitted overvoltage measurement system IG - impulse generator, VD - voltage divider; C_g, R_g, R_g - generator elements; C_s - front shaping capacitor, IT - instrument transformer (general schematic representation);

5.2.3 Test conditions

Test conditions for transmitted overvoltage test (parameters of the measurement system and value of test voltage) are presented in Tab. 4. The influence of atmospheric condition on test voltage value was not taken into consideration.

Tab. 4: Parameters of the transmitted overvoltage measurement system and parameters of the test voltage

IMPULSE GENERATOR			
Number of steps	n	1	
General capacitance	C_g	0,750	
Discharge resistance	R_d	150	
Damping resistance	R_d	89	
VOLTAGE DIVIDER			
HV unit resistance	R_{u1}	10098,96	
LV unit resistance	R_{u2}	10,06	
Scale factor	δ_v	1005	
FRONT SHAPING CAPACITOR			
Front shaping capacitor	C_s	500	
PARAMETERS OF THE TEST VOLTAGE			
Peak value of applied voltage	U_1	kV	23,6
Conventional front time	T_1	μs	0,50
Time to half-value	T_2	μs	74

5.2.4 Test results

Results of the transmitted overvoltage measurement are presented in Tab. 5. The oscillograms of all applied and registered impulses are present in Annex 4 of hereby Report.

Tab. 5: Transmitted overvoltage measurement results

terminal	U_1	U_2	U_s	U_{ps}
	kV	V	V	%
1a - 1n	23,52	175	816,5	51,0
2a - 2n	23,69	208	964,9	60,3
da - dn	23,59	136	632,7	39,5

Note:
 U_1 - peak value of applied voltage
 U_2 - maximal value of transmitted voltage
 U_s - maximal value of transmitted voltage for specified overvoltage U_p
 U_{ps} - specified overvoltage $U_{ps}=1,6 \cdot U_m \cdot \sqrt{2}/\sqrt{3}$
 U_{ps} - percent of permissible overvoltage $U_{ps}=U_s/U_p \cdot 100\%$

TEST RESULT: POSITIVE



HIGH VOLTAGE LABORATORY
INSTYTUT ENERGETYKI

01-330 WARSZAWA, ul. Mory 8, tel. (22) 3451242
tel. fax. (22) 8368048, e-mail: ewn@iem.com.pl

EWN/109/E/15-3

Annex 1

272

ANNEX 1 for test report EWN/109/E/15-3
(3 pages)

Documents provided by ABB Sp. z o.o. used as base of identification of test object:

- Declaration of conformity – No. 098/2015 (EN),
- Rating plate – Document No. 1HSE 22040-PCF,
- Technical drawing – Document id. 1HSE8851777.

ABB	Declaration of conformity	ABB Sp. z o.o. Dept. In Przasnysz POLAND
DECLARATION OF CONFORMITY No. 098/2015 (EN) (acc. to ISO/IEC 17050-1)		
Manufacturer:	ABB	
Product:	Voltage Instrument Transformer EMF-E084	
Above mentioned product conforms with the following standard :		
Standard	Title	Edition/Date
IEC 61869 - 3	Voltage Instrument Transformers	2015
Additional information:		
Serial numbers: 1HSE 8851777;		
Place and date of issue of declaration		
Przasnysz 05.10.2015		
Kierownik Operacyjny PPHV ABB Sp. z o.o. Oddział w Przasnyszu <i>[Signature]</i> (Name)		Kierownik ds. Zapewnienia Jakości ABB Sp. z o.o. Oddział w Przasnyszu <i>[Signature]</i> Krzysztof Lubbeck (Signature)



HIGH VOLTAGE LABORATORY
INSTYTUT ENERGETYKI

01-330 WARSZAWA, ul. Mory 8, tel. (22) 3451242
 tel. fax. (22) 8568048, e-mail: ewn@ien.com.pl

EWN/109/E/15-3

Annex 2

ANNEX 2 for test report EWN/109/E/15-3

(4 pages)

Reports of routine test and determination of errors:

- Routine test report of voltage instrument transformer EMF-084 (1HSE8851777),
- Routine test report of voltage instrument transformer EMF-084 (1HSE8851777) after lightning impulse,

ABB Sp. z o.o. 06-300 Przasnysz ul. Leszno 59		Routine test report of voltage instrument transformer		TYPE: EMF-084 Serial no: 1HSE8851777
A-N	77:√3 kV	84/150/380 kV	Voltage factor: 1.9/8h	IEC 61869-3 50 Hz
Winding		U _{sn} [kV]	S _n [VA]	Class
1a - 1n		0,11:√3	25	0,2
2a - 2n		0,11:√3	25	0,2
da - dn		0,11:3	50	3P
				S _{th} [VA]
				1000
				1000
				150

1. Oil dielectric parameters check before filling (oil after treatment):
 tg δ acc. IEC 60247, breakdown voltage acc. IEC 60156
2. Verification of terminal markings
3. Pressure and tightness test: oil overpressure: 0,8 bar / 24h — no traces of oil leakage on primary windings
4. Power-frequency withstand test
 - A: Up = 150kV / 60s, f = 50Hz
 - N: Up = 3kV / 60s, f = 50Hz
5. Partial discharge measurement
 - Up = 3 kV/60s
6. Power-frequency withstand test on secondary windings
7. Determination of errors
8. Measurement of capacitance and dielectric dissipation factor - tg δ
9. Measurement of windings' resistance

Oil dielectric parameters check before filling (oil after treatment)

- Measurement of oil tg δ according to IEC
 Tg δ = 0.2098 %; electrical stress = 1kV/mm, f = 50Hz, oil temp. = 90C ±1C.
- Measurement of breakdown voltage according to IEC 60156
 Mean breakdown voltage = 83.22 kV, Relative standard deviation = 2.59
 f = 50Hz, oil temp. = 24.3 °C, measurement without the stirrer, type of electrodes used: partially spherical.

Sample	Breakdown voltage [kV]
1	79.8
2	84
3	85.7
4	84.9
5	83.1
6	81.8

Partial discharge measurement

- Measurement according to procedure A (PD test voltages were reached while decreasing the voltage after the power-frequency withstand test on primary winding)
- Stress voltage: 150 kV / 60 s
 Frequency: 120 Hz

Test voltage	1,2 Um = 100.8 kV	1,2 Um / √3 = 58.2 kV
Level of partial discharge	0.5 pC	0.5 pC

Remarks: background noise level: 0.5 (measured after voltage switch off), measuring circuit was calibrated with 5 pC (calibrating charge).

274

ABB Sp. z o.o. 06-300 Pizaszysz ul. Leszno 59		Routine test report of voltage instrument transformer After lightning impulse		TYPE: EMF-084 Serial no: 1HSE8851777
A-N	77-√3 kV	84/150/380 kV	Voltage factor: 1,9/8h	IEC 61869-3 50 Hz

Winding	Un [kV]	Sn [VA]	Class	Sth [VA]
1a - 1n	0,11:√3	25	0,2	1000
2a - 2n	0,11:√3	25	0,2	1000
da - dn	0,11:√3	50	3P	150

- Oil dielectric parameters check before filling (oil after treatment):
tg δ acc. IEC 60247, breakdown voltage acc. IEC 60156
- Verification of terminal markings
- Pressure and tightness test: oil overpressure: 0,8 bar / 24h - no traces of oil leakage
- Power-frequency withstand test
on primary windings
- A: Up = 120kV / 60s, f = 120Hz; N: Up = 3kV / 60s, f = 50Hz
- Up = 3 kV/60s
- Partial discharge measurement
- Power-frequency withstand test on secondary windings
- Determination of errors
- Measurement of capacitance and dielectric dissipation factor - tg δ
- Measurement of windings' resistance

Oil dielectric parameters check before filling (oil after treatment)

- Measurement of oil tg δ according to IEC
Tg δ = 0,2088 %; electrical stress = 1kV/mm, f = 50Hz, oil temp. = 90C ±1C.
- Measurement of breakdown voltage according to IEC 60156
Mean breakdown voltage = 83,22 kV, Relative standard deviation = 2,59
f = 50Hz, oil temp. = 24,3 °C, measurement without the stirrer, type of electrodes used: partially spherical.

Sample	Breakdown voltage [kV]
1	79,8
2	84
3	85,7
4	84,9
5	83,1
6	81,8

Partial discharge measurement

- Measurement according to procedure A (PD test voltages were reached while decreasing the voltage after the power-frequency withstand test on primary winding)
- Stress voltage: 120 kV / 60 s
Frequency: 120 Hz

Test voltage	1,2 Um = 100,8 kV	1,2 Um / √3 = 68,2 kV
Level of partial discharge	0,5 pC	0,5 pC

Remarks: background noise level: 0,5 (measured after voltage switch off), measuring circuit was calibrated with 5 pC (calibrating charge).

Verification of accuracy ε U%, Δφ U min
Date of measurement: 2015-10-01

1a-1n: 25 VA		1a-1n: 25 VA		p.f. = 0,8 lag.	
ε U	1,0 Un	1,0 Un	1,0 Un	1,2 Un	1,2 Un
Δφ U	-0,047	-0,046	-0,006	0,008	0,008
ε U	1,68	1,73	2,56	2,72	2,77
Δφ U	1,63	1,68	2,56	2,72	2,77
1a-1n: 6,25 VA		1a-1n: 6,25 VA		p.f. = 0,8 lag.	
ε U	1,0 Un	1,0 Un	1,0 Un	1,2 Un	1,2 Un
Δφ U	0,0274	0,0297	0,0310	0,0739	0,0753
ε U	1,42	1,47	2,45	2,50	2,55
Δφ U	1,42	1,47	2,45	2,50	2,55
2a-2n: 25 VA		2a-2n: 25 VA		p.f. = 0,8 lag.	
ε U	1,0 Un	1,0 Un	1,0 Un	1,2 Un	1,2 Un
Δφ U	0,0507	0,053	0,0543	0,0975	0,0988
ε U	1,32	1,38	2,37	2,42	2,46
Δφ U	1,32	1,38	2,37	2,42	2,46
da-dn: 50 VA		da-dn: 12,5 VA		p.f. = 0,8 lag.	
ε U	1,0 Un	1,0 Un	1,0 Un	1,2 Un	1,2 Un
Δφ U	0,0508	0,053	0,0545	0,0974	0,0988
ε U	1,335	1,37	2,36	2,41	2,46
Δφ U	1,335	1,37	2,36	2,41	2,46
1a-1n: 25VA		1a-1n: 0 VA		p.f. = 0,8 lag.	
ε U	0,05 Un	0,05 Un	0,05 Un	0,05 Un	0,05 Un
Δφ U	0,802	0,905	1,028	1,001	1,122
ε U	0,34	-0,23	0,285	2,23	2,50
Δφ U	0,34	-0,23	0,285	2,23	2,50

Measurements uncertainty: ε U ± 0,044 %, Δφ U ± 2,2 min

Measurement of capacitance and dielectric dissipation factor - tg δ


Primary voltage	Tg δ	Capacity [pF]	Leak current [mA]
10 kV	0,25	228	0,742
45,5 kV	0,26	228	3,2
48,5 kV	0,26	228	3,48

Measurement of windings' resistance

	R (24 °C)	Rct (75 °C)
A-N	14,10 kΩ	16,926 kΩ
1a-1n	112,100 mΩ	134,568 mΩ
2a-2n	104,900 mΩ	125,925 mΩ
da-dn	40,620 mΩ	48,761 mΩ

Checked by: *[Signature]*

Przasnysz, 2015-10-01



OGA
10-58

Verification of accuracy \pm U%, $\Delta\phi$ U min)
Date of measurement: 2015-11-10

1a-1n: 25 VA		1a-1n: 25 VA		1a-1n: 25 VA		p.f. = 0,8 lag.	
2a-2n: 25 VA		2a-2n: 0 VA		2a-2n: 0 VA		p.f. = 0,8 lag.	
ε U	0,8 Un	1,0 Un	1,2 Un	0,8 Un	1,0 Un	1,2 Un	1,2 Un
$\Delta\phi$ U	-0,057	-0,054	-0,053	-0,013	-0,009	-0,009	-0,009
$\Delta\phi$ U	1,9	1,9	1,9	2,9	3,0	3,0	3,0
1a-1n: 6,25 VA		1a-1n: 6,25 VA		1a-1n: 6,25 VA		p.f. = 0,8 lag.	
2a-2n: 25 VA		2a-2n: 0 VA		2a-2n: 0 VA		p.f. = 0,8 lag.	
ε U	0,8 Un	1,0 Un	1,2 Un	0,8 Un	1,0 Un	1,2 Un	1,2 Un
$\Delta\phi$ U	0,078	0,021	0,023	0,063	0,066	0,067	0,067
$\Delta\phi$ U	1,6	1,6	1,7	2,7	2,7	2,7	2,7
2a-2n: 25 VA		2a-2n: 25 VA		2a-2n: 25 VA		p.f. = 0,8 lag.	
1a-1n: 25 VA		1a-1n: 0 VA		1a-1n: 0 VA		p.f. = 0,8 lag.	
ε U	0,8 Un	1,0 Un	1,2 Un	0,8 Un	1,0 Un	1,2 Un	1,2 Un
$\Delta\phi$ U	-0,052	-0,049	-0,047	-0,007	-0,004	-0,002	-0,002
$\Delta\phi$ U	1,8	1,8	1,8	2,8	2,8	2,8	2,8
2a-2n: 6,25 VA		2a-2n: 6,25 VA		2a-2n: 6,25 VA		p.f. = 0,8 lag.	
1a-1n: 25 VA		1a-1n: 0 VA		1a-1n: 0 VA		p.f. = 0,8 lag.	
ε U	0,8 Un	1,0 Un	1,2 Un	0,8 Un	1,0 Un	1,2 Un	1,2 Un
$\Delta\phi$ U	0,021	0,024	0,026	0,066	0,069	0,071	0,071
$\Delta\phi$ U	1,6	1,6	1,7	2,6	2,6	2,6	2,7
da-dn: 50 VA		da-dn: 12,5 VA		da-dn: 12,5 VA		p.f. = 0,8 lag.	
1a-1n: 25 VA; 2a-2n: 25 VA		1a-1n: 0 VA; 2a-2n: 0 VA		1a-1n: 0 VA; 2a-2n: 0 VA		p.f. = 0,8 lag.	
ε U	0,02 Un	0,05 Un	1,0 Un	0,02 Un	0,05 Un	1,0 Un	1,9 Un
$\Delta\phi$ U	3,4	2,7	2,7	4,1	3,3	3,2	3,3

Measurements uncertainty: ε U \pm 0,044 %, $\Delta\phi$ U \pm 2,2 min

Measurement of capacitance and dielectric dissipation factor - tg δ
Temperature: 23 °C, Frequency: 50

Primary voltage	Tg δ	Capacity [pF]	Leak current [mA]
10 kV	0,33	224	0,703
45,5 kV	0,33	224	3,132
48,5 kV	0,33	224	3,412


Measurement of windings' resistance

	$\%R$ (24 °C)	Rct (75 °C)
A-N	7,74,00 k Ω	16,861 k Ω
1a-1n	108,70 m Ω	130,814 m Ω
2a-2h	102,70 m Ω	123,688 m Ω
da-dn	42,53 m Ω	51,221 m Ω

OG4
KJ-58

Checked by: *[Signature]*

Przasnysz, 2015-11-10



HIGH VOLTAGE LABORATORY
INSTYTUT ENERGETYKI

01-330 WARSZAWA, ul. Mory 8, tel. (22) 3451242
tel. fax. (22) 8368048, e-mail: ewn@ien.com.pl

EWN/109/E/15-3
Annex 3

ANNEX 3 for test report EWN/109/E/15-3
(8 pages)

Lightning impulse test protocol:
□ ewn109e15-3a



HIGH VOLTAGE LABORATORY

POLAND 01-330 WARSZAWA, ul. Micy 8
fax: (+4822) 636-90-48, mail: ewn@len.com.pl

Próba udarem uciętym 1,2/50us

project: ewn109e15-3a

test date 07-10-2015

page 1

Test - object - data

WNR EWN/109/E/15-3a TR-No. 1HSE8851777 O.-No. 4500678253

test object vector group 380

output BIL

voltage 84 kVA frequency 50 Hz

customer ABB Sp. z o. o. ul. Zeganska 1, 04-713 Warszawa



HIGH VOLTAGE LABORATORY

POLAND 01-330 WARSZAWA, ul. Micy 8
fax: (+4822) 636-90-48, mail: ewn@len.com.pl

Próba udarem uciętym 1,2/50us

project: ewn109e15-3a

page 2

LI lightning-impulse

no.	Up [kV]	T1[us]	T2[us]	Tc[us]	Ip [A]	remark
1	-190.1	1.12	45.5		-57.73	LI: A - RW(50.0%)
2	-381.4	1.12	45.1		-65.13	LI: A - FW(100.0%)
3	-219.6	1.14		3.51	-66.33	LI: A - CRW(57.5%)
4	-438.6	1.12		3.91	-79.62	LI: A - CFW(115.0%)
5	-438.4	1.13		3.62	-74.01	LI: A - CFW(115.0%)
6	-380.9	1.12	45.2		-56.15	LI: A - FW(100.0%)
7	-381.1	1.12	45.2		-56.08	LI: A - FW(100.0%)
8	-381.1	1.12	45.2		-56.17	LI: A - FW(100.0%)
9	-381.3	1.12	45.2		-56.19	LI: A - FW(100.0%)
10	-381.2	1.13	45.2		-56.08	LI: A - FW(100.0%)
11	-381.2	1.12	45.2		-56.21	LI: A - FW(100.0%)
12	-381.3	1.12	45.2		-59.65	LI: A - FW(100.0%)
13	-381.1	1.12	45.3		-56.12	LI: A - FW(100.0%)
14	-381	1.12	45.3		-56.03	LI: A - FW(100.0%)
15	-381.1	1.12	45.2		-56.15	LI: A - FW(100.0%)
16	-381.3	1.12	45.2		-56.11	LI: A - FW(100.0%)
17	-381.3	1.12	45.3		-56.14	LI: A - FW(100.0%)
18	-381.1	1.12	45.2		-56.13	LI: A - FW(100.0%)
19	-381	1.12	45.3		-56.27	LI: A - FW(100.0%)
20	191.7	1.15	45.4		57.91	LI: A - RW(50.0%)
21	380.5	1.13	45.3		56.69	LI: A - FW(100.0%)
22	380.4	1.12	45.3		56.09	LI: A - FW(100.0%)
23	380.3	1.12	45.3		59.51	LI: A - FW(100.0%)
24	380.3	1.12	45.3		56.48	LI: A - FW(100.0%)
25	380.1	1.12	45.3		56.52	LI: A - FW(100.0%)
26	380.1	1.12	45.3		56.57	LI: A - FW(100.0%)
27	380.4	1.12	45.3		56.56	LI: A - FW(100.0%)
28	380	1.12	45.3		56.67	LI: A - FW(100.0%)
29	380.4	1.12	45.3		56.69	LI: A - FW(100.0%)
30	379.8	1.12	45.3		56.23	LI: A - FW(100.0%)
31	379.9	1.12	45.4		56.53	LI: A - FW(100.0%)
32	380.2	1.12	45.4		62.05	LI: A - FW(100.0%)
33	379.9	1.12	45.3		56.42	LI: A - FW(100.0%)
34	379.9	1.12	45.4		66.38	LI: A - FW(100.0%)
35	379.8	1.12	45.4		56.55	LI: A - FW(100.0%)

277







HIGH VOLTAGE LABORATORY

POLAND 01-530 WARSZAWA, ul. Mory 8
fax: (+4822) 835-60-48, mail: ewn@jan.com.pl

Próba udarem uciekłym 1,2/50us

project: ewn109e15-3a

page 5











HIGH VOLTAGE LABORATORY

POLAND 01-530 WARSZAWA, ul. Mory 8
fax: (+4822) 835-60-48, mail: ewn@jan.com.pl

Próba udarem uciekłym 1,2/50us

project: ewn109e15-3a

page 6



279



HIGH VOLTAGE LABORATORY

POLAND 01-330 WARSZAWA, ul. Mory 8
fax: (+4822) 836-30-48, mail: ewn@ewn.com.pl

project: ewn109e15-3b

test date 14-10-2015

page 1

Test - object - data

test date 14-10-2015
factory ser.-no. 1HSE8851777
test object EMF-E084
order-no. 4500678253
specification
test-field

Climate - Data

temperature 5 °C
humidity 48 %
air-pressure 1013 hPa

EWN/109/E/15-3

HIGH VOLTAGE LABORATORY INSTYTUT ENERGETYKI

01-330 WARSZAWA, ul. Mory 8, tel. (22) 3451242
tel. fax. (22) 8368048, e-mail: ewn@ewn.com.pl

Annex 4



ANNEX 4 for test report EWN/109/E/15-3

(3 pages)

Transmitted overvoltage test protocol:

□ ewn109e15-3b

281



project: ewm109e15-3b

lightning-impulse






page 2

no.	Up [kV]	T1[μs]	T2[μs]	Tc[μs]	Up [V]	remark
1	23.52	0.49	74.4		175	1a - 1n
2	23.52	0.49	74.4		175	1a - 1n zoom
3	23.69	0.51	73.8		208.3	2a - 2n
4	23.69	0.51	73.8		208.3	2a - 2n zoom
5	23.59	0.5	74.1		136	da - dn
6	23.59	0.5	74.1		136	da - dn zoom



project: ewm109e15-3b


page 3



HIGH VOLTAGE LABORATORY



INSTYTUT ENERGETYKI



LABORATORY ACCREDITED
BY THE POLISH CENTRE FOR ACCREDITATION
Accreditation Certificate of Testing Laboratory
No AB 272

TEST REPORT
No EWN/109/E/15-4

Transmitted overvoltage test,
Electromagnetic Compatibility (EMC) tests – RIV test
of voltage instrument transformer type EMF-E145

Warsaw, November 2015



HIGH VOLTAGE LABORATORY
INSTYTUT ENERGETYKI

01-330 WARSZAWA, ul. Mory 8, tel. (22) 3451242
tel. fax. (22) 8368048, e-mail: ewn@ien.com.pl

EWN/109/E/15-4

Page 2/11

TEST REPORT EWN/109/E/15-4

TEST OBJECT: Voltage instrument transformer type EMF-E145
TEST CUSTOMER: ABB Sp. z o.o.
 04-713 Warszawa, ul. Żeganińska 1
MANUFACTURER: ABB
ORDER NO: 4500678253 (15.09.2015)
TEST TYPE: Transmitted overvoltage test
 Electromagnetic Compatibility (EMC) tests – RIV test
 According to:
 PN-EN/IEC 61869-1
 PN/EN/IEC 61869-3
 Internal ABB specifications
TEST DATE: 29.10.2015; 03.11.2015
TEST RESULT: POSITIVE- details are presented in following parts of report

TEST PERFORMERS:

Michał Molas, M. Sc. EE

AUTHORISATION:

Jerzy Mikołajczyk, M. Sc. EE

HEAD OF LABORATORY:


J. L. Mikulski, Prof., Ph. D. EE

	Signature
	Signature
	Signature
	Signature

Warsaw, November 2015.

Publication or reproduction of the Report in any other form than a complete copy thereof is forbidden without written consent of the Laboratory

283

	HIGH VOLTAGE LABORATORY INSTYTUT ENERGETYKI	EWN/109/E/15-4
	01-330 WARSZA WA, ul. Mory 8, tel. (22) 3451242 tel. fax. (22) 8368048, e-mail: ewn@len.com.pl	Page 3/11

CONTENTS


1	COMPETENCE OF THE LABORATORY	4
2	TEST OBJECT DESCRIPTION	5
3	SCOPE OF TESTS AGREED UPON	6
4	TYPE TEST	6
4.1	Electromagnetic compatibility (EMC) tests - RIV test	6
4.1.1	Method of testing and acceptance criteria	6
4.1.2	Test arrangement	7
4.1.3	Test conditions	7
4.1.4	Test results	8
5	SPECIAL TESTS	9
5.1	Transmitted overvoltage test	9
5.1.1	Method of testing and acceptance criteria	9
5.1.2	Test arrangement	9
5.1.3	Test conditions	10
5.1.4	Test results	10

Test report includes:

11	numbered pages;
3	figures;
1	photograph;
5	tables.

Attached to the test report:

- Annex 1: Documents provided by ABB Sp. z o.o. used as base of identification of test object (3 pages);
Annex 2: Transmitted overvoltage test protocol (3 pages);

	HIGH VOLTAGE LABORATORY INSTYTUT ENERGETYKI	EWN/109/E/15-4
	01-330 WARSZA WA, ul. Mory 8, tel. (22) 3451242 tel. fax. (22) 8368048, e-mail: ewn@len.com.pl	Page 4/11

1 COMPETENCE OF THE LABORATORY

The High Voltage Laboratory is in possession of accreditation issued by the Polish Centre for Accreditation (Accreditation Certificate of Testing Laboratory No AB 272) concerning following tests:

Insulators and insulator strings	- lightning and switching impulse tests
	- power frequency voltage 50 Hz tests
	- radio interference measurements
Distribution substations	- lightning and switching impulse tests
	- power frequency voltage 50 Hz tests
	- radio interference measurements
Circuit breakers, disconnectors	- lightning and switching impulse tests
	- power frequency voltage 50 Hz tests
	- radio interference measurements
Insulators	- lightning and switching impulse tests
	- power frequency voltage 50 Hz tests
	- radio interference measurements
<u>Current and voltage transformers</u>	- <u>lightning and switching impulse tests</u>
	- <u>power frequency voltage 50 Hz tests</u>
Power transformers	- lightning and switching impulse tests
	- power frequency voltage 50 Hz tests
Lightning arresters and limiters	- lightning and switching impulse tests
	- power frequency voltage 50 Hz tests
Cables and cable fittings	- lightning and switching impulse tests
	- power frequency voltage 50 Hz tests
Line and station fittings	- radio interference measurements
Occupational safety equipment	- power frequency voltage 50 Hz tests

Full scope of accreditation of High Voltage Laboratory available on www.pca.gov.pl

Note

Tests described in sub-clause 5.1 of this Report don't comply with the scope of Laboratory accreditation.


2 TEST OBJECT DESCRIPTION

The tested object was instrument voltage transformer EMF-EI45 manufactured by ABB sp. z o.o. 04-713 Warszawa, Zęgańska 1 St. (Fabryka Aparatury Wysokich i Średnich Napięć, 06-300 Przasnysz, Leszno 59 St.), with the following parameters:

Prototype 1 – EMF-EI45

Serial number: JHSE851772

- Highest voltage for equipment 145 kV
- Rated primary voltage 145000 / $\sqrt{3}$ V
- Insulation level 275 / 650 kV
- Frequency 50 Hz
- Temperature range -40 – +40 °C
- Total mass 248 kg



Phot. 1: Tested voltage transformer EMF-EI45: a) general view, b) close-up front view, c) close-up rear view

3 SCOPE OF TESTS AGREED UPON

Test plan for voltage instrument transformer type EMF-EI45 was consulted with the Customer. Tab. 1 includes the list of performed tests and requirements, which tested objects should comply with.

Tab. 1: Scope of tests of voltage instrument transformer

Item	Performed tests	Requirement
TYPE TESTS		
1	Electromagnetic Compatibility (EMC) tests - RIV test	PN-EN/IEC 61869-1, p.7.2.5
SPECIAL TESTS		
2	Transmitted overvoltage test	PN-EN/IEC 61869-1, p.7.4.4

Determination of errors of transformer, performed to prove the positive results of consecutive tests, was carried out on the premises of Factory Laboratory of ABB Sp. z o.o. in the presence of a representative of the High Voltage Department of Institute of Power Engineering. Detailed results are presented in Annex 2.

Tests were carried out according to:

- IEC 61869-1:2007 „Instrument transformers - Part 1: General requirements” (equiv. with: PN-EN 61869-1:2009 “Przekładniki – Część 1: Wymagania ogólne”)
- IEC 61869-3:2011 „Instrument transformers - Part 3: Additional requirements for inductive voltage transformers” (equiv. with: PN-EN 61869-3:2011 “Przekładniki – Część 3: Wymagania szczególne dotyczące przekładników napięciowych indukcyjnych”)

4 TYPE TEST


4.1 Electromagnetic compatibility (EMC) tests - RIV test

4.1.1 Method of testing and acceptance criteria

Measurement of the radio interference voltage was performed according to IEC 61869-1 clause 7.2.5.1. Before taking the measurement a pre-stress voltage was applied and maintained for 30 s (voltage value $U_{pre}=1.5 \cdot U_n/\sqrt{3}$). Then, within 10 seconds, the voltage was decreased to test voltage value equal to $U_p=1.1 \cdot U_n/\sqrt{3}$ and maintained at this level for another 30 s. After that time RIV value was measured. It is considered that the instrument voltage transformer passed the test with a positive result if the value of the RIV, measured at a voltage equal to U_p , does not exceed 2500 μ V (IEC 61869-1 clause 6.11.2). Besides measuring the maximal level of the RIV at a voltage equal to U_p , the RIV characteristics of the tested instrument transformer were prepared in scope of voltages equal to $0.3 \cdot U_n/\sqrt{3} - 1.1 \cdot U_n/\sqrt{3}$.

Handwritten signature

Handwritten number 285



Measurement was carried out in a measuring system shown in the Fig. 1, measuring interference voltage drop on a resistance 300Ω at frequency 0.5 MHz with a RIV voltmeter LMZ-4 of a logarithmic scale (0 dB = 1 μV on 300Ω). Before actual measurements the calibration of the measuring system was performed using a stable signal generator resulting in correction factor estimation. Moreover, the „background level” was checked within the test voltages scope 0-300 kV.




Fig. 1: Diagram of the RIV level measuring system

4.1.3 Test conditions

Test conditions for measurement of the radio interference voltage are presented in Tab. 2. No correction factors for atmospheric conditions are applicable for this test.

Tab. 2: Test conditions for measurement of the radio interference voltage

ATMOSPHERIC CONDITIONS	
Temperature	t °C 10,6
Pressure	P hPa 1009,9
Relative humidity	R % 57,2
VOLTAGES	
Pre-stress voltage	U _{krV/m} kV 125,6
Test voltage	U _p kV 92
Estimated correction factor	RIV _{cr} dB 24

4.1.4 Test results

Maximal measured RIV level at a voltage equal to U_p = 92 kV : (39 +/- 0,5) dB = 89,1 μV

Tab. 3: RIV measurement results

U [kV]	92	84	75	67	59	50	42	33	25
x U _m /√3	1,1	1	0,9	0,8	0,7	0,6	0,5	0,4	0,3
[dB]	→	15	13	10	5	0	-	-	-
	←	-	14	12	7	1	-6	-	-
RIV [dB]	→	15	13	10	6	2	-5	-	-
RIV [μV]	39	37	34	30	26	16	-	-	-
	89,1	70,8	50,1	31,6	20,0	8,9	-	-	-




Fig. 2: RIV characteristic

TEST RESULT: POSITIVE

5.1.3 Test conditions

Test conditions for transmitted overvoltage test (parameters of the measurement system and value of test voltage) are presented in Tab. 4. The influence of atmospheric condition on test voltage value was not taken into consideration.

Tab. 4: Parameters of the transmitted overvoltage measurement system and parameters of the test voltage

IMPULSE GENERATOR	
Number of steps	1
General capacitance	C_g μF 0,750
Discharge resistance	R_d Ω 150
Damping resistance	R_a Ω 89
VOLTAGE DIVIDER	
HV unit resistance	R_{u1} Ω 10098,96
LV unit resistance	R_{u2} Ω 10,06
Scale factor	ϕ_v - 1005
FRONT SHAPING CAPACITOR	
Front shaping capacitor	C_s μF 500
PARAMETERS OF THE TEST VOLTAGE	
Peak value of applied voltage	U_1 kV 19,9
Conventional front time	T_1 μs 0,46
Time to half-value	T_2 μs 73

5.1.4 Test results

Results of the transmitted overvoltage measurement are presented in Tab. 5. The oscillograms of all applied and registered impulses are present in Annex 4 of hereby Report.

5 SPECIAL TESTS

5.1 Transmitted overvoltage test

5.1.1 Method of testing and acceptance criteria

Transmitted overvoltage test was performed according to IEC 61869-3, IEC 61869-1 clause 7.4.4 and 6.11.4. During the test type „A” impulse (U_1) was applied between the primary terminal A and earth. Measurements of transmitted voltage (U_2) were carried out for all the secondary windings of the voltage instrument transformer.

It is considered that the instrument voltage transformer passed the test with a positive result if the value of the transmitted voltage (U_2) does not exceed 1,6 kV (IEC 61869-1 clause 6.11.4 Table 9).

5.1.2 Test arrangement

Arrangement for transmitted overvoltage measurement was based on one step of Marx impulse generator made by KAEBFELY. Measurement of the voltage U_1 applied to the primary terminal of the instrument transformer was performed with impulse voltage measuring system Dr Strauss TR-AS 200-14, in connection with a resistive voltage divider Siemens SMR 10/770. The transmitted voltage U_2 measurement was also performed with impulse voltage measuring system Dr Strauss TR-AS 200-14. For both measured voltages U_1 and U_2 impulse peak value measuring uncertainty doesn't exceed 2% of the measured value for the confidence interval 95% and coverage factor $k=2$. Simplified diagram of the measurement system is shown in the Fig. 3.





Fig. 3: Simplified diagram of the transmitted overvoltage measurement system IG - impulse generator; VD - voltage divider; C_s , R_g , R_1 , R_2 - generator elements; C_s - front shaping capacitor; IT - instrument transformer (general schematic representation);

Handwritten signature

Handwritten signature


Handwritten signature

288



HIGH VOLTAGE LABORATORY
INSTYTUT ENERGETYKI
 01-330 WARSZA WA, ul. Mory 8, tel. (22) 3451242
 tel. fax. (22) 8368048, e-mail: ewn@len.com.pl

EWN/109/E/15-4
 Page 11/11



HIGH VOLTAGE LABORATORY
INSTYTUT ENERGETYKI
 01-330 WARSZA WA, ul. Mory 8, tel. (22) 3451242
 tel. fax. (22) 8368048, e-mail: ewn@len.com.pl

EWN/109/E/15-4
 Annex 1

Tab. 5: Transmitted overvoltage measurement results

terminal	U ₁ KV	U ₂ V	U _t V	U _{sp} %
1a - 1n	19,9	146,8	1397,4	87,3
2a - 2n	19,9	122,5	1169,0	73,1
3a - 3n	19,9	127,9	1218,7	76,2
da - dn	19,9	102,0	970,9	60,7

Note:
 U₁ - peak value of applied voltage
 U₂ - maximal value of transmitted voltage
 U_t - maximal value of transmitted voltage for specified overvoltage U_p
 U_p - specified overvoltage U_p=1,6·U_m·√2/3
 U_{sp} - percent of permissible overvoltage U_{sp}=U_t/U_p·100%

TEST RESULT: POSITIVE

ANNEX 1 for test report EWN/109/E/15-4
 (3 pages)

Documents provided by ABB Sp. z o.o. used as base of identification of test object:

- Declaration of conformity – No. 101/2015 (EN),
- Rating plate – Document No. 1HSE 22040-PCA,
- Technical drawing – Document id. 1HSE8851772.

ABB	Declaration of conformity	ABB Sp. z o.o. Dept. in Przasnysz POLAND						
<p align="center">DECLARATION OF CONFORMITY No. 101/2015 (EN) (acc. to ISO/IEC 17050-1)</p> <p>Manufacturer: ABB</p> <p>Product: Voltage Instrument Transformer EMF-E145</p> <p>Above mentioned product conforms with the following standard :</p> <table border="0"> <tr> <td>Standard</td> <td>Title</td> <td>Edition/Date</td> </tr> <tr> <td>IEC 61869 - 3</td> <td>Voltage Instrument Transformers</td> <td>2015</td> </tr> </table> <p>Additional information: Serial numbers: 1HSE8851772;</p> <p>Place and date of issue of declaration Przasnysz 29.10.2015</p> <div style="display: flex; justify-content: space-between; margin-top: 20px;"> <div data-bbox="965 1736 1077 2004"> <p>Kierownik Operacji (PPHM) ABB Sp. z o.o. Osiedle Wyznawczych Przasnysz</p> </div> <div data-bbox="933 1355 1077 1624"> <p>Kierownik ds. Zapewnienia Jakości. ABB Sp. z o.o. Oddział w Przasnysz Krzysztof Lubecki (Signature)</p> </div> </div>			Standard	Title	Edition/Date	IEC 61869 - 3	Voltage Instrument Transformers	2015
Standard	Title	Edition/Date						
IEC 61869 - 3	Voltage Instrument Transformers	2015						

ABB		ABB AB		Made in Sweden	
Voltage transformer	EMF-E145	Production year	YYYY	IEC 61869-3	
Serial number	145000043	Rated primary voltage	145 kV	Temperature range	-40 ~ +40 °C
Insulation level	145 kV	Highest voltage for equipment	145 kV	Total mass	248 kg

Serial number	1HSE 88504-5				
Insulation oil	IEC 61039-1-10-2003-80 Kg				
Volume factor	1.978h				

Terminal	Volts V	Current VA	Burden VA	Total burden VA	Thermal limit VA
1a-1n	115/73	0.1	25	25	1500±0
2a-2n	115/73	0.1	25	25	1500±0
3a-3n	115/73	0.1	25	25	1500±0
4a-4n	115/73	0.1	25	25	1500±0
5a-5n	115/73	0.1	25	25	1500±0
6a-6n	115/73	0.1	25	25	1500±0
7a-7n	115/73	0.1	25	25	1500±0
8a-8n	115/73	0.1	25	25	1500±0
9a-9n	115/73	0.1	25	25	1500±0
10a-10n	115/73	0.1	25	25	1500±0
11a-11n	115/73	0.1	25	25	1500±0
12a-12n	115/73	0.1	25	25	1500±0
13a-13n	115/73	0.1	25	25	1500±0
14a-14n	115/73	0.1	25	25	1500±0
15a-15n	115/73	0.1	25	25	1500±0
16a-16n	115/73	0.1	25	25	1500±0
17a-17n	115/73	0.1	25	25	1500±0
18a-18n	115/73	0.1	25	25	1500±0
19a-19n	115/73	0.1	25	25	1500±0
20a-20n	115/73	0.1	25	25	1500±0
21a-21n	115/73	0.1	25	25	1500±0
22a-22n	115/73	0.1	25	25	1500±0
23a-23n	115/73	0.1	25	25	1500±0
24a-24n	115/73	0.1	25	25	1500±0
25a-25n	115/73	0.1	25	25	1500±0
26a-26n	115/73	0.1	25	25	1500±0
27a-27n	115/73	0.1	25	25	1500±0
28a-28n	115/73	0.1	25	25	1500±0
29a-29n	115/73	0.1	25	25	1500±0
30a-30n	115/73	0.1	25	25	1500±0
31a-31n	115/73	0.1	25	25	1500±0
32a-32n	115/73	0.1	25	25	1500±0
33a-33n	115/73	0.1	25	25	1500±0
34a-34n	115/73	0.1	25	25	1500±0
35a-35n	115/73	0.1	25	25	1500±0
36a-36n	115/73	0.1	25	25	1500±0
37a-37n	115/73	0.1	25	25	1500±0
38a-38n	115/73	0.1	25	25	1500±0
39a-39n	115/73	0.1	25	25	1500±0
40a-40n	115/73	0.1	25	25	1500±0
41a-41n	115/73	0.1	25	25	1500±0
42a-42n	115/73	0.1	25	25	1500±0
43a-43n	115/73	0.1	25	25	1500±0
44a-44n	115/73	0.1	25	25	1500±0
45a-45n	115/73	0.1	25	25	1500±0
46a-46n	115/73	0.1	25	25	1500±0
47a-47n	115/73	0.1	25	25	1500±0
48a-48n	115/73	0.1	25	25	1500±0
49a-49n	115/73	0.1	25	25	1500±0
50a-50n	115/73	0.1	25	25	1500±0
51a-51n	115/73	0.1	25	25	1500±0
52a-52n	115/73	0.1	25	25	1500±0
53a-53n	115/73	0.1	25	25	1500±0
54a-54n	115/73	0.1	25	25	1500±0
55a-55n	115/73	0.1	25	25	1500±0
56a-56n	115/73	0.1	25	25	1500±0
57a-57n	115/73	0.1	25	25	1500±0
58a-58n	115/73	0.1	25	25	1500±0
59a-59n	115/73	0.1	25	25	1500±0
60a-60n	115/73	0.1	25	25	1500±0
61a-61n	115/73	0.1	25	25	1500±0
62a-62n	115/73	0.1	25	25	1500±0
63a-63n	115/73	0.1	25	25	1500±0
64a-64n	115/73	0.1	25	25	1500±0
65a-65n	115/73	0.1	25	25	1500±0
66a-66n	115/73	0.1	25	25	1500±0
67a-67n	115/73	0.1	25	25	1500±0
68a-68n	115/73	0.1	25	25	1500±0
69a-69n	115/73	0.1	25	25	1500±0
70a-70n	115/73	0.1	25	25	1500±0
71a-71n	115/73	0.1	25	25	1500±0
72a-72n	115/73	0.1	25	25	1500±0
73a-73n	115/73	0.1	25	25	1500±0
74a-74n	115/73	0.1	25	25	1500±0
75a-75n	115/73	0.1	25	25	1500±0
76a-76n	115/73	0.1	25	25	1500±0
77a-77n	115/73	0.1	25	25	1500±0
78a-78n	115/73	0.1	25	25	1500±0
79a-79n	115/73	0.1	25	25	1500±0
80a-80n	115/73	0.1	25	25	1500±0
81a-81n	115/73	0.1	25	25	1500±0
82a-82n	115/73	0.1	25	25	1500±0
83a-83n	115/73	0.1	25	25	1500±0
84a-84n	115/73	0.1	25	25	1500±0
85a-85n	115/73	0.1	25	25	1500±0
86a-86n	115/73	0.1	25	25	1500±0
87a-87n	115/73	0.1	25	25	1500±0
88a-88n	115/73	0.1	25	25	1500±0
89a-89n	115/73	0.1	25	25	1500±0
90a-90n	115/73	0.1	25	25	1500±0
91a-91n	115/73	0.1	25	25	1500±0
92a-92n	115/73	0.1	25	25	1500±0
93a-93n	115/73	0.1	25	25	1500±0
94a-94n	115/73	0.1	25	25	1500±0
95a-95n	115/73	0.1	25	25	1500±0
96a-96n	115/73	0.1	25	25	1500±0
97a-97n	115/73	0.1	25	25	1500±0
98a-98n	115/73	0.1	25	25	1500±0
99a-99n	115/73	0.1	25	25	1500±0
100a-100n	115/73	0.1	25	25	1500±0

Serial number 1HSE mmmmm = 1HSE 8851772
 Production year yyyy = Actual year for production

Prepared	Gustaf Högberg	2015-06-18	PPHC/IM	Rating plate
Approved	Björn Sjöström	2015-06-18	This over department	
Order no.	E90000012-10			
Document No.	1HSE 22040-PCA			

We reserve all rights in this document if the information contained herein is used for any purpose without express authority in writing from ABB Power Technologies AB (SE).
 This document is issued by means of a computerized system. The digitally stored original is electronically approved. The approved document has a date entered in the 'Approved' field. A manual signature is not required.



HIGH VOLTAGE LABORATORY
INSTYTUT ENERGETYKI

01-330 WARSZAWA, ul. Mory 8, tel. (22) 3451242
 tel. fax. (22) 8368048, e-mail: ewn@heia.com.pl

EWN/109/E/15-4


Annex 2

ANNEX 2 for test report EWN/109/E/15-4

(3 pages)

Transmitted overvoltage test protocol:

□ ewn109e15-4b



040



project: ewm109e15-4b

test date 29-10-2015

page 1

Test - object - data

test date 29-10-2015
factory ser.-no. 1HSE8851772
test object EMF-E145
order-no. 4500678253
specification
test-field

Climate - Data

temperature 7.7 °C humidity 73.9 %
air-pressure 1007 hPa

ewm 29A



project: ewm109e15-4b

page 2


LI lightning-impulsa

no.	Up [kV]	T1 [µs]	T2 [µs]	Tc [µs]	Up [V]	remark
1	19.9	0.46	72.8		146.8	1a - 1n
2	19.9	0.46	72.8		146.8	1a - 1n zoom
3	19.85	0.46	73		122.5	2a - 2n
4	19.85	0.46	73		122.5	2a - 2n zoom
5	19.88	0.46	73		-127.9	3a - 3n
6	19.88	0.46	73		-127.9	3a - 3n zoom
7	19.9	0.46	72.8		-102	1da - dn
8	19.9	0.46	72.8		-102	1da - dn zoom

HIGH VOLTAGE LABORATORY



INSTYTUT ENERGETYKI



LABORATORY ACCREDITED
BY THE POLISH CENTRE FOR ACCREDITATION
Accreditation Certificate of Testing Laboratory
No AB 272

TEST REPORT
No EWN/109/E/15-5

Electromagnetic Compatibility (EMC) tests - RIV test
of voltage instrument transformer type EMF-E145

Warsaw, November 2015



HIGH VOLTAGE LABORATORY INSTYTUT ENERGETYKI

01-330 WARSZAWA, ul. Mory 8, tel. (22) 3451242
tel. fax. (22) 8368048, e-mail: ewn@icn.com.pl

EWN/109/E/15-5

Page 2/8

TEST REPORT EWN/109/E/15-5

TEST OBJECT: Voltage instrument transformer type EMF-E145

TEST CUSTOMER: ABB Sp. z o.o.
04-713 Warszawa, ul. Żegawska 1

MANUFACTURER: ABB

ORDER NO: 4500678253 (15.09.2015)

TEST TYPE: Electromagnetic Compatibility (EMC) tests - RIV test

TEST PROCEDURE: According to:
PN-EN/IEC 61869-1
PN-EN/IEC 61869-3
Internal ABB specifications

TEST DATE: 04.11.2015

TEST RESULT: POSITIVE - details are presented in following parts of report

TEST PERFORMERS:

Michał Molas, M. Sc. EE

Adam Wieleńek, Tech.

AUTHORISATION:

Jerzy Mikołajczyk, M. Sc. EE

HEAD OF LABORATORY:

J. L. Mikulski, Prof., Ph. D. EE

	Signature
	Signature
	Signature
	Signature

Warsaw, November 2015.

Publication or reproduction of the Report in any other form than a complete copy thereof is forbidden without written consent of the Laboratory



HIGH VOLTAGE LABORATORY
INSTYTUT ENERGETYKI

01-330 WARSZAWA, ul. Mory 8, tel. (22) 3451242
 tel. fax. (22) 8368048, e-mail: ewn@iem.com.pl

EWN/109/E/15-5

Page 3/8

CONTENTS

1	COMPETENCE OF THE LABORATORY	4
2	TEST OBJECT DESCRIPTION	5
3	SCOPE OF TESTS AGREED UPON	6
4	TYPE TEST	6
4.1	Electromagnetic compatibility (EMC) tests - RIV test	6
4.1.1	Method of testing and acceptance criteria	6
4.1.2	Test arrangement	7
4.1.3	Test conditions	7
4.1.4	Test results	8

Test report includes:

- 8 numbered pages;
- 2 figures;
- 1 photograph;
- 3 tables.

Attached to the test report:

Annex 1: Documents provided by ABB Sp. z o.o. used as base of identification of test object (3 pages);



HIGH VOLTAGE LABORATORY
INSTYTUT ENERGETYKI

01-330 WARSZAWA, ul. Mory 8, tel. (22) 3451242
 tel. fax. (22) 8368048, e-mail: ewn@iem.com.pl

EWN/109/E/15-5

Page 4/8

1 COMPETENCE OF THE LABORATORY

The High Voltage Laboratory is in possession of accreditation issued by the Polish Centre for Accreditation (Accreditation Certificate of Testing Laboratory No AB 272) concerning following tests:

- Insulators and insulator strings
 - lightning and switching impulse tests
 - power frequency voltage 50 Hz tests
 - radio interference measurements
- Distribution substations
 - lightning and switching impulse tests
 - power frequency voltage 50 Hz tests
 - radio interference measurements
- Circuit breakers, disconnectors
 - lightning and switching impulse tests
 - power frequency voltage 50 Hz tests
 - radio interference measurements
- Insulators
 - lightning and switching impulse tests
 - power frequency voltage 50 Hz tests
 - radio interference measurements
- Current and voltage transformers
 - lightning and switching impulse tests
 - power frequency voltage 50 Hz tests
- Power transformers
 - lightning and switching impulse tests
 - power frequency voltage 50 Hz tests
- Lightning arresters and limiters
 - lightning and switching impulse tests
 - power frequency voltage 50 Hz tests
- Cables and cable fittings
 - lightning and switching impulse tests
 - power frequency voltage 50 Hz tests
- Line and station fittings
 - radio interference measurements
- Occupational safety equipment
 - power frequency voltage 50 Hz tests

Full scope of accreditation of High Voltage Laboratory available on www.pca.gov.pl

244



HIGH VOLTAGE LABORATORY
INSTYTUT ENERGETYKI

01-330 WARSZAWA, ul. Mory 8, tel. (22) 3451242
tel. fax. (22) 8368048, e-mail: ewn@ten.com.pl

EWN/109/E/15-5

Page 5/8




2 TEST OBJECT DESCRIPTION

The tested object was instrument voltage transformer EMF-EI45 manufactured by ABB sp. z o.o. 04-713 Warszawa, Żegalska 1 St. (Fabryka Aparatury Wysokich i Średnich Napięć, 06-300 Przasnysz, Leszno 59 St.), with the following parameters:

Prototype 2 – EMF-EI45

Serial number: IHSE851773

- Highest voltage for equipment 145 kV
- Rated primary voltage 145000 / $\sqrt{3}$ V
- Insulation level 275 / 650 kV
- Frequency 50 Hz
- Temperature range -40 – +40 °C
- Total mass 295 kg



Phot. 1: Tested voltage transformer EMF-EI45: a) general view, b) close-up front view, c) close-up rear view

245



HIGH VOLTAGE LABORATORY
INSTYTUT ENERGETYKI

01-330 WARSZAWA, ul. Mory 8, tel. (22) 3451242
tel. fax. (22) 8368048, e-mail: ewn@ten.com.pl

EWN/109/E/15-5

Page 6/8

3 SCOPE OF TESTS AGREED UPON

Test plan for voltage instrument transformer type EMF-EI45 was consulted with the Customer. Tab. 1 includes the list of performed tests and requirements, which tested objects should comply with.

Tab. 1: Scope of tests of voltage instrument transformer

Item	Performed tests	Requirement
TYPE TESTS		
1	Electromagnetic Compatibility (EMC) tests - RIV test	PN-EN/IEC 61869-1, p.7.2.5

Determination of errors of transformer, performed to prove the positive results of consecutive tests, was carried out on the premises of Factory Laboratory of ABB Sp. z o.o. in the presence of a representative of the High Voltage Department of Institute of Power Engineering. Detailed results are presented in Annex 2.

Tests were carried out according to:

- IEC 61869-1:2007 „Instrument transformers - Part 1: General requirements” (equiv. with: PN-EN 61869-1:2009 „Przekładniki – Część 1: Wymagania ogólne”)
- IEC 61869-3:2011 „Instrument transformers - Part 3: Additional requirements for inductive voltage transformers” (equiv. with: PN-EN 61869-3:2011 „Przekładniki – Część 3: Wymagania szczególne dotyczące przekładników napięciowych indukcyjnych”)

4 TYPE TEST

4.1 Electromagnetic compatibility (EMC) tests - RIV test

4.1.1 Method of testing and acceptance criteria

Measurement of the radio interference voltage was performed according to IEC 61869-1 clause 7.2.5.1. Before taking the measurement a pre-stress voltage was applied and maintained for 30 s (voltage value $U_{rvp} = 1.5 \cdot U_m / \sqrt{3}$). Then, within 10 seconds, the voltage was decreased to test voltage value equal to $U_p = 1.1 \cdot U_m / \sqrt{3}$ and maintained at this level for another 30 s. After that time RIV value was measured. It is considered that the instrument voltage transformer passed the test with a positive result if the value of the RIV, measured at a voltage equal to U_p , does not exceed 2500 μV (IEC 61869-1 clause 6.11.2).

Besides measuring the maximal level of the RIV at a voltage equal to U_p , the RIV characteristics of the tested instrument transformer were prepared in scope of voltages equal to $0.3 \cdot U_m / \sqrt{3} - 1.1 \cdot U_m / \sqrt{3}$.



4.1.2 Test arrangement

Measurement was carried out in a measuring system shown in the Fig. 1, measuring interference voltage drop on a resistance 300Ω at frequency 0.5 MHz with a RIV voltmeter LMZ-4 of a logarithmic scale ($0\text{ dB} = 1\text{ }\mu\text{V}$ on 300Ω). Before actual measurements the calibration of the measuring system was performed using a stable signal generator resulting in correction factor estimation. Moreover, the „background level” was checked within the test voltages scope $0\text{-}300\text{ kV}$.




Fig. 1: Diagram of the RIV level measuring system

4.1.3 Test conditions

Test conditions for measurement of the radio interference voltage are presented in Tab. 2. No correction factors for atmospheric conditions are applicable for this test.

Tab. 2: Test conditions for measurement of the radio interference voltage

ATMOSPHERIC CONDITIONS	
Temperature	t °C 10,5
Pressure	p hPa 1010
Relative humidity	R % 61
VOLTAGES	
Pre-stress voltage	$U_{20/50}$ kV 125,6
Test voltage	U_p kV 92
Estimated correction factor	RIV_{CF} dB 24



4.1.4 Test results

Maximal measured RIV level at a voltage equal to $U_p = 92\text{ kV}$: $(37 \pm 0,5)\text{ dB} = 70,8\text{ }\mu\text{V}$

Tab. 3: RIV measurement results

U [kV]	92	84	75	67	59	50	42	33	25
$x U_{m\Delta 3}$	1,1	1	0,9	0,8	0,7	0,6	0,5	0,4	0,3
[dB]	→	14	10	8	0	-	-	-	-
	→	-	11	9	1	-4	-	-	-
	→	13	10	8	1	-5	-	-	-
RIV [dB]	37	34	32	25	19	-	-	-	-
RIV [μV]	70,8	50,1	39,8	17,8	8,9	-	-	-	-




Fig. 2: RIV characteristic

TEST RESULT: POSITIVE



**HIGH VOLTAGE LABORATORY
INSTYTUT ENERGETYKI**

01-330 WARSZAWA, ul. Mory 8, tel. (22) 3451242
tel. fax. (22) 8368048, e-mail: ewnl@ten.com.pl

EWN/109/E/15-5

Annex 1

ANNEX 1 for test report EWN/109/E/15-5

(3 pages)

Documents provided by ABB Sp. z o.o. used as base of identification of test

object:

- Declaration of conformity – No. 102/2015 (EN),
- Rating plate – Document No. 1HSE 22040-PCB,
- Technical drawing – Document id. 1HSE8851773.



ABB	Declaration of conformity	ABB Sp. z o.o. Dept. in Przasnysz POLAND
DECLARATION OF CONFORMITY No. 102/2015 (EN) (acc. to ISO/IEC 17050-1)		
Manufacturer: ABB		
Product: Voltage Instrument Transformer EMF-E145		
Above mentioned product conforms with the following standard :		
Standard IEC 61869 - 3	Title Voltage Instrument Transformers	Edition/Date 2015
Additional information: Serial numbers: 1HSE8851773;		
Place and date of issue of declaration Przasnysz 29.10.2015		
<div style="display: flex; justify-content: space-between;"> <div data-bbox="821 750 957 949"> <p>Kierownik Oddziału Przemysłowego ABB Sp. z o.o. Przasnysz</p>  <p>Krzysztof Lubecki</p> </div> <div data-bbox="821 414 957 750"> <p>Kierownik ds. Zapewnienia Jakości ABB Sp. z o.o. Oddział w Przasnysz</p>  <p>Krzysztof Lubecki</p> </div> <div data-bbox="821 203 957 414"> <p>..... (Signature)</p> </div> </div>		

ABB Voltage transformer
 Serial number: 21577550
 Insulation level: 145 kV
 Highest voltage for equipment: 145 kV
 Frequency: 50 Hz
 Total mass: 295 kg
 Made in Sweden
 Type: EMVF-15/145
 Production year: 2007
 Standard: IEC 61865-3

Serial number: IHSE8851773
 Insulation oil: IEC 61033 LANTO-205 30 kg
 Voltage level: 145 kV

Terminal	Class	Burden VA	Yearly burden VA	Thermal limit VA
1a	0.1	0.1	0.1	0.1
1b	0.1	0.1	0.1	0.1
1c	0.1	0.1	0.1	0.1
1d	0.1	0.1	0.1	0.1
1e	0.1	0.1	0.1	0.1
1f	0.1	0.1	0.1	0.1
1g	0.1	0.1	0.1	0.1
1h	0.1	0.1	0.1	0.1
1i	0.1	0.1	0.1	0.1
1j	0.1	0.1	0.1	0.1
1k	0.1	0.1	0.1	0.1
1l	0.1	0.1	0.1	0.1
1m	0.1	0.1	0.1	0.1
1n	0.1	0.1	0.1	0.1
1o	0.1	0.1	0.1	0.1
1p	0.1	0.1	0.1	0.1
1q	0.1	0.1	0.1	0.1
1r	0.1	0.1	0.1	0.1
1s	0.1	0.1	0.1	0.1
1t	0.1	0.1	0.1	0.1
1u	0.1	0.1	0.1	0.1
1v	0.1	0.1	0.1	0.1
1w	0.1	0.1	0.1	0.1
1x	0.1	0.1	0.1	0.1
1y	0.1	0.1	0.1	0.1
1z	0.1	0.1	0.1	0.1

ABB Technology Ltd
 Project: EMVF-15/145
 Drawing: 2015-14-03
 Date: 2015-14-03
 Design: Dispart
 Project: P. Östergren
 Checked: P. Östergren
 Approved: P. Östergren
 2015-14-03
 Copyright 2015 ABB

Mass = 274 kg

Item No.	Qty	Part No.	Name	Remark
1	1	20HV027027	Truck	
2	1	20HV027053	Truck Cover	
3	1	20HV02824	Yoke	
4	1	20HV027059	Plug	
5	17	-	Washer	
6	20	-	Ball	
7	4	-	Nut	
8	1	20HV042554	Terminal Box	
9	8	-	Washer	
10	4	-	Eye Nut	
11	1	IHSE81669-8	Bracket	
12	1	IHSE85314-8	Expansion Spring	
13	1	20HV027101	Pin	
14	1	20HV027107	Eye Nut	
15	80	-	Oil	
16	1	-	Ball	

Serial number IHSE nnnnnnn = IHSE 8851773
 Production year yyyy = Actual year for production

Prepared: Gustaf Högberg
 Approved: Björn Sjöström
 Revision: A
 Date changed: 2015-07-01


Responsible department: PPHC/JM
 Title: Rating plate
 Part: 1
 Sheet: 1

Order No.: E90000012-20
 Document No.: IHSE 22040-PCB

ABB ABB AB

This document is issued by means of a computerized system. The digitally stored original is electronically approved. The approved document has a date oriented in the Approved field. A manual signature is not required.

HIGH VOLTAGE LABORATORY



INSTYTUT ENERGETYKI



LABORATORY ACCREDITED
BY THE POLISH CENTRE FOR ACCREDITATION
Accreditation Certificate of Testing Laboratory
No AB 272



TEST REPORT
No EWN/109/E/15-7

Electromagnetic Compatibility (EMC) tests – RIV test
of voltage instrument transformer type EMF-E145

Warsaw, December 2015



HIGH VOLTAGE LABORATORY
INSTYTUT ENERGETYKI
01-330 WARSZAWA, ul. Mory 8, tel. (22) 3451242
tel. fax. (22) 8368048, e-mail: ewn@ien.com.pl

EWN/109/E/15-7

Page 2/8

TEST REPORT EWN/109/E/15-7

TEST OBJECT: Voltage instrument transformer type EMF-E145
TEST CUSTOMER: ABB Sp. z o.o.
04-713 Warszawa, ul. Żegawska 1
MANUFACTURER: ABB
ORDER NO: 4500678253 (15.09.2015)
TEST TYPE: Electromagnetic Compatibility (EMC) tests – RIV test
TEST PROCEDURE: According to:
PN-EN/IEC 61869-1
PN-EN/IEC 61869-3
Internal ABB specifications
TEST DATE: 21.12.2015
TEST RESULT: **POSITIVE** - details are presented in following parts of report

TEST PERFORMERS:

Michał Mołas, M. Sc. EE

Adam Wroblec, Tech.

AUTHORISATION:

Jerzy Mikołajczyk, M. Sc. EE

HEAD OF LABORATORY:


J. L. Mikulski, Prof., Ph. D. EE

	Signature
	Signature
	Signature
	Signature

Warsaw, December 2015.

Publication or reproduction of the Report in any other form than a complete copy thereof is forbidden without written consent of the Laboratory

249



HIGH VOLTAGE LABORATORY
INSTYTUT ENERGETYKI
 01-330 WARSZAWA, ul. Mory 8, tel. (22) 3451242
 tel. fax. (22) 8368048, e-mail: ewn@len.com.pl

EWN/109/E/15-7

Page 3/8

CONTENTS


1	COMPETENCE OF THE LABORATORY	4
2	TEST OBJECT DESCRIPTION	5
3	SCOPE OF TESTS AGREED UPON	6
4	TYPE TEST	6
4.1	Electromagnetic compatibility (EMC) tests - RIV test	6
4.1.1	Method of testing and acceptance criteria	6
4.1.2	Test arrangement	6
4.1.3	Test conditions	7
4.1.4	Test results	8

Test report includes:

- 8 numbered pages;
- 2 figures;
- 1 photograph;
- 3 tables.

Attached to the test report:

Annex 1: Documents provided by ABB Sp. z o.o. used as base of identification of test object (3 pages);



HIGH VOLTAGE LABORATORY
INSTYTUT ENERGETYKI
 01-330 WARSZAWA, ul. Mory 8, tel. (22) 3451242
 tel. fax. (22) 8368048, e-mail: ewn@len.com.pl

EWN/109/E/15-7

Page 4/8

1 COMPETENCE OF THE LABORATORY

The High Voltage Laboratory is in possession of accreditation issued by the Polish Centre for Accreditation (Accreditation Certificate of Testing Laboratory No AB 272) concerning following tests:

- Insulators and insulator strings
 - lightning and switching impulse tests
 - power frequency voltage 50 Hz tests
 - radio interference measurements
- Distribution substations
 - lightning and switching impulse tests
 - power frequency voltage 50 Hz tests
 - radio interference measurements
- Circuit breakers, disconnectors
 - lightning and switching impulse tests
 - power frequency voltage 50 Hz tests
 - radio interference measurements
- Insulators
 - lightning and switching impulse tests
 - power frequency voltage 50 Hz tests
 - radio interference measurements
- Current and voltage transformers
 - lightning and switching impulse tests
 - power frequency voltage 50 Hz tests
 - radio interference measurements
- Power transformers
 - lightning and switching impulse tests
 - power frequency voltage 50 Hz tests
- Lightning arresters and limiters
 - lightning and switching impulse tests
 - power frequency voltage 50 Hz tests
- Cables and cable fittings
 - lightning and switching impulse tests
 - power frequency voltage 50 Hz tests
- Line and station fittings
 - lightning and switching impulse tests
 - radio interference measurements
- Occupational safety equipment
 - power frequency voltage 50 Hz tests

Full scope of accreditation of High Voltage Laboratory available on www.pca.gov.pl


2 TEST OBJECT DESCRIPTION

The tested object was instrument voltage transformer EMF-EI45 manufactured by ABB sp. z o.o. 04-713 Warszawa, Żegalska 1 St. (Fabryka Aparatury Wysokich i Średnich Napięć, 06-300 Przasnysz, Leszno 59 St.), with the following parameters:

Prototype 2 – EMF-EI45

Serial number: 1HSE851773

- Highest voltage for equipment 145 kV
- Rated primary voltage 145000 / $\sqrt{3}$ V
- Insulation level 275 / 650 kV
- Frequency 50 Hz
- Temperature range -40 – +40 °C
- Total mass 295 kg



Phot. 1: Tested voltage transformer EMF-EI45: a) general view, b) close-up front view, c) close-up side view

304.



3 SCOPE OF TESTS AGREED UPON

Test plan for voltage instrument transformer type EMF-EI45 was consulted with the Customer. Tab. 1 includes the list of performed tests and requirements, which tested objects should comply with.

Tab. 1: Scope of tests of voltage instrument transformer

Item	Performed tests	Requirement
TYPE TESTS		
1	Electromagnetic Compatibility (EMC) tests - RIV test	PN-EN/IEC 61869-1, p.7.2.5

Tests were carried out according to:

- IEC 61869-1:2007 „Instrument transformers - Part 1: General requirements” (equiv. with: PN-EN 61869-1:2009 “Przekładniki – Część 1: Wymagania ogólne”)
- IEC 61869-3:2011 „Instrument transformers - Part 3: Additional requirements for inductive voltage transformers” (equiv. with: PN-EN 61869-3:2011 “Przekładniki – Część 3: Wymagania szczególne dotyczące przekładników napięciowych indukcyjnych”)

4 TYPE TEST

4.1 Electromagnetic compatibility (EMC) tests - RIV test

4.1.1 Method of testing and acceptance criteria

Measurement of the radio interference voltage was performed according to IEC 61869-1 clause 7.2.5.1. Before taking the measurement a pre-stress voltage was applied and maintained for 30 s (voltage value $U_{RIVm}=1.5 \cdot U_m \sqrt{3}$). Then, within 10 seconds, the voltage was decreased to test voltage value equal to $U_p=1.1 \cdot U_m \sqrt{3}$ and maintained at this level for another 30 s. After that time RIV value was measured. It is considered that the instrument voltage transformer passed the test with a positive result if the value of the RIV, measured at a voltage equal to U_p , does not exceed 2500 $\mu V = 68.6$ dB (IEC 61869-1 clause 6.11.2).

Besides measuring the maximal level of the RIV at a voltage equal to U_p , the RIV characteristics of the tested instrument transformer were prepared in scope of voltages equal to $0.3 \cdot U_m \sqrt{3} - 1.1 \cdot U_m \sqrt{3}$.

4.1.2 Test arrangement

Measurement was carried out in a measuring system shown in the Fig. 1, measuring interference voltage drop on a resistance 300 Ω at frequency 0,5 MHz with a RIV voltmeter LMZ-4 of a logarithmic scale (0 dB = 1 μV on 300 Ω). Before actual measurements the calibration of the measuring system was performed using a stable signal generator resulting in correction factor estimation. Moreover, the „background level” was checked within the test voltages scope 0-300 kV.

[Handwritten signature]




Fig. 1: Diagram of the RIV level measuring system

4.1.3 Test conditions

Test conditions for measurement of the radio interference voltage are presented in Tab. 2. No correction factors for atmospheric conditions are applicable for this test.

Tab. 2: Test conditions for measurement of the radio interference voltage

ATMOSPHERIC CONDITIONS	
Temperature	t °C 10,1
Pressure	P hPa 1007,4
Relative humidity	R % 79,8
VOLTAGES	
Pre-stress voltage	U_{rvps} kV 125,6
Test voltage	U_p kV 92
Estimated correction factor	RIV _{cr} dB 23



4.1.4 Test results

Maximal measured RIV level at a voltage equal to $U_p = 92$ kV : 22 dB = 12,6 μV

Tab. 3: RIV measurement results

U [kV]	92	84	75	67	59	50	42	33	25
$x U_p \sqrt{3}$	1,1	1	0,9	0,8	0,7	0,6	0,5	0,4	0,3
[dB]	-	-1	-3	-	-	-	-	-	-
	-	-	-2	-5	-	-	-	-	-
	-	-1	-2	-4	-	-	-	-	-
RIV [dB]	22	21	19	-	-	-	-	-	-
RIV [μV]	12,6	11,2	8,9	-	-	-	-	-	-




Fig. 2: RIV characteristic

TEST RESULT: POSITIVE



**HIGH VOLTAGE LABORATORY
INSTYTUT ENERGETYKI**

01-330 WARSZAWA, ul. Mory 8, tel. (22) 3451242
tel. fax. (22) 3368048, e-mail: ewn@en.com.pl

EWN/109/E/15-7


Annex 1

ANNEX 1 for test report EWN/109/E/15-7

(3 pages)

Documents provided by ABB Sp. z o.o. used as base of identification of test object:

- Declaration of conformity – No. 102/2015 (EN),
- Rating plate – Document No. 1HSE 22040-PCB,
- Technical drawing – Document id. 1HSE8851773.

ABB	Declaration of conformity	ABB Sp. z o.o. Dept. in Przasnysz POLAND
DECLARATION OF CONFORMITY No. 102/2015 (EN) (acc. to ISO/IEC 17050-1)		
Manufacturer:	ABB	
Product:	Voltage Instrument Transformer EMF-E145	
Above mentioned product conforms with the following standard :		
Standard	Title	Edition/Date
IEC 61869 - 3	Voltage Instrument Transformers	2015
Additional information: Serial numbers: 1HSE8851773;		
Place and date of issue of declaration Przasnysz 29.10.2015		
Kierownik ds. Zapewnienia Jakości: ABB Sp. z o.o. Oddział w Przasnyszu  Krzysztof Lubocki (Signature)		

4

ABB Voltage transformer

ABB AB
Type: EMF-E145
Production year: 2015

Serial number: 1HSE8851773
Standard: IEC 61851-3

Rated primary voltage: 275/650 kV
Frequency: 50 Hz

Rated secondary voltage: 145 kV
Temperature range: -40 to +40 °C

Weight: 295 kg


1HSE 08504-5

Serial number: 1HSE8851773

Regulation coil: 1HSE 08504-5

Voltage factor: 1.27

Terminal	Volts V	Class	Burden VA	Total burden VA	Thermal limit VA
AS-N	145000/3	0.1	25	25	5000
1a-1b	15750	0.1	25	25	5000
2a-2b	15750	0.1	25	25	5000
3a-3b	15750	0.1	25	25	5000
4a-4b	15750	0.1	25	25	5000
5a-5b	15750	0.1	25	25	5000
6a-6b	15750	0.1	25	25	5000
7a-7b	15750	0.1	25	25	5000
8a-8b	15750	0.1	25	25	5000
9a-9b	15750	0.1	25	25	5000
10a-10b	15750	0.1	25	25	5000
11a-11b	15750	0.1	25	25	5000
12a-12b	15750	0.1	25	25	5000
13a-13b	15750	0.1	25	25	5000
14a-14b	15750	0.1	25	25	5000
15a-15b	15750	0.1	25	25	5000
16a-16b	15750	0.1	25	25	5000



1HSE 08504-4

Serial number 1HSE nnnnnn = 1HSE 8851773
Production year yyyy = Actual year for production

Prepared: Gustaf Högberg
Approved: Björn Sjöström
Revision: A

Responsible department: PPHCM
Date over: 2015-06-18

Title: Rating plate

Order No.: E9000012-20
Document No.: 1HSE 22040-PCB

Language: CH
Sheet: 1 of 1

1HSE 22040-PCB

We reserve all rights in this document and in the information contained herein. Reproduction, use or disclosure to third parties without express authority is strictly forbidden. © ABB Power Technologies AB (SE)

This document is issued by means of a computerized system. The digitally signed original is electronically approved. The approval comment has a date entered in the Approved field. A manual signature is not.

ABB Technology Ltd
1HSE8851773
Voltage Transformer EMF-E145

Approved: 2015-12-22
Reviewed: 2015-12-22
Checked: 2015-12-22

Part No. Name Qty

16	1	1HSE1688-B	Base
15	1	2GHV27107	Oil
14	1	2GHV27101	HY Oil
13	1	2GHV27101	Flux
12	1	2GHV27101	Flux
11	1	2GHV27101	Flux
10	4	1HSE1688-B	Flux
9	8	1HSE1688-B	Flux
8	1	2GHV4254	Terminal Box
7	4	2GHV4254	Terminal Box
6	20	2GHV4254	Terminal Box
5	17	2GHV4254	Terminal Box
4	1	2GHV27059	Flux
3	1	2GHV27059	Flux
2	1	2GHV27059	Flux
1	1	2GHV27059	Flux

Mass = 310 kg

Dimensions: 450, 410, 450, 410, 693, 522, 602, 1907, 1005, 4xØ 30, 691, 1685, Ø 448

HIGH VOLTAGE LABORATORY



INSTYTUT ENERGETYKI



LABORATORY ACCREDITED
BY THE POLISH CENTRE FOR ACCREDITATION
Accreditation Certificate of Testing Laboratory
No AB 272

TEST REPORT
No EWN/134/E/15

Impulse voltage withstand test on primary terminal,
chopped impulse voltage withstand test on primary terminal,
of voltage instrument transformer type EMF-EI45

Warsaw, November 2015



HIGH VOLTAGE LABORATORY
INSTYTUT ENERGETYKI
01-330 WARSZAWA, ul. Mory 8, tel. (22) 3451242
tel. fax. (22) 8368048, e-mail: ewn@ten.com.pl

EWN/134/E/15

Page 2/8

TEST REPORT EWN/134/E/15

TEST OBJECT: Voltage instrument transformer type EMF-EI45

TEST CUSTOMER: ABB Sp. z o.o.
04-713 Warszawa, ul. Żegajńska 1

MANUFACTURER: ABB

ORDER NO: 4500692511 (05.11.2015)

TEST TYPE: Impulse voltage withstand test on primary terminal,
Chopped impulse voltage withstand test on primary terminal

TEST PROCEDURE: According to:
PN-EN/IEC 61869-1
PN/EN/IEC 61869-3
Internal ABB specifications

TEST DATE: 06.11.2015

TEST RESULT: **POSITIVE** - details are presented in following parts of report

TEST PERFORMERS:

Michał Molas, M. Sc. EE

Jan Szolalski, M. Sc. EE

AUTHORISATION:

Jerzy Mikołajczyk, M. Sc. EE

HEAD OF LABORATORY:

J. L. Mikulski, Prof., Ph. D. EE

	Signature
	Signature
	Signature
	Signature

Warsaw, November 2015.

Publication or reproduction of the Report in any other form than a complete copy thereof is forbidden without written consent of the Laboratory



CONTENTS

1	COMPETENCE OF THE LABORATORY	4
2	TEST OBJECT DESCRIPTION	5
3	SCOPE OF TESTS AGREED UPON	6
4	TYPE TEST	6
	4.1 Impulse voltage withstand test on primary terminal	
	4.1.1 Method of testing and acceptance criteria	6
	4.1.2 Test arrangement	6
	4.1.3 Test conditions	6
	4.1.4 Test results	7
5	SPECIAL TESTS	8
	5.1 Chopped impulse voltage withstand test on primary terminal	8

Test report includes:

- 8 numbered pages;
- 1 figure;
- 1 photograph;
- 3 tables.

Attached to the test report:

- Annex 1: Documents provided by ABB Sp. z o.o. used as base of identification of test object (3 pages);
- Annex 2: Reports of routine test and determination of errors (8 pages);
- Annex 3: Lightning impulse test protocol (7 pages);



1 COMPETENCE OF THE LABORATORY

The High Voltage Laboratory is in possession of accreditation issued by the Polish Centre for Accreditation (Accreditation Certificate of Testing Laboratory No AB 272) concerning following tests:

- Insulators and insulator strings
 - lightning and switching impulse tests
 - power frequency voltage 50 Hz tests
 - radio interference measurements
- Distribution substations
 - lightning and switching impulse tests
 - power frequency voltage 50 Hz tests
 - radio interference measurements
- Circuit breakers, disconnectors
 - lightning and switching impulse tests
 - power frequency voltage 50 Hz tests
 - radio interference measurements
- Insulators
 - lightning and switching impulse tests
 - power frequency voltage 50 Hz tests
 - radio interference measurements
- Current and voltage transformers
 - lightning and switching impulse tests
 - power frequency voltage 50 Hz tests
- Power transformers
 - lightning and switching impulse tests
 - power frequency voltage 50 Hz tests
- Lightning arresters and limiters
 - lightning and switching impulse tests
 - power frequency voltage 50 Hz tests
- Cables and cable fittings
 - lightning and switching impulse tests
 - power frequency voltage 50 Hz tests
- Line and station fittings
 - radio interference measurements
- Occupational safety equipment
 - power frequency voltage 50 Hz tests

306

2 TEST OBJECT DESCRIPTION

The tested object was instrument voltage transformer EMF-EI45 manufactured by ABB sp. z o.o. 04-713 Warszawa, Żegalska 1 St. (Fabryka Aparatury Wysokich i Średnich Napięć, 06-500 Przasnysz, Leszno 59 St.), with the following parameters:

Prototype 2 – EMF-EI45

Serial number: 1HSE8851773

- Highest voltage for equipment 145 kV
- Rated primary voltage 145000 / $\sqrt{3}$ V
- Insulation level 275 / 650 kV
- Frequency 50 Hz
- Temperature range -40 – +40 °C
- Total mass 295 kg




Fig. 1: Tested voltage transformer EMF-EI45

307

3 SCOPE OF TESTS AGREED UPON

Test plan for voltage instrument transformer type EMF-EI45 was consulted with the Customer. Tab. 1 includes the list of performed tests and requirements, which tested objects should comply with.

Tab. 1: Scope of tests of voltage instrument transformer

Item	Performed tests	Requirement
TYPE TESTS		
1	Impulse voltage withstand test on primary terminal	PN-EN/IEC 61869-3, p.7.2.3
SPECIAL TESTS		
2	Chopped impulse voltage test on primary terminal	PN-EN/IEC 61869-1, p.7.4.1

Determination of errors of transformer, performed to prove the positive results of consecutive tests, was carried out on the premises of Factory Laboratory of ABB Sp. z o.o. in the presence of a representative of the High Voltage Department of Institute of Power Engineering. Detailed results are presented in Annex 2.

Tests were carried out according to:

- IEC 61869-1:2007 „Instrument transformers - Part 1: General requirements” (equiv. with: PN-EN 61869-1:2009 “Przekładniki – Część 1: Wymagania ogólne”)
- IEC 61869-3:2011 „Instrument transformers - Part 3: Additional requirements for inductive voltage transformers” (equiv. with: PN-EN 61869-3:2011 “Przekładniki – Część 3: Wymagania szczególne dotyczące przekładników napięciowych indukcyjnych”)

4 TYPE TEST

4.1 Impulse voltage withstand test on primary terminal

4.1.1 Method of testing and acceptance criteria

According to IEC 61869-1 clause 7.4.1 lightning impulse test (for negative polarity) can be combined with chopped impulse voltage test. For positive polarity lightning impulse test was performed according to IEC 61869-1 clause 7.2.3 (15 impulse method).

It is considered that the instrument transformer passed the test with a positive result if analysis of the waveforms recorded during the test does not indicate failure of internal insulation of instrument transformer.

4.1.2 Test arrangement

Arrangement for testing with full lightning impulse 1,2/50 µs and chopped lightning impulse was based on Marx impulse generator made by HAEFELY. Voltage measurement was performed with impulse voltage measuring system Dr. Strauss TR-AS 200-14, in connection with a capacitive voltage divider (impulse peak value measuring uncertainty doesn't exceed 2% of the measured value for the confidence interval 95% and coverage factor k=2). Simplified diagram of the measurement system is shown in the Fig. 1.

[Handwritten signature]




Fig. 1: Simplified diagram of the lightning impulse measurement system (for one step of the generator);
 IG - impulse generator; VD - voltage divider; C_p , R_p , R_r - generator elements; CD - chopping device;
 IT - instrument transformer (general schematic representation); R_{1p} , R_{2p} - detection resistance

4.1.1.3 Test conditions

Test conditions for full lightning impulse 1,2/50 μ s test and chopped lightning impulse test (parameters of the measurement system, values of test voltages and sequence of impulses applications) are presented in Tab. 2 and Tab. 3. The influence of atmospheric condition on test voltage value was not taken into consideration.



Tab. 3: Values of test voltages and sequence of impulses applications

Full impulse test voltage	RW = 325 kV FW = 650 kV
Chopped impulse test voltage	CRW = 373,7 kV CFW = 747,5 kV
Sequence of impulses	Positive polarity 1 reduced full impulse (RW), 15 full impulses (FW). Negative polarity 1 reduced full impulse (RW), 1 full impulse (FW), 1 reduced chopped impulse (CRW), 2 chopped impulses (CFW), 14 full impulses (FW).
Registration	Transients of test voltage (channel 1) Current flowing through secondary winding 1a-1n (channel 2) Current flowing through primary winding screen E (channel 3)

4.1.1.4 Test results

Oscillograms registered during the tests don't indicate any failures of the transformers' insulation (Annex 3). Comparison of the accuracy verification before and after the lightning impulse test of the transformers don't indicate significant changes of the transformers' metrological characteristics (Annex 2).

TEST RESULT: POSITIVE

5 SPECIAL TESTS

5.1 Chopped impulse voltage withstand test on primary terminal

Chopped impulse test on the primary winding was combined with the negative polarity lightning impulse test. Detailed results of this test are presented in Section 4.1 and Annex 3 of this report.

TEST RESULT: POSITIVE

Tab. 2: Parameters of the lightning impulse measurement system

IMPULSE GENERATOR	
Number of steps	n - 6
General capacitance	C_p μ F - 0,125
Discharge resistance	R_c Ω - 534
Damping resistance	R_d Ω - 157
VOLTAGE DIVIDER	
HV unit capacitance	C_u' pF - ~1200
LV unit capacitance	C_u'' μ F - 1,103
Scale factor	ϕ_v - 927,0
DETECTION RESISTORS	
Detection resistance	R_{d1} Ω - 0,707
	R_{d2} Ω - 2,970